

United States Department of the Interior
Heritage Conservation and Recreation Service

For HCRS use only

received

date entered

National Register of Historic Places Inventory—Nomination Form

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Greenbelt Historic District

and/or common Old Greenbelt

2. Location

Just north of the intersections of the Baltimore-
street & number Washington Parkway, and the Capital Beltway not for publication

city, town Greenbelt vicinity of congressional district Fifth

state Maryland code 24 county Prince George's code

3. Classification

Category	Ownership	Status	Present Use	
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> building(s)	<input type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial	<input checked="" type="checkbox"/> park
<input type="checkbox"/> structure	<input checked="" type="checkbox"/> both	<input type="checkbox"/> work in progress	<input checked="" type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input checked="" type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input checked="" type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input checked="" type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
		<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property

name Multipel public and private

street & number

city, town vicinity of state

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse

street & number

city, town Upper Marlboro state Maryland 20870

6. Representation in Existing Surveys

title has this property been determined eligible? yes no

date federal state county local

depository for survey records

city, town state

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED.

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt Historic District
Prince George's County
Maryland

CONTINUATION SHEET

ITEM NUMBER

PAGE

15

ACREAGE AND BOUNDARY JUSTIFICATION

The Greenbelt Historic District covers 789.05 acres of land. The boundaries of this district are drawn so as to include those areas of the City of Greenbelt which directly relate to the establishment and expansion of the planned community between 1935 and 1941 when the district acquired significance and to exclude the more recently developed parcels and roadways while utilizing such lines of convenience as the city limits on the north; a major physical and visual barrier, the Baltimore-Washington Parkway, on the east; and property lines on the south and west.

Included in the Greenbelt Historic District are three discontinuous parcels to the west of the district proper. These parcels, described below, are included in the district because of their historical linkage to the period when the district achieved significance but are made discontinuous by major highway systems and recent development between them and the district proper. The discontinuous parcels are:

Greenbelt Junior High School (33.86 acres)

Bounded by Breezewood Drive on the north, Edmonston Road on the east, Greenbelt Road on the south, and Beltway Plaza on the west, this school was completed in 1938 as part of the original construction of Greenbelt and was situated about a mile from the commercial center so that it would be equidistant from both Greenbelt and the town of Berwyn Heights to the west.

Greenbelt City Cemetary (3.1 acres)

Located north of Ivy Land (extended) to the west of Maryland Route 201 and surrounded completely by private land, this cemetary was formed around an existing burial plot.

Indian Springs (a city park, 3 acres)

Indian Springs is south of Greenbelt Lake and is bordered on the north by the highway ramp leading from Kenilworth Avenue northbound to the Capital Beltway (I-95) southbound. It is surrounded on the other three sides by private land currently under development. The three springs are on a hillside shaded by trees. The springs purportedly were a meeting place for local Indians, thus the name Indian Springs. Originally a part of Greenbelt Lake Park, the springs parcel was separated from the park by construction of the Capital Beltway.

In addition to structures and their immediate surroundings, the Greenbelt Historic District also includes numerous municipal parks scattered among the built areas, the Greenbelt Lake Park which was developed in 1938 and contains 62.1 acres, and four parcels of undeveloped land in the northeast section totally 174.9 acres which is all that remains of the original "green belt" that once completely surrounded the

7. Description

PG: 67-4

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

Greenbelt is an incorporated city in Northern Prince George's County, Maryland. It is located at the intersection of I-95 (the Capital Beltway) and the Baltimore-Washington Parkway.

The town (city) charter was granted by the Maryland State Legislature in June, 1937, three months before the first residents moved in. Greenbelt was the first municipality in Maryland to have the council-manager form of government.

Originally conceived during the New Deal initiatives of the Roosevelt administration, the projects sought to create jobs as well as to demonstrate the applicability of certain garden-city planning techniques to a project designed for low-income residents. The late Rexford Guy Tugwell was the "father of Greenbelt" as director of the Resettlement Administration during the early years of the Roosevelt Presidency. Frederick Bigger was in charge of the planning staff for the green towns. Bigger "believed that each town should be a distinct experiment--that new ideas and new approaches should be given the maximum possible opportunity to develop."¹

Greenbelt's location along major roads, 13 miles from the nation's capital, has placed enormous pressures on the community to expand. Much of the original belt of green has given way to shopping centers, garden apartments, single family homes, and condominiums. The population of Greenbelt has grown from 3,000 in 1937 to 7,000 in 1950, to approximately 20,000 today.

THE PLANNING OF A GARDEN COMMUNITY

Before selecting the sites for the "greenbelt towns," the federal government conducted detailed studies of the social and economic growth, wages, labor practices, accessibility to employment, topography, fertility of soil, presence of wooded areas for parks and recreation, and availability of low-priced land.

The rolling farmland in the Washington suburbs ideally met all of these criteria. The building of historic Greenbelt took advantage of the natural topography in the form of a crescent-shaped plateau:

The town is formed in the shape of a graceful crescent set on a vast background of green. . . . the essential shape of the Greenbelt town plan was indicated by nature. Here, as in many other great plans, the planners' job was primarily to discover, not invent. . . . the planners of Greenbelt revealed the potentialities of the great curves as a beautiful place for good living.²

Houses encircle the center, where stores, the post office, and community building/school are located; the apartment buildings form an inner circle. At a lower level, in a natural bowl, is the athletic field and the re-

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED.

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's

CONTINUATION SHEET Maryland

ITEM NUMBER 7

PAGE 2

DESCRIPTION, continued

center (the city's recreation department was the first established in Maryland).

The government initially constructed a total of 574 rowhouse units, 306 apartment units, and five detached homes built as experiments in pre-fabrication techniques. Ten houses were also built by a private developer in a small subdivision called "Parkbelt" located on Forest Way. The government purchased a total of 3,371 acres for the community and surrounding greenbelt.

In 1941 the federal government constructed 1,000 frame homes for workers engaged in the national defense effort. Greenbelt's "defense homes" were one of 43 such housing projects built throughout the United States to relieve the acute shortage of housing for persons engaged in war-time activities. The frame houses are located mainly to the north of the original planned community, and their interior design as well as the layout of the rows was intended to incorporate many of the plan features of the original homes. However, due to the need to construct housing quickly and at low cost, the defense homes are not as well constructed or as well planned as the original community.

The homes, arranged in superblocks to reduce the number of streets, sidewalks, and utility lines, are clustered in rows in housing "courts", set back from the main streets. From two to ten homes in a row were constructed, all with what is called a "garden side" and a "service side." The service side was planned for access to parking (most courts have off-street parking lots or garages), and for deliveries and garbage pick-up, while the garden side was designed to provide each family with a spacious and safe play and green area. Many homes face, on the garden side, common areas or small city parks. In some cases, the garden side faces woods.

Greenbelt's internal walkway system and pedestrian underpasses (the only ones to be constructed in the three greenbelt towns) are credited with separating pedestrian and vehicular traffic. Three pedestrian and underpasses cross Crescent Road and lead to the Commercial Center and the city's outstanding safety record is in part accredited to the use of these.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's

CONTINUATION SHEET Maryland ITEM NUMBER 7 PAGE 3

DESCRIPTION, continued

ORIGINAL APARTMENTS

Constructed at the same time as the rest of Old Greenbelt were twelve three-story apartment buildings. Designed for small families and single persons, the apartments were built near the Center and offered easy access to Center mall services and activities. In summary, apartment construction was as follows:

<u>Buildings</u>	<u>Type</u>	<u>Units</u>
1	48 family -- 3-story apartment	48
1	36 family -- 3-story apartment	36
2	21 family -- 3-story apartment	24
2	18 family -- 3-story apartment	36
3	24 family -- 3-story apartment	72
3	30 family -- 3-story apartment	90

Total: 306

The apartment buildings were built in the same manner and used the same materials as the cinder block homes. Today, they are owned by private rental companies.

THE COMMERCIAL CENTER

Central to the planned community is the Commercial Center. Located within one-half mile of the original dwellings, the Greenbelt Commercial Center is one of the oldest planned integrated shopping centers in the country. It is a neighborhood shopping center because its location off the main roads is unlikely to draw non-neighborhood business. Three parking lots and a service road along the front provide vehicular access to the Center. The Commercial Center is divided by an open air mall dominated by a mother and child statue sculpted in sandstone by Lenore Thomas of Accokeek, Maryland, for the Resettlement Administration. She also created the reliefs depicting scenes from the Preamble to the Constitution across the front wall of the Center Elementary School.

The Commercial Center consists of five buildings containing stores and offices. In earlier days, the city offices, and police and fire stations were also housed here. When the Center was opened in 1937, it was intended to offer residents complete shopping and service

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's

CONTINUATION SHEET Maryland ITEM NUMBER 7 PAGE 4

DESCRIPTION, continued

facilities, including a grocery store, dry cleaners, barber and beauty shops, bank, and post office. For the first few years, there was even a furniture store where residents could purchase specially made heavy-duty furniture; an entire house could be outfitted for \$300-\$400.

The buildings in the Commercial Center are now privately owned.

CENTER SCHOOL

The two-story community building (now Greenbelt Center Elementary School) was an integral part of the planned community, and first opened its doors in October 1937 with seven teachers and 24 students. The building is centrally located, within a half-mile of all the original homes, and can be reached directly by a system of paths and walkway--underpasses. Built as a combination school-community building, the facility contained 12 classrooms as well as a music room, arts and crafts workshop, home making room, health room, social room, and a large combined gymnasium-auditorium. Architecturally, Center School shares the simple functional design which dominates the planned community as a whole.

Until July 1, 1971, the building also housed a library, one of the most active in Prince George's County. Following much petitioning by Greenbelt citizens, a new library building was constructed by the County on land next to the school in 1971.

The building was owned by the government and loaned to the county as an elementary school. In 1948 the town leased it from the Public Housing Department for \$1 per year, and in turn received sufficient funds to operate it. In 1953 the building was dedicated by the government to the City of Greenbelt. In 1959 the Community Building was sold to the Prince George's County Board of Education for \$260,000.

In its early years, the Community Building housed the churches on Sunday and provided recreational facilities during the week. Local organizations met in the combination auditorium and gymnasium. Classrooms were used for adult education and vocational training in the evening.

It (the school) was to become one of our best-loved buildings, for it was here that all segments of the citizenry were to meet, discuss their mutual problems, worship, study and play.³

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

Greenbelt
Prince George's

CONTINUATION SHEET Maryland ITEM NUMBER 7 PAGE 5

DESCRIPTION, continued

NORTH END ELEMENTARY SCHOOL

The North End Elementary School was constructed to relieve the congestion in the Center School caused by the completion of the 1,000 frame "defense homes" in 1941-1942. Until the additional homes were constructed, the total number of children attending Center School averaged around 400. In 1943, after the new homes were constructed, attendance increased to 785 and the school had to go on double sessions. The two-story building features a simple design and contained ten classrooms, a kindergarten room, kitchen, infirmary, offices, and an auditorium.

JUNIOR HIGH SCHOOL

Originally a junior-senior high school, the structure was begun in the spring of 1937 and completed some 10 months later at a cost of \$142,000. The school was designed to serve students from the town of Berwyn Heights, as well, and was placed on the western edge of Greenbelt, about 1.5 miles from Center Elementary School. A gravel footpath led from Greenbelt through the woods to the school. The path crossed Edmonston Road, the only road separating the school from original Greenbelt, by means of an underpass. This route was absolutely free from traffic hazards.

The building is basic in design due to a lack of funds at that time. It contains classrooms, a science room, typing room, study room, music room, and a lunch room, among others.

In 1949 the County Board of Education purchased the building and land. The last senior class was graduated in 1951; the school was then converted to a junior-high school.

GREENBELT LAKE

In 1935, before home construction began, the federal government began construction of Greenbelt Lake to cover 23 acres of swamp land. Located to the west of the original town, the project took 200 men a year to complete, at a total cost of \$75,000. The lake and its shore line are now a city park.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's
Maryland

CONTINUATION SHEET ITEM NUMBER 7 PAGE 6

DESCRIPTION, continued

The swamp was the most heavily wooded spot in the area, with trees averaging 100 feet in height and 30 inches in diameter. These were pulled out by the roots and the stump piles mounted up as high as houses. They burned for two months or more. Some of the logs were used in construction work; the rest were turned over to the county relief board.⁴

It took about one year for the lake to fill, although it is fed by two streams and innumerable springs along the banks. The overflow empties into a stream that flows to Indian Creek, a tributary of which flows into the Anacostia River, eventually reaching the Potomac.

On November 13, 1936, President Franklin D. Roosevelt placed the first fish into the lake. Since that time, it has been stocked by the State of Maryland. Several varieties of wild and domestic ducks also make their home at the lake.

Fishing and boating are premitted at the lake. It is also a popular place for joggers, walkers, bicyclists, and picknickers. The annual Fourth of July fireworks display attracts thousands of visitors, who site on the bank and watch the colorful sight. In winter, ice skating is a favorite past-time, if the weather has been cold enough.

INDIAN SPRINGS

South of Greenbelt Lake is Indian Springs. It used to be accessible by walking across the dam at the lake, and then following a woodland trail between clumps of mountain laurel and wild azalea. The three springs are in a large open clearing, shaded by tulip poplars. With construction of the Capital Beltway, the Springs became separated from the Lake Park.

Above Indian Springs is the Walker family burial ground. Isaac Walker was a colonel in the American Revolution and is buried here. His son, who was born here, Colonel Samuel Hamilton Walker, was a hero of the Texas Rangers in the Mexican-American War and is also noted for assisting Samuel Colt in the perfection of the Colt revolver.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's
Maryland

CONTINUATION SHEET ITEM NUMBER 7 PAGE 7

DESCRIPTION, continued

PARCELS 1, 2, 3 and 4

These are four parcels of land on the eastern fringe of the City, currently owned by private developers, which are part of the original "green belt" that once surrounded the city. The total acreages of the parcels are as follows:

Parcel 1		155.5 acres
City park land	42.30 acres	
Undeveloped private parcels	103.24 acres	
Undeveloped Prince George's County land	10.00 acres	
Parcel 2		81.0 acres
Prince George's County land	61.40 acres	
City land	9.95 acres	
Undeveloped private land	9.75 acres	
Parcel 3 - Undeveloped private land		2.9 acres
Parcel 4 - Undeveloped private land		7.4 acres

THE OPENING OF GREENBELT

In the 30s, the idea of a city protected from over-crowding, sprawling, and haphazard development built by the federal government for low-income people was attacked as "radical" and "socialistic". Indeed, after the towns were built, thousands of tourists flocked to them to gawk at the residents, who were depicted as being rigidly controlled because of the many rules and regulations imposed by the federal administrators.⁵

Tagged "Tugwelltowns" by the press and Congress, they were portrayed as part of a "sinister plot to impose foreign, socialist, or communist ways of life on the American people or at least they forced unwanted regimentation by being planned."⁶

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED.

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's
Maryland

CONTINUATION SHEET ITEM NUMBER 7 PAGE 8

DESCRIPTION, continued

The first residents were carefully selected. They had to meet income requirements (\$800-\$2,200 annual), exhibit neat personal habits, present two references from previous landlords, undergo a physical examination, and demonstrate their need for rental housing in a new environment. One factor that eliminated many prospective residents was that the wives of employed husbands could not work. Attempts were made to reflect the religious ratio of Washington, D.C.: 63% Protestant, 30% Catholic, and 7% Jewish. One third were government employees.

Five families moved in on opening day. One year later, all 885 dwellings were occupied. By the end of 1937 Greenbelt was the second largest municipality in Prince George's County. By 1941 it was the largest. Today Greenbelt ranks third.

The residents thought of themselves as pioneers. The following article appeared in the first issue of the Cooperator (Greenbelt's weekly newspaper, begun in 1937, and still being published by a volunteer staff under the banner The Greenbelt News Review).

We did not arrive in Greenbelt after long, tiresome miles by covered wagon; nor did we find this place by chance. We were not the first to gaze upon this spot of ground; nor did we cut down trees in order to build homes. Nor is it necessary to clear the land to plant our crops that we may quench our thirst.

Yes, we are pioneers--of a new way of living. We are the sculptors of a new way of living. We are the sculptors handling the soft, yielding clay of a new community. What form shall we mold of it?

This project has given most of us an opportunity we'd never anticipated. We are in the process of creating homes! Our families and our children will live under laws of our own making. Only in our fondest and most youthful dreams have we imagined such a chance. What will we make of it?

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's
Maryland

CONTINUATION SHEET ITEM NUMBER 7 PAGE 9

DESCRIPTION, continued

Let us make good laws--wise laws, and not too many of them. Let us keep ourselves, our community, our city government, our ideals, as clean as our new, windswept roofs. Let us continue ourselves and the management of our Greenbelt in such a way as to deserve the pride with which all America will be looking on.⁷

As strangers to each other in a completely new environment, new social patterns and group emerged. Greenbelt is unique in that it is the only one of the three "green" towns to have preserved the established cooperative concepts, enterprises, and organizations. Greenbelt Consumer Services, one of the largest consumer cooperatives on the east coast, developed here. It operated bus lines and a variety of stores in the shopping mall. Today GCS has consolidated to include food, furniture, and a gas station. A cooperative nursery school and the housing cooperative symbolize the Greenbelt philosophy for community living begun by those "pioneers".

ARCHITECTURAL DESCRIPTION

When the new towns were built, architecture was secondary to the concept of a planned community. Each of the new towns had its own set of architects and planners. Hale Walker, Harold Bursley, and Reginald Wadsworth designed Greenbelt and were among those who reacted negatively to the ornamentation of the styles of the 30s. Walker, Bursley, and Wadsworth designed buildings in what was then called "New Tradition" and now is labeled the "International Style" of Walter Gropius and the Bauhaus.

The original masonry or block units are flat-roofed cinderblock homes, painted white with window sash and bands of brick between windows painted green.

The brick veneer homes have gable roofs laid with slate; soon after construction, these were also painted white with green trim. For many years, no other colors were permitted. Green and white still represent the city and are the colors of the city's flag.

The interiors of the block homes are furred inside the masonry and insulated with plaster board covered with aluminium foil on the outer surface and plastered on the inner. Floor construction is of rein-

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's

CONTINUATION SHEET Maryland ITEM NUMBER 7 PAGE 10

DESCRIPTION, continued

forced concrete on which asphalt tile is laid with mastic. The roof is covered with four-ply roofing laid in pitch and surfaced with slag or gravel. Windows are steel casements with wood doors and trim.

The brick homes are constructed of brick veneer with diagonal sheathing and rock wool insulation between the studs. The tenor is finished with plaster on metal lath. The lower floor is reinforced concrete slab, while upper floors are of wood. The concrete floor is covered with asphalt tile. Thin layers of slate are laid over wood sheathing to form the roof. Shrubbery, particularly private hedges, were part of each home's landscape design.

A typical brick or block home has a living room, dining room, and kitchen on the first floor, and 2-3 bedrooms upstairs. There are 16 one-bedroom homes, called honeymoon cottages, on the first floor ends of some masonry rows. Twenty-two masonry homes have finished basements. Some of these have asbestos shingles covering the masonry surface.

The "defense" homes were built with one, two, or three bedrooms. Kitchens face the service side while living rooms face woods or parks. Asbestos shingles cover the exterior of the homes. Wood flooring and dry wall were used in the interiors and wood frame push-up windows throughout. Because of the speed with which they were constructed during World War II and the lack of materials and funds committed to the project, the frame units have galvanized steel piping instead of the copper used in the masonry, and lack the sound insulation and landscaping features of the original homes.

One bedroom frame homes are located on the first and second floor ends of some buildings; eight buildings are completely composed of one-bedroom units on each of the two floors, with 8 to 12 units in a row. In addition 104 units of two-story apartments were constructed.

The Greenbelt Historic District contains approximately 360 buildings of which nearly 90% date from the 1935-1941 period when the district achieved its major significance.

PG:67-4

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's

CONTINUATION SHEET Maryland ITEM NUMBER 7 PAGE 11

DESCRIPTION, continued

EXPERIMENTAL HOUSES

As an experiment in prefabricated housing, the Suburban Division of the Resettlement Administration included in Greenbelt five experimental freestanding houses, which were located in the northern area of the city.

These houses demonstrated certain possibilities of using plywood as a structural material. The dead weight was greatly reduced, and there were fewer parts involved, since the basic construction unit was a large plywood panel, constructed earlier and brought to the site whole. The plywood was glued to the studs and joists to form simple boxlike structural units in which the plywood provides most of the strength and stiffness.

All five units are one-story, two-bedroom structures with sample plans indicated below. They were constructed on an area of about 40,000 square feet for a total cost of \$6,600 or an average cost of \$1,320 per house. They contain the following total area measurements:

<u>House</u>	<u>Total Area (Sq. Ft.)</u>
A	994
B	994
C	999
D	658
E	716

A WORD ON REHABILITATION

Because the original housing is now 42 years old and the remainder is 38 years old, Greenbelt Homes, Inc., the owner of most of the residential property, is now in the planning stages for a comprehensive rehabilitation program. First priority in this program is directed towards energy conservation as these houses and their heating systems are energy inefficient. Greater use of electrical appliances over the past 40 years and advanced age has resulted in the need for considerable electrical wiring work to be done. A thorough examination of wooden structures is required to determine the extent of damage from age, rot, termites, etc. To do this, the exterior asbestos shingle siding needs to be removed.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

PG:67-4

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

Greenbelt
Prince George's

CONTINUATION SHEET Maryland ITEM NUMBER 7 PAGE 12

DESCRIPTION, continued

In undertaking rehabilitation, the cooperative is ever mindful of the need to achieve results that will assure the continuation of these buildings as moderate priced houses. Thus, consideration is being given to ways and means of reducing maintenance costs as well as replacing deteriorated or inadequate fixtures and structural sections.

While most rehabilitation work will be within the buildings, new windows and exterior siding are being considered for many of the buildings. New window units will have built-in storm windows and provide tight seals.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's
Maryland

CONTINUATION SHEET

ITEM NUMBER 7

PAGE 13

FOOTNOTES

1

Clarence Stein, Toward New Towns for America (Cambridge, Mass.: MIT Press, 1957), p. 120.

2

Ibid., p. 127.

3

Henry Churchill, "America's Towns Planning Begins," The New Republic, June 12, 1936.

4

Greenbelt, 25th Anniversary, 1937-1962 (Brochure prepared under the auspices of the Silver Anniversary Committee, from material provided by the Greenbelt News Review, and other local government organizations), p. 42.

5

Joseph Arnold, The New Deal in the Suburbs, A History of the Greenbelt Town Program, 1935-1954. Ohio State University Press. 1971. pp.196-197.

6

Ibid., p. 197.

7

Greenbelt, 25th Anniversary, p. 12

8. Significance

PG: 67-4

Period	Areas of Significance—Check and justify below					
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input checked="" type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion		
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian		
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater		
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input checked="" type="checkbox"/> politics/government	<input type="checkbox"/> transportation		
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)		

Specific dates 1935-1941 **Builder/Architect** Reginald J. Wadsworth and Douglas D. Ellington, principal architects
Harold Bursley, engineering designer

Statement of Significance (in one paragraph)

SIGNIFICANCE

The Greenbelt Historic District is the original developed section of the City of Greenbelt which was established and expanded between 1935 and 1941 as one of three "green towns" founded by the United States government under the New Deal as an attempt to solve social and economic problems confronting the nation. The three towns are Greenbelt, Maryland; Greenhills, Ohio (near Cincinnati); and Greendale, Wisconsin (near Milwaukee). A fourth community, Greenbrook, New Jersey, never passed the planning stage. Greenbelt differs from the other "green towns" in that the predominate type of building originally erected is the multi-storied apartment house whereas the duplex is the predominate type originally used in the other communities. Of the three towns, Greenbelt is the only one to still retain many of the original features such as the buildings and sections of the surrounding "greenbelt." Greenbelt also continues the concept of community responsibility as the majority of the housing is owned by a cooperative.

HISTORY AND SUPPORT

The idea of a planned "green town" can be traced to the late 19th century in Great Britain when Ebenezer Howard detailed such planning ideas in a book entitled Garden Cities of Tomorrow published in 1898. Howard presented the idea of a "garden town" surrounded by large open spaces maintained by the residents. Two such cities were built in England in the early twentieth century. In the United States a private developer began construction in 1928 of Radburn, New Jersey, a garden town outside New York City, but the Great Depression halted construction in the early 1930s. Radburn was considered at the time to be the model American "green town."

Although it smothered Radburn, the Depression was, in many ways, responsible for the creation of the New Deal efforts that built Greenbelt and the other "green towns" in the late 1930s. In 1935 the director of the Rural Resettlement Administration, later the Division of Farm Security in the Department of Agriculture, was the late Rexford Guy Tugwell, a disciple of Howard's garden city philosophy. He convinced President Roosevelt that the basic planning concepts of the green town were valid and plans were laid for four "green towns" as a method of combatting unemployment and to move low-income families out of overcrowded urban areas while keeping them close to opportunities in the city.

See continuation sheet number 14

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt
Prince George's County
Maryland

CONTINUATION SHEET

ITEM NUMBER

8

PAGE 14

HISTORY, Continued

Of the three towns that were finally built, Greenbelt carried out the Radburn idea more than the other two. Low and moderate income families predominated. The rowhouse residents formed a housing cooperative (an idea not before employed in green towns) in 1953 when the federal government divested itself of its housing interests. That cooperative thrives today, as do many of the ancillary cooperative institutions, including the newspaper, nursery school, garden club, baby-sitting club, and Greenbelt Consumer Services, which runs the large grocery store in the Center.

Approximately 40 of the original residents still live in Greenbelt. Many children, grandchildren, and other relatives of original settlers chose to make Greenbelt their home.

Greenbelt has successfully demonstrated the neighborhood concept radiating into a garden city. Two recently completed planned communities-- Reston, Virginia and Columbia, Maryland-- have expanded on the successful elements of Greenbelt.

Because Greenbelt was planned as a viable, living community, it should change with the times and not become solely a representative of a former time. However, those planning concepts which made Greenbelt significant when it was first built and which remain viable today should be preserved for the future. These planning concepts include:

- * Moderate priced housing in a garden or park setting;
- * Cluster housing;
- * Superblocks with interior green space;
- * Interior sidewalk system which crosses under major streets to underpasses;
- * A central core of commercial, civic, recreational, athletic, and park facilities;
- * A surrounding belt of open space.

NOTE: Further history can be found in the description.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED.

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

Greenbelt Historic District
Prince George's County
Maryland

CONTINUATION SHEET

ITEM NUMBER

PAGE 16

ACREAGE AND BOUNDARY JUSTIFICATION conintued

city. These undeveloped parcels, known as Parcels 1, 2, 3, and 4 and privately owned, are considered as part of the district because they reflect their original purpose of being a natural buffer zone encircling the community.

PHOTOGRAPH EXPLANATORY NOTE

The photographs submitted as part of the documentation for this application, though varied in date with some more than four years in age, do visually represent the Greenbelt Historic District as it appears as of the date of this application.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

PG:67-4

FOR HCRS USE ONLY
RECEIVED
DATE ENTERED.

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

Greenbelt Historic District
Prince George's County
Maryland

CONTINUATION SHEET

ITEM NUMBER 9 PAGE 17

SECTION 9: MAJOR BIBLIOGRAPHICAL REFERENCES

Arnold, Joseph. The New Deal in the Suburbs: A History of the Greenbelt Town Program, 1935-1954. Ohio State University Press, 1971.

Churchill, Henry. "America's Towns Planning Begins," The New Republic, June 12, 1936.

Greenbelt, 25th Anniversary, 1937-1962)brochure prepared under the auspices of the Silver Anniversary Committee from material provided by the Greenbelt News Review and other local organizations)

Stein, Clarence. Toward New Towns for America. Cambridge, Mass.: MIT Press, 1957.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

Greenbelt Historic District
Prince George's County

CONTINUATION SHEET Maryland ITEM NUMBER 10 PAGE 18

GEOGRAPHICAL DATA

BELTSVILLE QUADRANGLE

Greenbelt Historic District

- D. 18/335610/4318530
- E. 18/337210/4319840

Greenbelt Cemetery

- A. 18/336100/4319340
- B. 18/336060/4319200
- C. 18/335940/4319270
- D. 18/335990/4319390

Greenbelt Junior High School

- D. 18/335160/4318360

LANHAM QUADRANGLE--No UTM point(s)

LAUREL QUADRANGLE

Greenbelt Historic District

- A. 18/338910/4319830
- B. 18/338320/4318300

WASHINGTON EAST QUADRANGLE

Greenbelt Historic District

- C. 18/337300/4317770

Greenbelt Junior High School

- A. 18/335440/4318220
- B. 18/335310/4317860
- C. 18/334900/4317960

City Park

- A. 18/336120/4318200
- B. 18/335820/4318190
- C. 18/335890/4318390

9. Major Bibliographical References

PG:67-4

see continuation page 17

10. Geographical Data

Acreage of nominated property 789.05 acres
 Quadrangle name Washington East, Beltsville,
Lanham and Laurel Quadrangle Maps Quadrangle scale 1:24000
 UMT References (SEE CONTINUATION SHEET #18.)

A	Zone	Easting	Northing	B	Zone	Easting	Northing
C				D			
E				F			
G				H			

Verbal boundary description and justification

The boundaries of the Greenbelt Historic District are indicated by the wide red line drawn on the accompanying maps labeled "City of Greenbelt/Prince George's County/ Maryland" drawn to a scale of 1"=500' and prepared in 1964 and revised in 1980.

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
state	code	county	code

11. Form Prepared By

name/title Thomas Hauenstein
 organization City of Greenbelt date November 1979
 street & number 25 Crescent Road telephone (301) 474-8000
 city or town Greenbelt state Maryland 20770

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature *[Signature]* date 5-29-80

title STATE HISTORIC PRESERVATION OFFICER date

For HCRS use only
I hereby certify that this property is included in the National Register

keeper of the National Register date

Attest: date

Chief of Registration date



PG. 67-4
Greenbelt
Historic
District

RESEARCH CENTER

GREENBELT

GREENBELT

GREENBELT

GREENBELT

PARK

GODDARD
SPACE FLIGHT CENTER
(NASA)
LAURENCE
LANHAM

GODDARD
SPACE FLIGHT CENTER
(NASA)

Schom Hills
Rec. Center

Magnolia
Springs

Hynesboro

Lanham



NAME GREEN BELT, Md HOUSING

PG:67-4

LOCATION GREEN BELT Rd

FACADE S

PHOTO TAKEN 10/25/74 MDWVER



NAME GREENBELT, Md.

PG:67-4

LOCATION GREENBELT, Rd. GREENBELT, Md.


FACADE SW

PHOTO TAKEN 10/25/74 M DWYER



PE:67-4

- 1) GREENBELT HISTORIC DISTRICT
- 2) PRINCE GEORGE'S COUNTY, MARYLAND
- 3) DON VOLK
- 4) ~~12-V~~
MTU, 1967
- 5) 12-V RIDGE ROAD, GREENBELT, MARYLAND
- 6) VIEW OF CENTER MTU



- 1) GREENBELT HISTORIC DISTRICT
- 2) PRINCE GEORGE'S COUNTY, MARYLAND
- 3) DON VOLK
- 4) AUGUST, 1978
- 5) 12-V RIDGE ROAD, GREENBELT, MARYLAND
- 6) WINDOW DETAIL, BRICK HOME

PG:67-4

JULY 78



PROMOTE THE GENERAL WELFARE

AMS
72 1) GREENBELT HISTORIC DISTRICT

2) PRINCE GEORGE'S COUNTY, MARYLAND

3) DON VOLK

4) AUGUST, 1978

5) 12-V RIDGE ROAD

6) FRIEZE ON FRONT OF CENTER ELEMENTARY SCHOOL

PG: 67-4


**GREENBELT
ELEMENTARY**



- 1) GREENBELT HISTORIC DISTRICT
- 2) PRINCE GEORGE'S COUNTY, MARYLAND
- 3) DON VOLK
- 4) JULY, 1978
- 5) 12-V RIDGE ROAD, GREENBELT, MARYLAND
- 6) GREENBELT CENTER ELEMENTARY SCHOOL

PG: 67-4

JULY 1978



1/8" = 1' SCALE
 1/4" = 1' SCALE
 1/2" = 1' SCALE
 1" = 1' SCALE
 2" = 1' SCALE
 4" = 1' SCALE
 8" = 1' SCALE
 16" = 1' SCALE
 32" = 1' SCALE
 64" = 1' SCALE
 128" = 1' SCALE
 256" = 1' SCALE
 512" = 1' SCALE
 1024" = 1' SCALE
 2048" = 1' SCALE
 4096" = 1' SCALE
 8192" = 1' SCALE
 16384" = 1' SCALE
 32768" = 1' SCALE
 65536" = 1' SCALE
 131072" = 1' SCALE
 262144" = 1' SCALE
 524288" = 1' SCALE
 1048576" = 1' SCALE
 2097152" = 1' SCALE
 4194304" = 1' SCALE
 8388608" = 1' SCALE
 16777216" = 1' SCALE
 33554432" = 1' SCALE
 67108864" = 1' SCALE
 134217728" = 1' SCALE
 268435456" = 1' SCALE
 536870912" = 1' SCALE
 1073741824" = 1' SCALE
 2147483648" = 1' SCALE
 4294967296" = 1' SCALE
 8589934592" = 1' SCALE
 17179869184" = 1' SCALE
 34359738368" = 1' SCALE
 68719476736" = 1' SCALE
 137438953472" = 1' SCALE
 274877906944" = 1' SCALE
 549755813888" = 1' SCALE
 1099511627776" = 1' SCALE
 2199023255552" = 1' SCALE
 4398046511104" = 1' SCALE
 8796093022208" = 1' SCALE
 17592186044416" = 1' SCALE
 35184372088832" = 1' SCALE
 70368744177664" = 1' SCALE
 140737488355328" = 1' SCALE
 281474976710656" = 1' SCALE
 562949953421312" = 1' SCALE
 1125899906842624" = 1' SCALE
 2251799813685248" = 1' SCALE
 4503599627370496" = 1' SCALE
 9007199254740992" = 1' SCALE
 18014398509481984" = 1' SCALE
 36028797018963968" = 1' SCALE
 72057594037927936" = 1' SCALE
 144115188075855872" = 1' SCALE
 288230376151711744" = 1' SCALE
 576460752303423488" = 1' SCALE
 1152921504606846976" = 1' SCALE
 2305843009213693952" = 1' SCALE
 4611686018427387904" = 1' SCALE
 9223372036854775808" = 1' SCALE
 18446744073709551616" = 1' SCALE
 36893488147419103232" = 1' SCALE
 73786976294838206464" = 1' SCALE
 147573952589676412928" = 1' SCALE
 295147905179352825856" = 1' SCALE
 590295810358705651712" = 1' SCALE
 1180591620717411303424" = 1' SCALE
 2361183241434822606848" = 1' SCALE
 4722366482869645213696" = 1' SCALE
 9444732965739290427392" = 1' SCALE
 18889465931478580854784" = 1' SCALE
 37778931862957161709568" = 1' SCALE
 75557863725914323419136" = 1' SCALE
 151115727451828646838272" = 1' SCALE
 302231454903657293676544" = 1' SCALE
 604462909807314587353088" = 1' SCALE
 1208925819614629174706176" = 1' SCALE
 2417851639229258349412352" = 1' SCALE
 4835703278458516698824704" = 1' SCALE
 9671406556917033397649408" = 1' SCALE
 19342813113834066795298816" = 1' SCALE
 38685626227668133590597632" = 1' SCALE
 77371252455336267181195264" = 1' SCALE
 154742504910672534362390528" = 1' SCALE
 309485009821345068724781056" = 1' SCALE
 618970019642690137449562112" = 1' SCALE
 1237940039285380274899124224" = 1' SCALE
 2475880078570760549798248448" = 1' SCALE
 4951760157141521099596496896" = 1' SCALE
 9903520314283042199192993792" = 1' SCALE
 19807040628566084398385987584" = 1' SCALE
 39614081257132168796771975168" = 1' SCALE
 79228162514264337593543950336" = 1' SCALE
 158456325028528675187087900672" = 1' SCALE
 316912650057057350374175801344" = 1' SCALE
 633825300114114700748351602688" = 1' SCALE
 1267650600228229401496703205376" = 1' SCALE
 2535301200456458802993406410752" = 1' SCALE
 5070602400912917605986812821504" = 1' SCALE
 10141204801825835211973625643008" = 1' SCALE
 20282409603651670423947251286016" = 1' SCALE
 40564819207303340847894502572032" = 1' SCALE
 81129638414606681695789005144064" = 1' SCALE
 162259276829213363391578010288128" = 1' SCALE
 324518553658426726783156020576256" = 1' SCALE
 649037107316853453566312041152512" = 1' SCALE
 1298074214633706907132624082305024" = 1' SCALE
 2596148429267413814265248164610048" = 1' SCALE
 5192296858534827628530496329220096" = 1' SCALE
 10384593717069655257060992658440192" = 1' SCALE
 20769187434139310514121985316880384" = 1' SCALE
 41538374868278621028243970633760768" = 1' SCALE
 83076749736557242056487941267521536" = 1' SCALE
 166153499473114484112975882535043072" = 1' SCALE
 332306998946228968225951765070086144" = 1' SCALE
 664613997892457936451903530140172288" = 1' SCALE
 1329227995784915872903807060280344576" = 1' SCALE
 2658455991569831745807614120560689152" = 1' SCALE
 5316911983139663491615228241121378304" = 1' SCALE
 10633823966279326983230456482242756608" = 1' SCALE
 21267647932558653966460912964485513216" = 1' SCALE
 42535295865117307932921825928971026432" = 1' SCALE
 85070591730234615865843651857942052864" = 1' SCALE
 170141183460469231731687303715884105728" = 1' SCALE
 340282366920938463463374607431768211456" = 1' SCALE
 680564733841876926926749214863536422912" = 1' SCALE
 1361129467683753853853498429727072845824" = 1' SCALE
 272225893536750770770699685945415169152" = 1' SCALE
 544451787073501541541399371890830338304" = 1' SCALE
 1088903574147003083082798743781660676608" = 1' SCALE
 2177807148294006166165597487563321353216" = 1' SCALE
 4355614296588012332331194975126642706432" = 1' SCALE
 8711228593176024664662389950253285412864" = 1' SCALE
 17422457186352049329324779900506568825728" = 1' SCALE
 34844914372704098658649559801013137651456" = 1' SCALE
 69689828745408197317299119602026275302912" = 1' SCALE
 139379657490816394634598239204052550605824" = 1' SCALE
 278759314981632789269196478408105101211648" = 1' SCALE
 557518629963265578538392956816210202423296" = 1' SCALE
 1115037259926531157076785913632420404846592" = 1' SCALE
 2230074519853062314153571827264840809693184" = 1' SCALE
 4460149039706124628307143654529681619386368" = 1' SCALE
 8920298079412249256614287309059363238772736" = 1' SCALE
 17840596158824498513228574618118726477545472" = 1' SCALE
 35681192317648997026457149236237452955090944" = 1' SCALE
 71362384635297994052914298472474905910181888" = 1' SCALE
 142724769270595988105828596944949811820363776" = 1' SCALE
 285449538541191976211657193889899637640727552" = 1' SCALE
 57089907708238395242331438777979927528145504" = 1' SCALE
 114179815416476790484662877555959855056291008" = 1' SCALE
 228359630832953580969325755111919710112582016" = 1' SCALE
 456719261665907161938651510223839420225164032" = 1' SCALE
 913438523331814323877303020447678840450328064" = 1' SCALE
 1826877046663628647754606040895357680900656128" = 1' SCALE
 3653754093327257295509212081790715361801312256" = 1' SCALE
 7307508186654514591018424163581430723602624512" = 1' SCALE
 1461501637330902918203684832716286146720529024" = 1' SCALE
 2923003274661805836407369665432572293441058048" = 1' SCALE
 5846006549323611672814739330865144586882116096" = 1' SCALE
 11692013098647223345629478661730289173764232192" = 1' SCALE
 23384026197294446691258957323460578347528464384" = 1' SCALE
 46768052394588893382517914646921156695056928768" = 1' SCALE
 93536104789177786765035829293842313390113857536" = 1' SCALE
 187072209578355573530071658587684626780227715072" = 1' SCALE
 374144419156711147060143317175369253560455430144" = 1' SCALE
 748288838313422294120286634350738507120910860288" = 1' SCALE
 1496577676626844588240573268701477014241817200576" = 1' SCALE
 2993155353253689176481146537402954028483634401152" = 1' SCALE
 5986310706507378352962293074805908056967268802304" = 1' SCALE
 11972621413014756705924586149611816113934537604608" = 1' SCALE
 23945242826029513411849172299223632227869075209216" = 1' SCALE
 47890485652059026823698344598447264455738150418432" = 1' SCALE
 95780971304118053647396689196894528911476300836864" = 1' SCALE
 191561942608236107294793378393789057822952601673728" = 1' SCALE
 383123885216472214589586756787578115645905203347456" = 1' SCALE
 766247770432944429179173513575156231291810406694912" = 1' SCALE
 1532495540865888858358347027150312462583620813389824" = 1' SCALE
 3064991081731777716716694054300624925167241626779648" = 1' SCALE
 6129982163463555433433388108601249850334483253559296" = 1' SCALE
 12259964326927110866866776217202499700668965107118592" = 1' SCALE
 24519928653854221733733552434404999401337930214237184" = 1' SCALE
 49039857307708443467467104868809998802675860428474368" = 1' SCALE
 98079714615416886934934209737619997605351720856948736" = 1' SCALE
 196159429230833773869868419475239995210703441713897472" = 1' SCALE
 39231885846166754773973683895047999042140688342794944" = 1' SCALE
 78463771692333509547947367790095998084281376685589888" = 1' SCALE
 156927543384667019095894735580191996168562753371179776" = 1' SCALE
 313855086769334038191789471160383992337125506742359552" = 1' SCALE
 627710173538668076383578942320767984674251013484719104" = 1' SCALE
 1255420347077336152767157884641535969348502026969438208" = 1' SCALE
 2510840694154672305534315769283071938697004053938876416" = 1' SCALE
 5021681388309344611068631538566143877394008107877752832" = 1' SCALE
 100433627766186892221372631771322877547880162157555056" = 1' SCALE
 200867255532373784442745263542645755095760324315110112" = 1' SCALE
 401734511064747568885490527085291510191520648630220224" = 1' SCALE
 803469022129495137770981054170583020383041297260440448" = 1' SCALE
 1606938044258990275541962108341166040766082594520880896" = 1' SCALE
 3213876088517980551083924216682332081532165189041761792" = 1' SCALE
 6427752177035961102167848433364664163064330378083523584" = 1' SCALE
 12855504354071922204335696866729328326128660756167047168" = 1' SCALE
 25711008708143844408671393733458656652257321512334094336" = 1' SCALE
 51422017416287688817342787466917313304514643024668188672" = 1' SCALE
 102844034832575377634685574933834626609029286049336371344" = 1' SCALE
 205688069665150755269371149867669253218058572098672672688" = 1' SCALE
 411376139330301510538742299735338506436117144197345345376" = 1' SCALE
 822752278660603021077484599470677012872234288394690690752" = 1' SCALE
 1645504557321206042154969198941354025744468576789381381504" = 1' SCALE
 3291009114642412084309938397882708051488937153578762763008" = 1' SCALE
 6582018229284824168619876795765416102977874307157525526016" = 1' SCALE
 1316403645856964833723975359153083220595574861431505104032" = 1' SCALE
 2632807291713929667447950718306166441191149722863010208064" = 1' SCALE
 5265614583427859334895901436612332882382299445726020416128" = 1' SCALE
 10531229166855718669791802873224665764764598911452040832256" = 1' SCALE
 21062458333711437339583605746449331529529197822904081664512" = 1' SCALE
 42124916667422874679167211492898663059058395645808163329024" = 1' SCALE
 84249833334845749358334422985797326118116791291616326658048" = 1' SCALE
 168499666689691498716668845971594652236233585983232653116096" = 1' SCALE
 336999333379382997433337691943189304472467171966465306232192" = 1' SCALE
 673998666758765994866675383886378608944934343932930612464384" = 1' SCALE
 134799733351753198973335076777275721788986868786586124892768" = 1' SCALE
 269599466703506397946670153554551443577973737573172249785536" = 1' SCALE
 539198933407012795893340307109102887155947475146344499571072" = 1' SCALE
 1078397866814025591786680614218205774311894900292688991422144" = 1' SCALE
 2156795733628051183573361228436411548623789800585377982844288" = 1' SCALE
 4313591467256102367146722456872823097247579601170755965688576" = 1' SCALE
 8627182934512204734293444913745646194495159202341511931377152" = 1' SCALE
 17254365869024409468586889827491292388990318404683023862754304" = 1' SCALE
 34508731738048818937173779654982584777980636809366047725508608" = 1' SCALE
 69017463476097637874347559309965169555961273618732095451017216" = 1' SCALE
 138034926952195275748695118619930339111922547237464190902034432" = 1' SCALE
 276069853904390551497390237239860678223845094474928381804068864" = 1' SCALE
 55213970780878110299478047447972135644769018894985676360813728" = 1' SCALE
 110427941561756220598956094895944271289538037799971352721627456" = 1' SCALE
 220855883123512441197912189791888542579076075599942705443254912" = 1' SCALE
 441711766247024882395824379583777085158152151199885410886509824" = 1' SCALE
 883423532494049764791648759167554170316304302399770821773019648" = 1' SCALE
 1766847064988099529583297518335108340632608604799541643546039296" = 1' SCALE
 3533694129976199059166595036670216681265217209599083287092078592" = 1' SCALE
 7067388259952398118333190073340433362530434419198166574184157184" = 1' SCALE
 14134776519904796236666380146680866725060868838396333148368314368" = 1' SCALE
 28269553039809592473332760293361733450121737676792666296736628736" = 1' SCALE
 56539106079619184946665520586723467000243475353585332593473257472" = 1' SCALE
 113078212159238369893331041173446934000487350707170665186946514944" = 1' SCALE
 226156424318476739786662082346893868000974701414341330373893029888" = 1' SCALE
 452312848636953479573324164693787736001948402828682660747780059776" = 1' SCALE
 904625697273906959146648329387575472003896805657365321495560119552" = 1' SCALE
 1809251394547813918293296658775150944007793611314730642991120239104" = 1' SCALE
 3618502789095627836586593317550301888015587222629461285982240478208" = 1' SCALE
 7237005578191255673173186635100603776031174445258922571964480956416" = 1' SCALE
 14474011156382511346346373270201207552062348890517845143928961912832" = 1' SCALE
 28948022312765022692692746540402415104124697781035690287857923825664" = 1' SCALE
 57896044625530045385385493080804830208249395562071380575

Reproduced from the Collections
of the Library of Congress

RS

78985

344-548-D

PG:67-4

ULTIMATE TOWN
GREENBELT MARYLAND



RS
Reproduced from the Collections
of the Library of Congress

58634

344-3213

PG:67-4



GREENBELT MARYLAND
RESETTLEMENT ADMINISTRATION
DIVISION OF SUBURBAN RESETTLEMENT

Reproduced from the Collections
of the Library of Congress

6-8694

344-547-B

PG 67-4

Image # 7



What they could get

Government Clerks Can't Have Homes

What they wanted



...if we could find an inexpensive cottage in a modest neighborhood quite a ways out



...or a cozy little apartment on a sunlit court where children could play




61%

OF ALL FEDERAL EMPLOYEES IN WASHINGTON EARN LESS THAN \$2000 A YEAR

Buying 20 percent of houses for rent, these employees should be able to find adequate modern dwellings for their families at the following figures:

\$16.88	monthly for those earning \$1000 a year
\$20.00	monthly for those earning \$1200 a year
\$22.25	monthly for those earning \$1400 a year
\$26.86	monthly for those earning \$1800 a year
\$35.00	monthly for those earning \$1900 a year
\$29.32	monthly for those earning \$2000 a year



by One of Them.

There are no homes within the reach of the average Government clerk in Washington. After five or six months, I know this to be true. The budget experts say you may spend one-third of your income for rent. For me and my husband that means \$20 a month and there are plenty of others in the same boat, since something like 60 per cent of the Federal employees in the District earn less than \$2,000 a year. If for any reason you're headed the wrong way of moment, you'll find it all healthy and mutually competent Americans to produce 13 children, your problem is just 13 times as difficult. But let me tell you what happened to me when I tried to find a home for my family in Washington.

I began by seeking a home, because I thought it was so much better for the children to have a yard to play in and we'd be willing to live in a very modest neighborhood, quite a way out if we could find an inexpensive little cottage. Well, we couldn't. I couldn't have bothered asking myself the idea. The woman who runs the home-finding department of a local newspaper will tell you she has managed to find for small places costing \$1 to \$2 a month, and in two months' time all others have been able to secure a one cottage for \$250, with an outside privy.

I didn't want anything like that, so naturally I turned myself into a child's playground. Some of them do. Yes, some of them, but not for the price we can pay. But I didn't know that to begin with, so I headed for the Washington section, where I'd heard there are some decent apartments built around courts. These are nice and they are delightful. The buildings are neat and they have a vacant lot so that there is fresh air and sunlight. I felt better as soon as I saw them. Of course, the rent was a bit more than we should pay—\$2 to \$3 a month—but I was willing to pay. "We just won't have that work done at the deadline and I'll get along another week without a car!"

Oh, with visions of sturdy children playing in a sunlit court I searched the chain to the second floor to interview the resident manager. He wasn't quite as enthusiastic as I expected when I told him I wanted to rent one of his apartments. He was sorry, but there were no vacancies. Yes, there was a waiting list, but there couldn't be any one putting someone on it, because there were only 28 apartments and the list already stretched over 200 names.

Followed a series of brokers up steps and down steps. During the process I looked at apartments ranging from \$20 without heat and hot water, stretching one from another out of our budget until all we had left were two buildings, "hot" and "rent." But I couldn't have bothered, for it was always "no vacancies."

Finally, I decided to go straight to a free dealing in rental. I went out to work, but in several, and made the discovery that a couple of \$20 a month aren't even carried on their list. Very sneaky! I inquired how one discovers apartments not on their list. "I don't think you'll find many," was the answer. "I don't know of one myself. But maybe the newspapers—"

Ah, yes! I bought a newspaper. Not so many listed after all. The price amounted most of them. "Adults only" dominated nearly all the rest. (Do the sanitary professions know that apartments are rented to "adults only"? Well, I must find some solution. I phoned the numbers listed in the free remaining ads that seemed to have possibilities, only to find they had not. Then I sought the lady in charge of a newspaper home-finding department.

She took my name and address and started thumbing through lists of apartments. I mentioned the price and she stopped. "Nothing like that in Washington," I noticed there must be something and I proceeded to making myself her particular problem. She gave me street numbers. I went forth equipped with hope, but didn't come back that way because I had been viewing a succession of unattractive rooms spotted through dingy window frames and unimproved apartments. I had been viewing windowless rooms containing a plate gas stove and the doubtful privilege of using the "shared bathroom" on another floor, and had been viewing actual slums where they wouldn't even let you see the fire escapes and littered roads.

Finally, I was convinced. Washington can't be like this, but it is. There are no decent two-room apartments for rent at \$20 a month. They were right, all of them. I was in a quandary to take advice. "These, lady, where do Government clerks live?" she brightens. This is something she can deal with.

"They don't," she explains. "In private homes as if you prefer you can rent a room in a house and eat out. Lots of 'em do. Now there's a room and bathroom not far from Massachusetts avenue. That's a good neighborhood."

The lady was correct, demonstrably. It was a good neighborhood and it was a nice, large room. It needed to be for the time my husband, my children and I were installed. Of course, it has its drawbacks, but what a relief to be settled. Settled! We are practically wedded!

All we needed to make the complete was the letter from our parents saying they were looking forward to visiting us in our new home. That's a joy. Shall we return the letter marked "unknown at this address" or should we explain that it is an old Washington custom for an entire family to reside in one room? That we have to entertain guests on the sidewalk because the children are sleeping in our only room and that we're run an extension to our reading lamp into the hall so that the light won't wake the baby, and besides, this gives us a vantage point from which we can watch for an opportunity to get into the bathroom.

When our healthily built-up toes were just two inches to show the bath with us, she neglected to mention that they would each do domestic amount of laundry work whenever my husband would be above.

I can laugh about the way we live—sometimes. But when I think of the thousands of decent, intelligent people—earning less, and of the ugly, dirty houses into which they must crowd, I don't feel like laughing. Isn't there some humane solution?

Reprinted from The Washington Post.




RG

58694

Reproduced from the Collections
of the Library of Congress

342-1378

PG:67-4



- LEGEND -

- ▲ AIRPORTS, SEAPORTS AND RAILROADS
- BUSINESS, COMMERCIAL AND INDUSTRIAL
- RESIDENTIAL
- ▨ PUBLIC UTILITIES AND PUBLIC WORKS
- ▧ RECREATION, PARKS AND OPEN SPACE
- ▩ LANDS CONTAINED IN FEDERAL RESERVE SYSTEM
- FEDERAL LANDS
- STATE AND LOCAL LANDS
- ▬ WATERWAYS
- ▭ UNDEVELOPED

WASHINGTON - BALTIMORE
REGIONAL PLAN

SCALE 7" = 8 MILES

RS

Reproduced from the Collections
of the Library of Congress

59634

504-1380-13

PG67-4