

**United States Department of the Interior
Heritage Conservation and Recreation Service**

**National Register of Historic Places
Inventory—Nomination Form**

For HCRS use only

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic TOME SCHOOL FOR BOYS HISTORIC DISTRICT
and/or common BAINBRIDGE NAVAL TRAINING CENTER; SUSQUEHANNA-CHESAPEAKE JOB CORPS TRAINING CENTER

2. Location

street & number On Bainbridge Naval Training Center Grounds N/A not for publication
city, town Port Deposit vicinity of _____ congressional district First
state Maryland code 24 county Cecil code 015

3. Classification

Category	Ownership	Status	Present Use
<input checked="" type="checkbox"/> district	<input checked="" type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	_____ agriculture _____ museum
_____ building(s)	_____ private	_____ unoccupied	_____ commercial _____ park
_____ structure	_____ both	_____ work in progress	<input checked="" type="checkbox"/> educational _____ private residence
_____ site	Public Acquisition	Accessible	_____ entertainment _____ religious
_____ object	_____ in process	<input checked="" type="checkbox"/> yes: restricted	_____ government _____ scientific
	_____ being considered	_____ yes: unrestricted	_____ industrial _____ transportation
	<input checked="" type="checkbox"/> N/A	_____ no	_____ military _____ other:

4. Owner of Property

name U.S. Navy, c/o Naval Facilities Engineering Command, Atlantic Division
street & number _____
city, town Norfolk _____ vicinity of _____ state Virginia 23511

5. Location of Legal Description

courthouse, registry of deeds, etc. Cecil County Court House
street & number _____
city, town Elkton _____ state Maryland 21921

6. Representation in Existing Surveys

title Maryland Historical Trust
Inventory of Historic Sites has this property been determined eligible? _____ yes no
date June 1982 _____ federal state _____ county _____ local
depository for survey records Maryland Historical Trust
city, town Annapolis _____ state Maryland 21401

7. Description

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

DESCRIPTION: SUMMARY

The buildings of the former Tome School for Boys occupy the southwest quadrant of the Bainbridge Naval Training center on a 200 foot bluff overlooking the town of Port Deposit and the Susquehanna River in southern Cecil County, Maryland (see attached map). The buildings are now being leased by the U.S. Department of Labor and are used as the Susquehanna Job Corps Center. The historic district is comprised of 16 buildings on approximately 30 acres: the main academic building (Tome Memorial Hall), the three dormitories (Jackson, Harrison, and Madison Halls), the Director's residence, the Tome Inn dormitory and dining hall, the gymnasium (Monroe), six Masters' cottages, a non-contributing modern metal building and two non-contributing mid-20th century frame garages. All the buildings except the metal structure and garages date from 1900 to 1905. The rectangular metal building was added by the Job Corps in the 1970s for instructional and storage space. The buildings are arranged around a quadrangle oriented northeast-southwest, except the Masters' cottages, which are located on a road downslope to the southeast of the quadrangle. The stone buildings are in an elaborate Beaux-Arts-influenced, Georgian Revival style. The Masters' cottages are frame and stucco in a vernacular residential style. The addition of exterior fire escapes, minor changes in fenestration, and replacement of doors and roofs have not compromised the integrity of the complex.

GENERAL DESCRIPTION

The Tome School property also included a power plant, an infirmary, some frame outbuildings, and at least two 19th century farmhouses which are not within the district because of distance from the central area of the school or loss of historical integrity. The infirmary building originally stood near the athletic field behind Monroe House, but was moved prior to 1942 to its present location. The grounds were originally completely cleared and professionally landscaped with avenues of trees and a formal Italian garden in front of Tome Memorial Hall. Much of the quadrangle area and some of the buildings are obscured by overgrown trees and shrubs. The only unoccupied structure in the district, the Director's residence, is the most deteriorated and overgrown. Vandals have entered the building and damage has been done to the interior fixtures, although weather deterioration presents the greatest problem. The stone balustrades of the Italian garden are badly deteriorated and/or missing and marred by spray paint graffiti. The open space at the quadrangle's northeast end remains unchanged. The overgrown trees along the quadrangle serve to camouflage the one-story gable roofed metal building and de-emphasize its modernity in contrast with the stone buildings.

The interiors of most of the buildings have been altered over the years and must be considered as having lost historical integrity. The few surviving important interior features are described in detail in individual Maryland Historical Trust Inventory forms for each historic building in the district.

Descriptions and histories of individual buildings are included in the enclosed state inventory forms.

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input checked="" type="checkbox"/> education	<input checked="" type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1900-1905 **Builder/Architect** Boring and Tilton, Architects

Statement of Significance (in one paragraph)

Applicable Criteria: A and C

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

SIGNIFICANCE SUMMARY

The Tome School for Boys possesses significance in national architectural, educational and military history covering the period 1900 to 1974. The architectural significance of the school centers on the site plan and Beaux-Arts-influenced Georgian Revival style of the buildings designed by the firm of Boring and Tilton in 1900. This firm had just received international recognition, winning the Gold Medal of the Paris Exposition of 1900 for its design of the U.S. Immigration Station, Ellis Island, New York. The architecture of Tome School embodies the distinctive characteristics of the Beaux-Arts movement which flourished from about 1890 to 1930. The monumental scale of the buildings, their symmetrical facades, the elaborate ornamentation derived from English Renaissance and American Colonial Revival sources, and the axial site plan are the main elements of the movement present in the Tome School. The School is significant in national educational history for its association with James Cameron Mackenzie, the planner of both the Tome School and the Lawrenceville School in New Jersey. The Lawrenceville School of 1882, upon which the Tome School plan was based, was the prototype of the non-sectarian college preparatory boarding school which proliferated in America during the late 19th and early 20th centuries. Finally, the Tome School is significant in military history as the location of the Naval Academy Preparatory School (NAPS) from 1943 to 1974, excepting the years 1949 to 1951. The NAPS, the third oldest school in the U.S. Navy after the Naval Academy and the Naval War College, prepares enlisted candidates in the Navy and Marine Corps for admission to the Naval Academy. The NAPS was located in the Tome School buildings for a total of 29 years covering a period of three major wars, during which the school played a continuing role in providing naval leadership for those conflicts.

HISTORY AND SUPPORT

1. Pre-1899 Land Use: The land which later became the Tome School property was part of Susquehanna Manor, a land grant from Charles Calvert, Third Lord Baltimore, to George Talbot in 1680. (See Figure 1.) The area remained in agricultural use until 1899 when the first purchase of land for the School was made by the Board of Trustees of the Jacob Tome Institute of Port Deposit (Fig. 2).

See Continuation Sheet #1

United States Department of the Interior
Heritage Conservation and Recreation Service

For HCERS use only

received

date entered

**National Register of Historic Places
Inventory—Nomination Form**

Continuation sheet

Item number 8

Page 1

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

HISTORY AND SUPPORT (continued)

2. Port Deposit and Jacob Tome: Port Deposit was established as a river crossing point in the early 18th century and evolved into a mill and stone quarrying town by the early 19th century. It became an important transfer point for goods after the Maryland Canal opened in 1812. Port Deposit flourished throughout the 19th century but did not grow much larger in size than the present town boundaries. One of its most prominent citizens was Jacob Tome (1810-1898), a principal figure in the lumber and banking business. He came to Port Deposit from York County, Pennsylvania in 1833. Getting his start in the lumber business, Tome prospered so well in Port Deposit that by 1851 he opened the Cecil County Bank in the town. He was also involved in canal and railroad companies, coal mining and stone quarrying. Tome also founded the National Bank of Elkton, Bank of Frederickburg (Va), the National Bank of Hagerstown, and the Citizens National Bank of Washington, D.C.

3. The Jacob Tome Institute: Jacob Tome was the town's leading philanthropist as well as its most important businessman. He built the Methodist Church in 1872 and endowed the Methodist Episcopal Church. As a largely self-taught and self-made man, Tome was concerned about the education of local children of the middle class and poor. In 1894, he opened the Jacob Tome Institute in Port Deposit to serve as the free public school of the town. Completely equipped and endowed by Tome, the school was for white children of both sexes and emphasized a well-rounded curriculum. Cognizant of the need for basic manual skills as well as intellectual education, Tome included instruction in metal working and carpentry, business management, sewing and child care in the Institute.

4. Plans for Boarding School: The school immediately became the best in northern Maryland and attracted interested students from outside Port Deposit. As the demand for day and boarding facilities increased, the Board of Trustees made plans to use part of the endowment for this purpose. Jacob Tome died in 1898 before the boarding school was built, but his wife, Evalyn N. Tome, remained on the Board and continued his plans.

5. James C. Mackenzie: The Board diligently worked to bring the best educators to the Institute. The most well known educator in private secondary schools at the end of the 19th century was James Cameron Mackenzie, the planner of the Lawrenceville School in New Jersey. Established in 1882 to provide better prepared entering students to Princetown, the Lawrenceville School was planned by Mackenzie after visits to Exeter, Andover and St. Paul's schools, among others. He worked closely with Robert S. Peabody of the firm of Peabody and Stearns, one of the best-known and most prolific architectural firms of the late 19th century, on the design of the buildings and the planning of the grounds. Mackenzie was also responsible for the curriculum which had a heavy emphasis on the classics and science. Lawrenceville was unique in having a home boarding system, whereby

See Continuation Sheet #2

United States Department of the Interior
Heritage Conservation and Recreation Service

**National Register of Historic Places
Inventory—Nomination Form**

For HCRS use only

received

date entered

Continuation sheet

Item number 8

Page 2

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

HISTORY AND SUPPORT (continued)

younger students lived with a professor and his wife in small groups near the campus. Older and less affluent students lived in dormitories on the grounds. The Lawrenceville School was the first of many private college preparatory schools founded in the last part of the 19th century and the first years of the 20th century.

6. Plan and Design of Tome School: In 1899, Mackenzie was hired to plan the Tome School. Mackenzie recommended Peabody as the consulting architect, and in early 1900, a competition for the school plan and design was held. Peabody recommended the Colonial style as most appropriate and best adapted to the purposes of the School. The Board chose the designs of Boring and Tilton, a New York firm which had recently won a Gold Medal at the Paris Exposition of 1900 for the design of the U.S. Immigration Station at Ellis Island, New York. The Board purchased several farm properties totaling about 200 acres for the school site adjacent to Port Deposit's northern boundary. Charles W. Leavitt of New York was employed as Civil Engineer and Landscape Gardener. Boring and Tilton, with Leavitt's collaboration, designed the site plan including the roads, landscaping and the Italian garden.

By mid-1900, the first building, the Tome Inn, was under construction. This was to be used as guest housing and included individual rooms and suites as well as a dining room. It was designed in a shingled traditional style reminiscent of resort hotels of the period. Plans for the Tome Memorial Hall, the Director's residence, the Dining Hall, the dormitories and three types of Masters' cottages were adopted in August, 1900. The Infirmary design was adopted in October, 1900.

7. Completion of Buildings: The Inn was completed in late December, 1900. The Director's residence was finished in 1902, followed by the Dining Hall (Monroe), Jackson dormitory in 1903, and Madison dormitory in 1904. Three Masters' cottages, in different designs, were completed in 1902; three others of a fourth type were finished in 1904. The power plant was erected in 1901.

8. School Curriculum: Mackenzie's curriculum plan was apparently well received by the Board. Each grade or form had a strong emphasis on college preparatory courses in English, science, mathematics and foreign languages. Physical education was required at all levels. In keeping with Jacob Tome's wishes, manual training and business administration were included. Tome Memorial Hall contained completely equipped machine and carpentry shops as well as laboratory facilities and classrooms. Ironically, Mackenzie terminated his employment with

See Continuation Sheet #3

United States Department of the Interior
Heritage Conservation and Recreation Service

**National Register of Historic Places
Inventory—Nomination Form**

For HCRS use only

received

date entered

Continuation sheet

Item number 8

Page 3

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

HISTORY AND SUPPORT (continued)

the Tome School before the opening of classes, apparently due to unspecified disagreements with the Board of Trustees.

9. Harrison House and Dining Hall Addition to Tome Inn: The first classes were held in 1901 in the Tome Institute building in Port Deposit. Boarding students were housed in the Town Hall until the dormitories were finished. By 1904, enrollment had increased so dramatically that a third dormitory was needed. The Baltimore firm of Wyatt and Nolting was hired to design and build Harrison House. The dining hall in Monroe House had also been outgrown and the same contract called for an addition to the Tome Inn for a larger facility. Monroe House was converted to a gymnasium with the addition of an indoor swimming pool and basketball court. The two new buildings were finished in 1905 and were the last major building activities on the Tome School grounds.

10. School Development in 1920s and 1930s: Enrollment at the Tome School rose to a peak of about 225 boarders and 100 day students in the early 1920s. One of the original ideas of the Board was that each boy was to have his own room. This policy served to keep the number of students at a low level, as did the rising tuition costs. In about 1910, fees for "board, room, laundry, mending, lectures and entertainments and ordinary medical attention" totaled \$700 plus \$10 annual athletic association dues. Maryland residents were given a \$100 discount by direction of Tome's will. By the late 1920s and early 1930s, the fee totaled \$1,500. Tome was advertised as "The Most Beautiful and Best-equipped School in America", and often as the most highly endowed school in the nation. In 1906, the Cum Laude Society was founded at the Tome School by the Director, Dr. A. W. Harris. This honorary academic organization eventually grew to 76 chapters and 7,000 active and honorary members nationwide.

11. Decline: Continuing problems with the school's administration centered on the relationship with the Tome Institute in the town. The original intent of the Tome School was to provide a boarding school adjunct to the town school. As the prestige and enrollment of "the hill school" increased, however, disagreements arose over the administration of the endowment fund. Some Board members felt that more money should be appropriated for the town school. In addition, the stock market crash of 1929, and the ensuing Depression tended to lower enrollment at the Tome School as fewer parents could afford the tuition costs.

12. Closing of Tome School: In the late 1930s the troubles came to a head with the dismissal of the current Director, Dr. Charles J. Keppel. In protest, 158 students refused to attend classes for three days. Keppel was reinstated, but the financial problems of the School continued and, in 1938, a Tome School Corporation, composed of School alumni, bought the school from the Board of

See Continuation Sheet #4

United States Department of the Interior
Heritage Conservation and Recreation Service

National Register of Historic Places
Inventory—Nomination Form

For HCRS use only
received
date entered

Continuation sheet

Item number 8

Page 4

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

HISTORY AND SUPPORT (continued)

Trustees for \$350,000. The School continued to operate until 1941, but the Corporation was unable to meet its financial obligations, and the Tome School closed its doors after commencement ceremonies that year. The ownership of the School reverted to the Tome Institute.

13. U.S. Navy Acquisition of Tome School Property: In the Spring of 1942, the U.S. Navy acquired the Tome School by condemnation for the sum of \$941,820 for 330 acres. The complete power, water and sewer facilities of the site, its proximity to the Susquehanna River, and the undeveloped land adjacent to the grounds satisfied the Navy's need for an East Coast basic training site. A second condemnation in late 1942, involving 740 acres at \$218,226, expanded the site and by the end of 1942 the nucleus of temporary training facilities had been erected. The Tome School was used to house the Naval Academy Preparatory School (NAPS), which was moved to the training center, named after Commodore William Bainbridge, the commander of the U.S.S. Constitution during the War of 1812.

14. Navy Use of Tome School: The Tome School dormitories were renovated for use by the NAPS students, enlarging the formerly single rooms to accommodate several men. The Director's residence and the Masters' cottages became officers' quarters as did the Infirmary, which had been moved from its original location near the athletic field to a point on Tome Road prior to the School's closure in 1941. Monroe House became the Commissioned Officers' Club.

15. Bainbridge NTC Closure: Except for the period 1949 to 1951, NAPS remained in the Tome School buildings until 1974 when it was moved to Newport, R. I. The Bainbridge Naval Training Center expanded its operations and property throughout the 1940s and 1950s, eventually becoming the largest population center and main economic force in Cecil County during this period. Declining enlistment quotas led to the gradual closure of portions of the sprawling Center until 1976, when the last active units were transferred elsewhere and the Center was closed completely.

16. Job Corps Center: In 1978, the Department of Labor leased the Tome School buildings and most of its former grounds as well as Camp Rodgers, one of the adjacent naval training areas, for use as a Job Corps Training Center. In 1979, the Tome School property became the Susquehanna Job Corps Center. The Singer Corporation operates the facility, providing intensive basic education, vocational skills training and supportive services to severely disadvantaged young people aged 16 to 21. The Susquehanna Center gives instruction in clerical skills,

United States Department of the Interior
Heritage Conservation and Recreation Service

**National Register of Historic Places
Inventory—Nomination Form**

For HCRS use only

received

date entered

Continuation sheet

Item number 8

Page 5

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

culinary arts, technical trades, nurse's aide skills, building and apartment maintenance and landscaping. The landscape classes required the erection of a metal building on the west side of the quadrangle between Madison House and Tome Memorial Hall. The adjoining Chesapeake Job Corps Center, under the same direction as the Susquehanna Center, offers courses in construction trades, warehousing, automotive and clerical skills. This section occupies the former naval training area.

United States Department of the Interior
Heritage Conservation and Recreation Service

National Register of Historic Places
Inventory—Nomination Form

For HCRS use only

received

date entered

Continuation sheet

Item number 9

Page 6

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

Cecil County: A Reference Book of History, Business and General Information.
County Directories of Maryland, Inc., Baltimore, 1956.

Command Histories on file at Naval Historical Center, Washington, D.C., (Bainbridge Naval Training Center and Naval Academy Preparatory School).

Interview by phone with Captain Richard Stratton, Officer in Charge, Naval Academy Preparatory School, Newport, R.I.

Interview with Dr. William M. Hogue, Ph.D., Executive Director, Tome School.

Kraushaar, Otto F.. American Non-public Schools: Patterns of Diversity. John Hopkins University Press, Baltimore, 1972.

Lake, Griffing and Stevenson. An Illustrated Atlas of Cecil County, Maryland, 1877.

Land Records of Cecil County, Cecil County Court House, Elkton, Maryland.

Minutes of the Board of Trustees, Tome Institute, at Tome School, North East, Maryland.

"Naval Training Station: East Coast", Architectural Forum, 79, pp.47-54, September 1943.

Property Records of Department of the Navy, Naval Facilities Engineering Command, Atlantic Division, Norfolk, Virginia and Alexandria, Virginia.

Survey Files, Maryland Historical Trust, Annapolis, Maryland.

Vertical Files, Cecil County Historical Society, "Tome School", "Bainbridge Naval Training Center".

Vertical Files, Enoch Pratt Free Library, Baltimore, "Tome School"; "Jacob Tome Institute"; "Bainbridge Naval Training Center".

"Views, Plans, and Drawings, Jacob Tome Institute, Port Deposit, Maryland", Architecture, 5, pp. 172-180, 1902.

Withey, Henry F., and Elsie Rathburn Withey. Biographical Dictionary of American Architects, Deceased. Hennessey and Ingalls, Inc., Los Angeles, 1970.

United States Department of the Interior
Heritage Conservation and Recreation Service

**National Register of Historic Places
Inventory—Nomination Form**

For HCRS use only

received

date entered

Continuation sheet

Item number 10

Page 7

Tome School for Boys Historic District
Bainbridge Naval Training Center
Port Deposit, Cecil County, Maryland

Boundary Justification:

The boundary has been established to include the major academic buildings surrounding the Tome School quadrangle and the six Masters' cottages on Tome Road immediately east of the quadrangle. These buildings are the historical heart of the district and have been only slightly altered on the exteriors since their construction. The power plant (Bldg. 7) and the Infirmary (Bldg. D-D) are part of the original plan, but are more distant and visually cut off from the quadrangle area by topography and vegetation. The two non-contributing garages (Bldgs. 19 and 23) are small frame buildings in unobtrusive locations. The non-contributing metal building is one story high and tan in color. It is low and partially hidden by trees. The southwest boundary is a chain link fence at the edge of the Bainbridge NTC property. Structures 76 and 77 on the map are a swimming pool and wading pool next to Monroe House and are screened by a high wood fence.

9. Major Bibliographical References

See Continuation Sheet 6.

10. Geographical Data

Acreeage of nominated property ca. 30

Quadrangle name Havre de Grace

Quadrangle scale 1:24,000

UMT References

A

118	405	21010	413	814	21610
Zone	Easting		Northing		

B

118	405	21010	413	814	01010
Zone	Easting		Northing		

C

118	404	71110	413	813	81010
Zone	Easting		Northing		

D

118	404	61010	413	813	91810
Zone	Easting		Northing		

E

118	405	01010	413	814	31210
Zone	Easting		Northing		

F

118	405	01810	413	814	21310
Zone	Easting		Northing		

G

118	405	11610	413	814	31010
Zone	Easting		Northing		

H

Zone	Easting		Northing		

Verbal boundary description and justification

For verbal boundary description, see attached map.

For boundary justification, see Continuation Sheet #7.

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
N/A			

state	code	county	code

11. Form Prepared By

name/title Janet L. Davis

organization Maryland Historical Trust date May-June 1982

street & number 21 State Circle telephone (301)269-2438

city or town Annapolis state Maryland 21401

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature

title _____ date _____

For HCRS use only

I hereby certify that this property is included in the National Register


date _____

Keeper of the National Register

Attest:

date _____

Chief of Registration



MAP
of the upper part
of the Peninsula,
showing
the location of the
**INDIAN FORTS, EARLY LAND
GRANTS, BOUNDARY LINES &c.**

Drawn by
GEO. M. REESE,
under the direction of the Author
and designed to illustrate
the history of
CECIL COUNTY.

SCALE : 5 MILES TO ONE INCH


Tome School Historic District CE-1285
Cecil County, Maryland


Fig. 1: Map of Late 17th century land
grants in Cecil County

From: Cecil County Reference Book, 1956

Fig. 2: Port Deposit vicinity

From: Lake, Griffing, & Stevenson,
An Illustrated Atlas of Cecil
County, Maryland, 1877





Tome School Historic District CE-1285
 Cecil County, Maryland


Contributing Buildings = C
 Non-contributing Buildings = NC

76 & 77: swimming pools

C = Contributing
 NC = Non-contributing

CE-1285


GOLF COURSE



Tome School Historic District CE-1285
 Cecil County, Maryland

Site Plan

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY



76°07'30"
404000m E
405
5'
RISING SUN 8.1 MI.
LIBERTY GROVE 2.8 A
4.7 MI. TO U.S. 1
OCTORARO 3.8 MI.

RISING SUN 6.1 MI
WOODLAWN 0.9 MI

Bainbridge NTC Boundary

Proposed Tome School H.D. Boundary

BAINBRIDGE
NAVAL TRAINING
CENTER

Tome School Historic District CE-1285
Cecil County, Maryland
U.S.G.S. 7.5 Minute Map
Havre de Grace Quadrangle
Scale: 1:24000
1970



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

Dorms and gym from Memorial Hall, c.
1907

1/5



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Italian Garden & Director's Res., c.

1907 2/5



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Italian Garden & Memorial Hall, vw. W.

3/5



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Italian Garden

4/5



Tome School Historic District CE-1285

Cecil County, Maryland


photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Italian Garden balustrades

5/5



Tome School Historic District CE-1285
Cecil County, Maryland
photo: Janet Davis
neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Tome Memorial Hall (CE-1262), main ent.

1/07



Tome School Historic District CE-1285
Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Tome Memorial Hall (CE-1262), S. entr.

2/7



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Tome Memorial Hall (CE-1262), c. 1907

yw. from s. 3/87



62.

Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Tome Memorial Hall (CE-1262), c. 1907

yw. from s. 4/7



Tome School Historic District CE-1285

Cecil County, Maryland


photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Tome Memorial Hall (CE-1262), c. 1907

vw. of library 5/7



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Tome Memorial Hall (CE-1262), c. 1907

vw. of woodworking shop 6/87



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Tome Memorial Hall (CE-1262) from Ital.
Garden [redacted] 7/7



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Master's Cottage L (CE-1269), s. elev.

1/8



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Master's Cottage B (CE-1269), vw. from

SW 2/8



Tome School Historic District CE-1285
Cecil County, Maryland
photo: Janet Davis
neg loc: Maryland Historical Trust,
Annapolis, MD
May 1982
Master's Cottage C (CE-1269), ne elev.
3/8



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Master's Cottage E (CE-1269), NE elev.

4/8



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Master's Cottage E (CE-1269), c. 1907

vw. 5/8



Tome School Historic District CE-1285
Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Master's Cottage F (CE-1269), NE elev.
6/8



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Street vw., Masters' Cottages (CE-1269)

7/8



Tome School Historic District CE-1285

Cecil County, Maryland

photo: Janet Davis

neg loc: Maryland Historical Trust,
Annapolis, MD

May 1982

Street vw., Masters' Cottages (CE-1269)

c. 1907 8/8



CE-1285

Tome School Historic District