

United States Department of the Interior
National Park Service

National Register of Historic Places
Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If any item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property


historic name Langley Park (PG#65-7)
other names McCormick-Goodhart Mansion

2. Location

street & number 8151 15th Avenue not for publication
city or town Langley Park vicinity
state MD code MD county Prince George's code 033 zip code 20783

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act of 1966, as amended, I hereby certify that this nomination request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property meets does not meet the National Register criteria. I recommend that this property be considered significant nationally statewide locally. (See continuation sheet for additional comments).


Signature of certifying official/Title

7-15-08
Date

State or Federal agency and bureau

In my opinion, the property meets does not meet the National Register criteria. (See continuation sheet for additional comments).

Signature of certifying official/Title

Date

State or Federal agency and bureau

4. National Park Service Certification

I hereby, certify that this property is:

- entered in the National Register.
 See continuation sheet.
- determined eligible for the National Register.
 See continuation sheet.
- Determined not eligible for the National Register.
- removed from the National Register.
- other (explain): _____

Signature of the Keeper

Date of Action

5. Classification

Ownership of Property

(Check as many boxes as apply)

- private
- public-local
- public-State
- public-Federal

Category of Property

(Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

(Do not include previously listed resources in the count)

Contributing	Noncontributing	
1		buildings
		sites
		structures
		objects
1	0	Total

Name of related multiple property listing N/A

(Enter "N/A" if property is not part of a multiple property listing)

N/A

number of contributing resources previously listed in the National Register

0

6. Function or Use

Historic Functions

(Enter categories from instructions)

DOMESTIC/single dwelling

Current Functions

(Enter categories from instructions)

WORK IN PROGRESS

SOCIAL/civic

7. Description

Architectural Classification

(Enter categories from instructions)

Georgian Revival

Materials

(Enter categories from instructions)

foundation Concrete

walls Brick

roof Asphalt shingle

other Cast stone trim

Narrative Description

(Describe the historic and current condition of the property on one or more continuation sheets)

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A** Property is associated with events that have made a significant contribution to the broad pattern of our history.
- B** Property associated with the lives of persons significant in our past.
- C** Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D** Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all the boxes that apply)

Property is:

- A** owned by a religious institution or used for religious purposes.
- B** removed from its original location.
- C** a birthplace or grave.
- D** a cemetery.
- E** a reconstructed building, object, or structure.
- F** a commemorative property.
- G** less than 50 years of age or achieved significance within the past 50 years.

Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets)

Area of Significance

(Enter categories from instructions)

Architecture

Period of Significance

1924-1947

Significant Dates

1924

Significant Person

(Complete if Criterion B is marked above)

N/A

Cultural Affiliation

N/A

Architect/Builder

George Oakley Totten, Jr., architect

9. Major Bibliographical References

Bibliography

(Cite the books, articles, and other sources used in preparing this form on one or more continuation sheets)

Previous documentation on files (NPS):

- preliminary determination of individual listing (36 CFR 67) has been requested
- previously listed in the National Register
- previously determined eligible by the National Register
- designated a National Historic Landmark
- recorded by Historic American Buildings Survey # _____
- recorded by Historic American Engineering Record # _____

Primary location of additional data:

- State Historic Preservation Office
- Other State agency
- Federal agency
- Local government (M-NCPPC)
- University
- Other

Name of repository: Prince George's Co. Historical Society

Langley Park (PG#65-7)
Name of Property

Prince George's County, Maryland
County and State

10. Geographical Data

Acreage of Property .6625 acre

UTM References

(Place additional UTM references on a continuation sheet)

1	1	8	3	2	8	3	6	2	4	3	1	7	3	9	7
	Zone		Easting				Northing								
2															

3															
	Zone		Easting				Northing								
4															

See continuation sheet

Verbal Boundary Description

(Describe the boundaries of the property on a continuation sheet)

Boundary Justification

(Explain why the boundaries were selected on a continuation sheet)

11. Form Prepared By

name/title Susan G. Pearl, Historian
Organization Prince George's County Historical Society date October 2007
street & number 6701 McDonough Terrace telephone 301-262-3367
city or town Bowie state MD zip code 20720

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

A **USGS map** (7.5 or 15 minute series) indicating the property's location.

A **Sketch map** for historic districts and properties having large acreage or numerous resources.

Photographs

Representative **black and white photographs** of the property.

Additional Items

(Check with the SHPO or FPO for any additional items)

Property Owner

(Complete this item at the request of SHPO or FPO)

name Willowbrook Limited Partnership (Sawyer Realty Holdings)
street & number 9658 Baltimore Avenue, Suite 300 telephone 301-479-1600
city or town College Park state MD zip code 02494-2820

Paperwork Reduction Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 *et. seq.*).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Project (1024-0018), Washington, DC 20503.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Section 7 Page 1

Prince George's County, Maryland
County and State

Description Summary:

Langley Park is a Georgian Revival estate mansion, built in 1924 of brick, clay tile, and concrete, circa 180 by 40 feet; the exterior is of brick with cast-stone trim. It consists of a three-part, three-story, hip-roof main block, with a lower kitchen wing extending to the east. The main block comprises a central three-bay square flanked by two symmetrical three-bay wings, and is distinguished by a monumental two-story pedimented Ionic portico at its principal south entrance. The main elevations are highlighted by fluted pilasters surmounted by a continuous architrave, plain frieze and dentillated cornice. The two-story kitchen wing, simpler and without the wide cornice of the main block, extends to the east. The interior of the main block features a large entry salon, formal living room and dining room with fine classical revival detail, and a particularly fine double staircase with jigsawed grillework and second-story gallery. The building, once the centerpiece of a 500-acre estate, is now surrounded by low-rise garden apartment units. The building is in deteriorated condition, but is in the process of being carefully restored.

General Description:

Exterior

The main block consists of a three-story, three-bay square, 40 by 40 foot structure, flanked by two symmetrical three-bay wings, 34 by 34 feet, which are slightly inset from the central block on both facades. Entrance is in the central bay of the principal south façade through a round arched doorway. The double door is flanked by fluted columns, and surmounted by a fluted frieze and wave molding within a keystone arch. A smaller door has replaced the original double door, and the space around it and that in the surmounting fanlight have been infilled with grooved plywood. Above the south door at second level is a double door (now missing) with a small metal-grille balcony.

Sheltering most of the south façade is a monumental two-story front-gabled portico. Four two-story cast stone Ionic columns support a full entablature: a plain frieze with dentillated cornice and pediment, and, in the tympanum, molded decorations of central shield with urns and acanthus leaves. The ceiling of the portico has a central cast-iron medallion. Fluted pilasters mark the juncture of portico with the central block. The portico is accessed by a flight of eight concrete steps. The two tall first-story windows that flank the central door are surmounted by flat brick arches with cast stone keystones, above which are small cast-stone medallion decorations.

Flanking the three-bay central section are two symmetrical three-bay wings, 34 by 34 feet each, and three stories high. The lateral bays of the two flanking wings are also clearly defined by four fluted pilasters

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Prince George's County, Maryland
County and State

Section 7 Page 2

surmounted by architrave, frieze, and dentillated cornice. The 6/6 double-hung-sash windows of the first story have flat brick arches with cast stone keystones, and each is set in a shallow recessed arch with cast stone keystone and impost blocks. Windows on the second story (6/6 double-hung-sash) have plain flat arches. Most of the window sashes throughout the house have been destroyed or removed, and all openings are now boarded up.

The rear north elevation reflects some of the same features as the principal south facade: the three central bays are clearly defined by four two-story fluted pilasters surmounted by architrave, frieze and dentillated cornice. The north door is set in an inset arch with keystone and impost blocks, and that space has been infilled with board. Above the door at second level is a rectangular concrete plaque with the raised coat of arms of the Goodhart family: on a shield, a Cross of Lorraine is flanked by two eagles over a buck flanked by two flying bees; above the shield is a crest consisting of a beehive flanked by two bees and surmounted by a rainbow terminating in clouds. Beneath the shield is a banner with "*A Deo Omnia*," and on the sides of the shield is the date 1924. The north door opens out onto a 12 by 40 foot terrace which was originally bounded by a balustrade with sculpted lions (no longer existing). As in the south principal facade, the three-bay flanking wings of the main block are slightly inset on the north elevation; unlike the south facade, however, only two fluted pilasters mark the north elevation of the flanking wings, outside and enclosing the three bays of these wings.

A one-story porch (10 feet by 24) shelters the door that is centered in the west elevation. Plain Tuscan columns support the cornice and frieze; a flight of five concrete steps leads to the porch, which has in recent years been enclosed. There is a single shed dormer at third level in the west elevation.

Extending to the east is a two-story hip-roof service wing, measuring 46 by 30 feet. It is five bays by three bays, and is the only section of the building which has a full basement. Windows are 6/6 double hung sash, and have concrete keystones set into flat-arch lintels on the first story, plain arches on the second. The service wing consisted originally of kitchen, scullery, pantry, and servants' hall on the first story, three bedrooms, one dressing room and two baths on the second. There are entrances into the service wing in the first and third bay of the north elevation, as well as a metal fire escape. The porch on the west elevation is balanced by a 9 by 15 foot storage space at the east end of the service wing.

The shell of the entire building is constructed of brick and clay tile, but faced on all elevations by brick laid in Flemish bond. The hip-on-hip roof is covered with asphalt shingle. Five brick chimneys rise from the roof, irregularly spaced to serve interior fireplaces. The third story of the main block is lighted on the south by two long three-window shed dormers, and by seven individual shed dormers on the north.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Prince George's County, Maryland
County and State

Section 7 Page 3

Interior

The south portico leads into a large, 26 by 38 foot entry salon (denoted "Living Room" on Totten's original plans) on the south, and a transverse stairhall on the north. There is a fireplace in the east wall of the salon; the elaborate, dark wood with geometric-design mantel and overmantel have been removed, and there is some fire damage in this area. Dropped ceiling has been installed in the salon, as in many other parts of the building. The walls of this entry salon are finished with ornately molded wainscoting: "linen fold" panels of oak surmounted by a narrow horizontal floral rinceaux panel. Fluted pilasters on molded pedestals mark the corners and openings of the salon walls. In the northwest corner of the salon, a double door, boxed and enframed by fluted pilasters, leads west by a small corridor to the westerly spaces of the house. A corresponding door in the northeast corner of the salon leads by a small corridor to the easterly spaces and to the service wing. Centered in the north wall of the salon, a wider opening leads into the northerly transverse stairhall.

In the transverse stairhall, three steps lead up to a landing and the north entrance. The north door was originally enframed by sidelights and three-light transom, surmounted by a double fanlight, all highly decorated with geometric tracery. The inner six-ray fanlight is enframed by an outer three-section fan, all now boarded up. Two closed-string, two-run flights of stairs rise from the central entrance landing along the north wall of the stairhall, then turn 90 degrees and rise again along the east and west walls to a gallery on the south wall at second level. The newels are square and paneled, with ornate carved wood console brackets. Highly decorative jigsawn grillework decorates the spaces between plain balusters and the wainscoting along the wall. The gallery of the same jigsawn grillework overlooks the stairhall from the second story.

The west flanking wing includes on the first story a 21-by-32-foot living room; the fireplace is centered in the north wall, but the mantel has been removed. Prominent courses of plaster molding – a wide convex course of flowers and grapes between a course of egg-and-dart and a course of fasces – form a decorative boundary pattern on the ceiling. A small boudoir, accessible both from the west living room and from the west corridor, retains its Colonial Revival style wooden mantel, with dentillated entablature and central plaque (with molded figures of women and children) in the plain frieze.

An ornate dining room, measuring 21 by 32 feet, occupies the same position in the east flanking wing as the living room does in the west wing. The entry door, in the west wall of the dining room, has a handsome enframing; the architrave features bold console brackets framing a frieze with projecting swags and central urn, above which is a dentillated broken pediment framing a central cornucopia urn. Two doors in the eastern wall of the dining room lead into the pantry and scullery; each of these two narrower doors has a slightly more modest architrave than the westerly door, with the same frieze and brackets, and a plain dentillated pediment. Between the two easterly doors is the fireplace. Only the entablature and shelf of the plaster mantel survive; the frieze is decorated with vertical moldings and a central plaque beneath a simple Greek meander molding. The

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Section 7 Page 4

Prince George's County, Maryland
County and State

supporting colonnettes have been removed, and only ghosts of the swag moldings of the overmantel are still visible. The southernmost eight feet of the dining room is set off as a sort of alcove from the rest of the room; originally there was a pair of columns *in antis* supporting the dividing beam. This alcove has an ornate plaster ceiling with rinceaux molding. Occupying the location corresponding to that of the boudoir in the west is a small library; centered in its west wall is a dark wood mantel with deep molded shelf, and the walls are paneled with dark stained wood as high as the top of the mantel shelf. The partially vaulted ceiling is decorated with geometric figures.

The two easterly doors of the dining room lead into the east service wing, containing scullery and pantry, and then the kitchen. These spaces have been essentially gutted, but walls of shelves and cabinets survive. Between the pantry and scullery, and accessible from a narrow connecting corridor is a safe, with thick iron door. Beyond the kitchen, south of the servants' hall is a winding stair leading to the basement and to the second-story bedchambers.

On the second story of the main block, the master bedroom, with adjoining dressing room and bath, takes up the projecting central section of the building on the south, the corresponding space on the north being filled with the double staircase and gallery. There are six additional bed chambers, another dressing room and five baths, accessed by a very narrow hall. On the third story are six servants' rooms, one bath and three large storage spaces.

The setting

The mansion is approached by a circular drive from the south. Its former grounds are now filled with three-story garden apartment buildings. Not included in the nominated parcel are the community swimming pool east of the mansion and the former stable and carriage house that serves as the physical plant for the apartment complex.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park

Name of Property

Prince George's County, Maryland

County and State

Section 8 Page 1

Summary Statement of Significance:

Langley Park is significant under Criterion C as a nearly unique example in Prince George's County of a great country house of the 1920s; it embodies the distinctive characteristics of an early twentieth-century estate mansion of the Georgian Revival style. The residence was designed in 1924 by leading Washington, D.C., architect George Oakley Totten, Jr., for Frederick and Henrietta McCormick-Goodhart, an affluent Anglo-American couple who had purchased more than 500 acres northwest of Bladensburg. The McCormick-Goodharts named their new property after the Goodhart family's Elizabethan estate house in Kent, England. They contracted with architect Totten to design a great house—a massive three-story Georgian Revival mansion with monumental Ionic portico, with the interior lavishly decorated with plaster cornices and medallions, Colonial Revival style mantels, and an elaborate double staircase and gallery. The period of significance begins in 1924 with construction of the house and extends to 1947, when the property was sold by the McCormick-Goodhart heirs. The mansion and 25 acres then became the center for the Eudist Fathers, a French Canadian Catholic order. In 1963, the property was purchased by a real estate syndicate, and the Willowbrook garden apartment units were built all around the mansion. Until the 1990s, the mansion itself served as a school for the local community.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Prince George's County, Maryland
County and State

Section 8 Page 2

Resource History and Historic Context:

Historical Background

Langley Park is located in the northwest section of Prince George's County, an area bordering the District of Columbia on the south and Montgomery County on the west, and watered by the Northwest Branch of the Anacostia to the north and northeast. Before the twentieth century, this area, like all of Prince George's County, was agricultural, consisting of several tracts, such as Elizabeth's Delight, Giliad, and Adelphi, and large antebellum plantations, then later large farms carved out of the plantation acreages. The subject property had been part of Elizabeth's Delight, owned and farmed in the late nineteenth century by merchant farmer brothers William Bladen Jackson and Benjamin Lowndes Jackson, descendants of Christopher Lowndes, a prominent figure in pre-Revolutionary Bladensburg. During the nineteenth century, the most prominent landmark in the area was the Adelphi Mill, a short distance to the east on the Northwest Branch; this mill had been constructed late in the eighteenth century by the brothers Scholfield on their Adelphi tract, and was owned and operated during the nineteenth century by the family of George Washington Riggs of nearby Green Hill.

At the beginning of the twentieth century, the area that would become Langley Park remained agricultural and undeveloped. The residential community of Takoma Park was beginning to be developed on the boundary between Prince George's and Montgomery Counties (about 2 miles to the southwest), and the nearest communities in Prince George's County were tiny Branchville and fast-developing Hyattsville, three miles to the east and southeast, respectively. It was in this agricultural setting that the McCormick-Goodhart family established its Langley Park country estate. The first aerial photographs, dating from 1937 to 1938, show the area to be completely undeveloped, with the Langley Park mansion, completed in 1924, surrounded by agricultural fields and wooded areas on both sides of the Northwest Branch. In the years during and immediately following World War II, however, the McCormick-Goodhart family began to sell some of the Langley Park acreage. Dynamic suburban growth began, fed by arterial roads, new water mains, sewerage lines and school construction. The mansion was converted into a Seminary operated by the Eudist Fathers, and in 1948 and 1949, 506 multifamily units—40 to 60 per development—were built all around the Seminary's 25 acres. In 1963 the Seminary was sold to apartment developers, the lake was filled in, and new apartment units were built within the 25-acre grounds. For many years, the mansion itself was operated as a community school, but the serious deterioration of the building caused its closure in the 1990s. At present, plans are underway for the complete restoration of the building.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Section 8 Page 3

Prince George's County, Maryland
County and State

Resource History

In 1921, Frederick and Henrietta McCormick-Goodhart came to the Washington area. Frederick Goodhart (1854-1924) was the son of Charles Emanuel Goodhart of Langley Park in Beckenham, Kent, England. Frederick Goodhart had first come to the United States in 1883 regarding a Utah mine in which his father had an interest. Spending some time in Chicago during this trip, he met and became engaged to Henrietta McCormick (1857-1932), niece and daughter, respectively, of Cyrus and Leander McCormick of McCormick Reaper fame. They were married in November 1883 and went to England to live at the groom's ancestral home, Langley Park. Their two sons, Leander and Frederick Hamilton McCormick-Goodhart, were born in England in 1884 and 1887.¹ Frederick McCormick-Goodhart practiced law in England, then entered politics, running unsuccessfully for a Conservative seat in the House of Commons in 1900 and 1905. He became well known for work in organizing the Imperial Service College for the education of sons of officers of the British Army and Navy. He served many years as treasurer of the Church Army, one of the largest charitable organizations in the British Isles. His wife also was known for her philanthropic work. Their two sons were educated at Eton and Oxford.²

The family spent most of their time in England, with occasional trips to the United States to spend time with Henrietta's family. In 1899, at the request of Henrietta's father, Frederick, through a "Royal Licence," added McCormick to his surname, and the family name officially became McCormick-Goodhart.³ In 1913, the Elizabethan house at Langley Park in Kent was destroyed by fire, and in 1920 Frederick and Henrietta McCormick-Goodhart decided to settle in the United States. In 1921 they purchased 565 acres of land northwest of Bladensburg, including parts of early tracts known as Elizabeth's Delight and Adelphi. Part of this land had been owned by merchant farmer brothers William Bladen Jackson and Benjamin Lowndes Jackson, direct descendants of the Lowndes family of Bladensburg. In 1855 the Jackson brothers, whose business was located in the District of Columbia, had purchased 231 acres of property just outside of Washington in northwesterly Prince George's County. Known as Burgundy Farm, the farm was named for its culture of grapes, and the spacious, multi-section Burgundy Farm house was a favorite retreat from the city for members of the Jackson family. The McCormick-Goodharts moved into the Jacksons' spacious Burgundy Farm house soon after their purchase of the property in 1921, but in November of 1922 the Burgundy Farm house was destroyed by fire.⁴

¹ McCormick-Goodhart, Henrietta, *Hands Across the Sea*, privately printed, 1921; McCormick, Leander J., *Family Record and Biography*, Chicago, 1896; telephone interview with Leander McCormick-Goodhart, September 2007

² McCormick-Goodhart, Henrietta, *op. cit.*

³ McCormick-Goodhart, Henrietta, *op. cit.*, p. 56.

⁴ Prince George's County Deeds EWB#1:140, #169:276; interview with Jackson family descendant, September 2007

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Section 8 Page 4

Prince George's County, Maryland
County and State

Almost immediately Frederick and Henrietta McCormick-Goodhart began to plan the construction of a great country house on the property. They contracted with George Oakley Totten, Jr., (1866-1939) to design their country mansion on the Burgundy Farm acreage. Totten had gained fame for his design of many elaborate private residences and Embassy buildings in Washington, D.C. He was born in New York City, and had taken up the study of architecture at Columbia University. He later won a McKim Traveling Scholarship, and went to Paris to study at the Ecole des Beaux Arts. He came to Washington in the 1890s, and served two years (1895-97) as a member of the U.S. Supervising Architect's office. Together with a Columbia classmate, he established the architectural firm Totten & Rogers, which operated from 1899 to 1907. He opened his own private studio in 1910, and developed a wide practice, designing buildings for Embassies and other foreign legations, as well as Club Houses and private homes. He was hired to design homes in the Meridian Hill neighborhood by Mrs. John B. Henderson, who planned to lease or sell them to embassies. Between 1906 and 1927 he designed nine houses in Meridian Hill, and also private houses and embassies on Massachusetts Avenue west of Dupont Circle.⁵

Totten was a member of the American Institute of Architects, and one-time president of the Latrobe Chapter. He was director of the Allied Architects of Washington, D.C., an honorary member of the Old Russian Society of Architects, and of architectural societies in Belgium, Austria and Spain. Totten designed public buildings and private homes in places other than Washington, D.C., but the house that he designed for the McCormick-Goodhart family is his only known work in Prince George's County.⁶

The home that Totten designed for the McCormick-Goodharts was a massive three-story Georgian Revival mansion, with monumental Ionic portico and molded exterior cast stone medallions and plaques. The interior was lavishly decorated with plaster cornices and ceiling detail, fine Colonial Revival style mantels, and an elaborate double staircase and gallery. The estate was named Langley Park, after the family estate in England. Its 565 acres were located in rural, agricultural land on the south side of the Northwest Branch, including the Adelphi Mill property, and extending from the Montgomery County line on the west to the community of Adelphi on the east. A lake was created just north of the mansion, a greenhouse to the west and a stable/carriage house to the east. Floor plans and photographs of the newly-completed mansion were featured in a 1926 issue of *The American Architect*.⁷

⁵ Withey, Henry F. and Elsie R., *Biographical Dictionary of American Architects (Deceased)*, New Age Publishing Co, Los Angeles, California, 1956; *American Art Annual*, Vol. 21, 1924-25; Obituary of George Totten, Jr., *New York Times*, 3 February 1939; Scott, Pamela, & Antoinette J. Lee, *Buildings of the District of Columbia*, New York, Oxford University Press, 1993.

⁶ Withey, Henry F. and Elsie R., *Biographical Dictionary of American Architects (Deceased)*, New Age Publishing Co, Los Angeles, California, 1956; *American Art Annual*, Vol. 21, 1924-25; Obituary of George Totten, Jr., *New York Times*, 3 February 1939.

⁷ *American Architect*, Volume CXXIX, 20 May 1926

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Prince George's County, Maryland
County and State

Section 8 Page 5

The new Langley Park mansion was finished in the summer of 1924, but Frederick McCormick-Goodhart had essentially no time to enjoy it. He died suddenly, 26 September 1924, less than a week after moving into the newly finished mansion. He was eulogized for his charitable and educational work in England, and noted for the construction of his new estate house at Langley Park in Maryland. He was buried at Rock Creek Cemetery in Montgomery County.⁸

Mrs. McCormick-Goodhart continued to live in the mansion, with a large staff to maintain the house and grounds. She maintained the connections that her husband and son, Leander, had through their work with the British Embassy in Washington, and, according to descendants of the family, continued to entertain visiting Britons often at Langley Park. In 1931, she deeded to her two sons, Leander and Frederick Hamilton McCormick-Goodhart, the entire Langley Park estate, 565 acres including the original 231 acres on which the house had been built and 38 acres on which stood the historic Adelphi Mill. She remained in the mansion, maintaining a large staff there, until her death in November 1932. She was noted for her prominence in Washington society of the time, and was buried with her husband at Rock Creek Cemetery.⁹

Frederick Hamilton McCormick-Goodhart died at a young age in Washington in December 1938; after the establishment of a trust, management of the Langley Park property resided in his elder brother, Leander McCormick-Goodhart, and a trustee.¹⁰ The elder McCormick-Goodhart was honorary commercial secretary to the British Embassy in Washington, and lived at least part time at the *Langley Park* mansion during the period of the Second World War. Leander McCormick-Goodhart had worked in the Trade Division of the British Admiralty during the First World War, and was given the Order of the British Empire for his work. He came to the United States in the early 1920s and worked as commercial secretary to the British Embassy in Washington. From 1939 until his retirement in 1942, he worked as special personal assistant to the British Ambassador. In 1947, through his trustee, and together with other members of the McCormick-Goodhart family, he sold circa 25 acres of the Langley Park acreage that included the mansion, lake and immediate grounds, to members of the Eudist Fathers, a French Catholic order, who established the Willowbrook Seminary on the property.¹¹

⁸ *Washington Evening Star*, 27 September 1924, page 7; *New York Times*, 28 September 1924, p. 27.

⁹ Prince George's County Deed #375:243; interview with Leander McCormick-Goodhart, September 2007; *Washington Evening Star*, 21 November 1932, page A-2

¹⁰ *Washington Evening Star*, 13 December 1938; Prince George's County Deeds #628:3, #630:374, #652:273, #776:68, #795:19, #1125:376, #1186:350

¹¹ *Washington Evening Star*, 17 December 1965; Prince George's County Deed #926:171; interview with Leander McCormick-Goodhart, September 2007. Leander McCormick-Goodhart sold the Adelphi Mill property to The Maryland-National Capital Park and Planning Commission in 1951 (Prince George's County Deed #1436:321); the renovated mill structure is now maintained by the Department of Parks and Recreation as a rental facility in a park setting on the Northwest Branch of the Anacostia.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Prince George's County, Maryland
County and State

Section 8 Page 6

The Society of Eudist Fathers (La Congrégation de Jésus et Marie) was founded in 1643 in France by St. John Eudes (1601-1680, canonized in 1925), with its principal goal being the education of priests. Many Eudist schools and seminaries were established in Canada, and later, in the aftermath of Second World War, Reverend Albert D'Amours, Superior of the Université de Sacre Coeur (Quebec), initiated the attempt to establish Eudist seminaries in the United States. After considering several locations, the Eudist Fathers purchased from the McCormick-Goodhart family's trustee 25 acres of land of the Langley Park property, and established in the mansion the new Willowbrook Seminary. It opened its doors in the autumn of 1947, the first seminarians being Eudist recruits from Ireland. The establishment did not prove successful; maintenance of the property proved to be very expensive, many of the seminarians left, and those remaining transferred to Sacre Coeur in Quebec during the 1950s. The mansion became the residence of a few students and missionaries until the property was sold by the Eudists in 1963.¹²

During the Eudists tenure, the setting of the Langley Park mansion remained essentially unchanged, but major change was soon to come. With the closing of the seminary in 1963, the Eudist seminary property was sold to apartment developers. The lake was filled in, and construction began on 590 low-rise garden apartment rental units (Willowbrook Apartments) on the circa 25-acre grounds (known as Parcel L) of the mansion. In 1964 work began on the mansion to convert it into the Willowbrook Montessori School.¹³ The mansion remained the centerpiece of this new residential development, and the Montessori School operated into the 1990s, until serious deterioration of the building caused its closure.

During this time, the immigrant population, particularly Hispanic, of the area surrounding the Langley Park mansion increased. In 1985, CASA de Maryland, a small social service organization, was founded, with the goal of providing assistance, training, job placement, and access to resources to low-wage Latinos and other immigrant families. In recent years, CASA, in collaboration with the owners of Parcel L, began to plan the restoration of the mansion to serve as CASA's regional headquarters, and multicultural center for the assistance of community residents. In 2005, the owners of Parcel L, Willowbrook Limited Partnership, signed a lease with CASA to proceed with this work. This agreement, regarding the mansion and its .6625-acre setting, was extended in October 2007. Plans for the complete restoration of the building have been approved, and work will begin before the end of 2007.¹⁴

¹² "Willowbrook Seminary, Hyattsville, Md." *Service des archives provinciales eudistes de l'Amérique du Nord* <http://www.eudistes.org/archives.htm>; Prince George's County Deeds #926:171, #1205:311

¹³ Prince George's County Deeds #2851:432, #5040:71, #14878:65; Prince George's County Plat WWW#49:11; *The Evening Star*, 19 June 1964.

¹⁴ *CASA de Maryland: Building for the Future*, October 3, 2007 (booklet for opening event at Langley Park), October 3, 2007; Lease agreement, 17 May 2005, with amendment 3 October 2007

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Section 8 Page 7

Prince George's County, Maryland
County and State

Resource Analysis

Langley Park is nearly unique in Prince George's County, being one of only three architect-designed estate houses of the early twentieth century. It was the first of these three, and was designed by George Oakley Totten, Jr., a well-known architect from Washington, D.C. It can be compared with Oxon Hill Manor (1929) and the Newton White Mansion (1939), both designed by well-known architects, and, both, like Langley Park, built in areas that were still rural and completely undeveloped at the time of their construction.

Oxon Hill Manor was designed by Jules Henri de Sibour (1872-1938), well known for the mansions (many now embassies) that he designed in Washington, D.C., during the first quarter of the 20th century. Oxon Hill Manor was built in 1929 for career diplomat Sumner Welles. It is a neo-Georgian house built of brick, standing on landscaped grounds overlooking the Potomac River. The house is more than 100 feet long, with balustraded porches, casement windows, and elaborate pedimented entrances among its fine detail. Acquired in 1976 by the Maryland-National Capital Park & Planning Commission, this impressive estate house is now available for rental.

The Newton White Mansion, also known as Enterprise Farm, was designed by William Lawrence Bottomley (1883-1951) for Newton H. White, Commanding Officer of the U.S.S. Enterprise. Bottomley did some design work in Washington, D.C., but is best known for his neo-classical mansions in the Richmond, Virginia, area. The White mansion is built of brick, with curved hip roofs and porthole windows suggesting a naval theme, and features many neo-classical motifs. The house and more than 500 surrounding acres of the model dairy farm that Commander White developed were acquired in 1971 by the Maryland-National Capital Park and Planning Commission. The house now serves as a reception hall, and the grounds have been developed into a golf course.

Langley Park differs from the two mansions cited above in that the area around it has been completely developed with apartment units, and nothing survives of its original landscaped grounds. Unlike Oxon Hill Manor and the Newton White Mansion, Langley Park is in deteriorated condition, principally from sections of roof failure and consequent interior water damage. Langley Park is, however, eminently restorable; detailed plans for its restoration have been approved, and work will begin in late 2007 and early 2008. The plans for its adaptive use promise to return this outstanding building to its former prominence.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Langley Park (PG#65-7)

Name of Property

Prince George's County, Maryland

County and State

Section 9 Page 1

Major Bibliographical References:

See notes, Item 8

McCormick-Goodhart, Henrietta, *Hands Across the Sea*, privately printed, 1921

American Architect, Volume CXXIX, 20 May 1926

Prince George's County Deeds; items from *Washington Evening Star*

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

PG#65-7
Langley Park
Name of Property

Section 10 Page 1

Prince George's County, Maryland
County and State


Verbal Boundary Description:

See attached description and plat of Parcel "A" – 28,857 square feet or 0.6625 acre.

Boundary Justification:

Parcel "A" comprises the Langley Park mansion and its immediate grounds. No other buildings or structures are located on the nominated property.

PG#65-7 Langley Park, Prince George's County, MD



Americap Architect
May 20 1926, Plate 110

SCHEDULE "B"

PARCEL "L"
 LANGLEY PARK
 PLAT 49 NO. 11
 WILLOWBROOK LIMITED PARTNERSHIP
 L 14878 F.085

RECREATIONAL
 PARCEL
 18,517 SQ. FT.
 0.4251 AC.

PARCEL "A"
 28,857 SQ. FT.
 0.6625 AC.


PARCEL "L"
 LANGLEY PARK
 PLAT 49 NO. 11
 WILLOWBROOK LIMITED PARTNERSHIP
 L 14878 F.085

SCALE: 1" = 50'
 NAD 83 DATUM

N00°03'16"E 966.86' BOUNDARY LINE
 N00°01'20"E 966.86' PLAT LINE

N44°04'04"W 365.72'
 BOUNDARY LINE

N28°15'33"E
 403.80'



Lolederman
 Soltesz Associates, Inc.

LANHAM OFFICE

4266 Forbes Boulevard Lanham, MD 20706 t.301.794.7555 f.301.794.7656

Engineering Planning Surveying Environmental Sciences www.LSAssociates.net

I hereby certify to the best of my professional knowledge, information, and belief, that the information shown hereon is correct and is based on available records.


As to the establishment of easement lines.

John W. Kostic 9-27-07
 John W. Kostic Date
 Property Line Surveyor
 Md. Reg. No. 473



S:\2322000\SURVEY\Sketches\PARCELS.sht

PG#65-7 Langley Park, Prince George's County, MD
Floor Plan from American Architect, May 20, 1926




COUNTRY HOUSE OF F. F. MCCORMICK-GOODHART, NEAR WASHINGTON, D. C.

GEORGE OAKLEY TOTTEN, JR., ARCHITECT

(KENSINGTON)
2.11 SE

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

5662 III ST
(BELTSVIL)



PG# 65-7
Langley Park
Langley Park,
Prince Georges
County, MD
UTM Reference:
3/528362/4317397
Quad:
Wash. E.

THE WHITE HOUSE 6 MI.



Langley Park (P6# 65-7)

Prince George's Co. MD

Susan G. Pearl

15 August 2007

Negative: MD Hist Trust, Crownsville, MD

South facade, from southwest

#1 of 30



Langley Park (PG #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD Hist Trust

View south from mansion

2 of 30



Langley Park (PG # 65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD Hist Trust

South portico from south

#3 of 30



Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

South portico detail

4 of 30



Langley Park (PA # 65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

South fenestration detail

#5 of 30



Langley Park (PG #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

South cornice/pilaster detail

#6 of 30



Langley Park (Pg # 65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

West porch from southwest

7 of 30



Langley Park (Pg #65.7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

North elevation from north east

8 of 30



Langley Park (Pl # 65-7)

Prince George's Co., MD

Jusan G. Pearl

15 August 2007

Neg: MD SHPO

North elevation from north west

#9 of 30



Langley Park (Pg # 65-7)

Prince George's Co, MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Plaque, north entrance

#10 of 30



Joyes view E

Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Entry salon, view to east

#11 of 30



Inyer W door

Langley Park (Pa #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Entry salon, view to northwest

#12 of 30



Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

West corridor, view to west

#13 of 30

Susan Pearl
W



Ceiling W LR

Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

West Living Room, ceiling detail (west)

#14 of 30



Ceiling @ LR

Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

West Living Room, ceiling detail (north)

#15 of 30

LF



Langley Park (PG #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

West boudoir (view to east)

#16 of 30

Boudoir W



Fayer view N

Langley Park (PG #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Entry salon, view north to stair hall

#17 of 30



Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

North door, view north from stairhall

18 of 30

N door



Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Stair, view to west

#19 of 30

Stair
w



Langley Park (Pg#65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Stair, view to east

#20 of 30

Stair E



Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Stair, detail

#21 of 30



N don

Langley Park (Ph #65-7)

Prince George's Co., MD


Susan G. Pearl

15 August 2007

Neg: MD SHPO

North door from second story

#22 of 30



Steel gallery

Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Second story gallery

#23 of 30



Langley Park (Pg # 65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

East corridor, view to east

#24 of 30

Fayer view E



Langley Park (Pg #65-7)

Prince George's Co, P, MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

West boudoir mantel, view to east

#25 of 30



Langley Park (Pg # 65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Dining Room, northeast door, view to east

#26 of 30

DR
NE door



DR W door

Langley Park (Pg #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Dining room, west door, view to west

#27 of 30



Langley Park (Pg. #65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Library, view to west (mantel)

#28 of 30



Library ceiling

Langley Park (Ph # 65-7)

Prince George's Co., MD

Susan G. Pearl

15 August 2007

Neg: MD SHPO

Library, ceiling detail

29 of 30



Langley Park (Pis #65-7)

Prince George's Co, MD

Susan Cr. Pearl

15 August 2007

Neg: MD SHPO

Pantry cabinets, view to north

#30 of 30

Pantry

MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM

NR Eligible: yes no

Property Name: Langley Park Inventory Number: P.G. #65-7

Address: 8151 15th Avenue City: Langley Park Zip Code: 20783

County: Prince Georges USGS Topographic Map: Washington East

Owner: Willowbrook Real Estate Is the property being evaluated a district? yes no

Tax Parcel Number: _____ Tax Map Number: _____ Tax Account ID Number: _____

Project: _____ Agency: _____

Site visit by MHT staff: no yes Name: _____ Date: _____

Is the property is located within a historic district? yes no

If the property is within a district District Inventory Number: _____
NR-listed district yes Eligible district yes Name of District: _____
Preparer's Recommendation: Contributing resource yes no Non-contributing but eligible in another context yes

If the property is not within a district (or the property is a district) Preparer's Recommendation: Eligible yes no

Criteria: A B C D Considerations: A B C D E F G None

Documentation on the property/district is presented in:
Maryland Inventory of Historic Properties, Maryland Historical Trust

Description of Property and Eligibility Determination: *(Use continuation sheet if necessary and attach map and photo)*

Langley Park is a three-part Georgian Revival brick and concrete country house completed in 1924 by Washington architect George Oakley Totten for Frederick and Henrietta McCormick-Goodhart. The three-story principal block is delineated with fluted pilasters on the front and rear elevations and the façade is enriched with a two-story Ionic portico with full entablature and molded concrete medallions and plaques. A two-story service wing extends to the east. The interior is embellished with an elaborate double staircase and gallery, Colonial Revival style mantels, and plaster cornices and medallions.

Langley Park is eligible for the National Register under Criterion C, as it embodies the distinctive characteristics of a Georgian Revival country house of the 1920s. The house retains its integrity of location, design, workmanship, materials, feeling and association; the estate is now the centerpiece of the Willowbrook apartment complex. Frederick Goodhart and his wife Henrietta McCormick purchased 565 acres of land northwest of Bladensburg when they came to the Washington area in 1921. After the frame farmhouse on the property burned, the McCormick-Goodharts engaged George Oakley Totten, Jr., who had designed more than ten embassy buildings in Washington, D.C. The estate was named after the Goodhart family home in England. Langley Park is one of only two such estate houses in Prince George's County.

Prepared by: Nancy Kurtz Date Prepared: 03/13/2003

MARYLAND HISTORICAL TRUST REVIEW
Eligibility recommended Eligibility not recommended
Criteria: A B C D Considerations: A B C D E F G None
MHT Comments
Langley Park has been evaluated in a local context and found to have significance at the local level.
Reviewer, Office of Preservation Services _____ Date _____
Peter Kurtz *[Signature]* _____ March 13, 2003
Reviewer, NR Program _____ Date _____

Vmk

PRINCE GEORGE'S COUNTY
HISTORIC SITE SUMMARY SHEET

Survey #: P.G. #65-7

Building Date: 1924

Building Name: Langley Park

Location: 8151 15th Avenue, Langley Park, Maryland

Private/Educational/Occupied/Fair/Accessible

Description:

Langley Park is a three-story Georgian Revival brick-and-concrete mansion; it consists of a three-part three-story principal section, with a lower kitchen wing extending to the east. The main block consists of a three-bay square, flanked by two symmetrical wings. Entrance is in the central bay of the principal south facade through a segmentally arched doorway flanked by fluted columns, and surmounted by a keystone arch. First story windows are 12/12 double hung sash and have keystone lintels and plaster decorations above them. Sheltering the south facade is a monumental two-story front-gabled portico, four Ionic columns support a full entablature. The north facade reflects some of the same features; the three bays are clearly delineated by fluted pilasters surmounted by architrave, frieze, and dentilled cornice. Flanking the central section are two symmetrical three-bay three-story wings, and to the east is a two-story service wing. The mansion is surrounded by a complex of apartment buildings.

Significance:

Langley Park is a nearly unique example in Prince George's County of a great country house of the 1920's; it was designed in 1924 by George Oakley Totten, a prominent Washington architect, for Frederick and Henrietta McCormick-Goodhart. The McCormick-Goodharts purchased 565 acres of land northwest of Bladensburg when they came to the Washington area in 1921 and contracted with Major George Oakley Totter, Jr. to design a large brick country house. The home which he designed was a massive three-story Georgian Revival mansion with monumental Ionic portico; the interior was lavishly decorated with plaster cornices and medallions, Colonial Revival style mantels, and an elaborate double staircase and gallery. Langley Park passed after 1932 to the sons of the McCormick-Goodharts; it remained in the family until 1947 when the mansion and 25 acres were sold to a French Catholic order. In 1963 the property was purchased by a real estate syndicate, and it became the centerpiece of the Willowbrook apartment complex. Langley Park has considerable historical and architectural significance. It was designed as a country estate for an affluent Anglo-American family by one of the leading architects of the day; it is one of the last great country houses of the 1920's, and is one of only two such estate houses in Prince George's County.

Acreage: 24.45 acres

Magi No.

DOE yes no

Maryland Historical Trust State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic Langley Park

and/or common McCormick - Goodhart Mansion

2. Location

street & number 8151 15th Avenue not for publicationcity, town Langley Park vicinity of congressional district 5state Md county Prince George's

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input checked="" type="checkbox"/> educational	<input type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Willowbrook Real Estate

street & number 8555 16th Street telephone no.:

city, town Silver Spring state and zip code MD 20910

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse liber 5040

street & number Main Street folio 71

city, town Upper Marlboro state MD

6. Representation in Existing Historical Surveys

title Historic Sites and Districts Plan

date 1981 federal state county local

depository for survey records Historic Preservation Commission MNCPPC

city, town Upper Marlboro state MD

7. Description

Survey No. PG#65-7

Condition

excellent
 good
 fair

deteriorated
 ruins
 unexposed

Check one

unaltered
 altered

Check one

original site
 moved date of move _____

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Langley Park is a three-story Georgian Revival brick-and-concrete mansion, circa 180 by 40 feet. It consists of a three-part three-story principal section, with a lower kitchen wing extending to the east.

The main block consists of a three-story three-bay square, 40 by 40 feet; it is flanked by two symmetrical three-bay wings, 34 by 34 feet, which are slightly inset from the central block on both facades. Entrance is in the central bay of the principal south facade through a segmentally arched doorway. The double door is flanked by fluted columns, and surmounted by a keystone arch. First story windows are 12/12 double hung sash and have keystone lintels and plaster decorations above them. Above the south door at second level is a double door with a small metal balcony.

Sheltering the south facade is a monumental two-story front-gabled portico. Four (concrete) Ionic columns support a full-entablature: a plain frieze with dentilled cornice and raking cornice, and molded decorations in the tympanum of central shield with urns and acanthus leaves. The ceiling of the portico has a central medallion. Fluted pilasters mark the juncture of portico with central block.

The rear north facade reflects some of the same features: the three bays are clearly delineated by four two-story fluted pilasters surmounted by architrave, frieze, and dentilled cornice. The north door is set into an inset arch with keystone; above the door at second level is a rectangular concrete plaque with raised coat-of-arms. The north door opens onto a 12 by 40 foot terrace originally bounded by a balustrade.

Flanking the three-bay central section are two symmetrical three-bay wings 34 by 34 feet each, three stories high. These lateral bays are also clearly delineated (as is the north elevation) by fluted pilasters surmounted by architrave, frieze, and dentilled cornice. The 6/6 windows of the first story have flat brick arches with concrete keystones, and each is set in a shallow recessed arch. Windows on the second story have flat arches.

This three-part main block has a hip-on-hip roof with continuous shed-roof dormers on the south, and seven shed-roof dormers on the north.

The south portico leads into a large (26 by 38 foot) grand salon on the south, and a transverse stairhall on the north. Two closed-string two-run staircases rise from the central doorway along the north wall of the stairhall, then turn 90° and rise again along the east and west walls to a gallery on the south wall at second level. The newels are square and panelled; highly decorative jigsaw grillework decorates the spaces between plain balusters. The west lateral wing includes a 21 by 32 foot living room decorated with elaborate plaster cornice and medallions; there is a dining room in the corresponding position in the east lateral wing. Both rooms are further adorned by handsome Colonial Revival style mantels and pedimented door surrounds. The second story of the main block includes six bedrooms, two dressing rooms, and five baths. On the third story are six servants' rooms, one bath, and three large storage spaces.

Extending to the east is a two-story hip-roof service wing, 46 by 30 feet. It is five bays by three bays, and is the only section of the building which has a basement. Windows are 6/6 double hung sash, and have concrete keystones set into flat arch lintels on the first story. The service wing houses scullery, pantry kitchen and servants' hall on the first story, and three bedrooms, one dressing room and two baths on the second. There is a metal fire escape on the north elevation.

The first story of the building has been modified to serve as a day care center. The upper stories are closed and secured.

A one-story 10 by 24 foot covered porch on the west elevation is balanced by a 9 by 15 foot storage space at the east end of the kitchen wing.

The mansion is approached by a circular drive from the south. Its grounds are now filled with apartment buildings. Immediately east of the mansion is a community swimming pool. Immediately north of the pool is a three-part one-story brick building which serves as the physical plant for the apartment complex; it was originally built as a stable and carriage house.

8. Significance

Survey No. PG#65-7

Period	Area of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1924 Builder/Architect George Oakley Totten, Jr.

check: Applicable Criteria: A B C D
 and/or
 Applicable Exception: A B C D E F G
 Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

Langley Park is a nearly unique example in Prince George's County of a great country house of the 1920's; the only other example of this type in the County is Oxon Hill Manor, designed for Sumner Welles by Jules Henri de Sibour and completed in 1929. Langley Park was designed and built in 1924 by Major George Oakley Totten, Jr., a prominent Washington architect, for Frederick and Henrietta McCormick-Goodhart.

Frederick Goodhart and his wife, Henrietta McCormick, purchased 565 acres of land northwest of Bladensburg when they came to the Washington area in 1921. This land, parts of "Elizabeth's Delight" and "Adelphi", had been known in the second half of the nineteenth century as "Burgundy Farm", part of the 1,000-acre establishment of merchant farmers Benjamin L. and William B. Jackson.¹ The new owners began in 1921 to remodel the Jackson farmhouse. Within a year, however, this old frame farmhouse was destroyed by fire, and in 1923, the McCormick-Goodharts contracted with Major George Oakley Totten, Jr. to design for them a large brick country house. Totten had gained fame in Washington as the designer of more than ten embassy buildings on Fifteenth and Sixteenth Streets, N.W.² The home which he designed for the McCormick-Goodhart family was a massive three-story Georgian Revival mansion, with monumental Ionic portico and molded exterior concrete medallions and plaques. The interior was lavishly decorated with plaster cornices and medallions, fine Colonial Revival style mantels, and an elaborate double staircase and gallery. The estate was named Langley Park after the Goodhart family estate in England; its 565 acres extended from Montgomery County on the west to Adelphi on the east, on the south side of the Northwest Branch. A lake was created north of the house, a greenhouse to the west, and a stable/carriage house to the east. Floor plans and photographs of the newly-completed mansion were featured in the 1926 issue of The American Architect.³

The mansion was completed in 1924, and Frederick Goodhart died before the end of that year. His widow lived at Langley Park until her death in 1932; before her death she deeded the estate to her two sons, Frederick

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
Statement of Significance (continued)

Survey No. PG#65-7

Section 8 Page 2

and Leander.⁴ It remained in the possession of Leander McCormick-Goodhart until 1947 when he sold the mansion and 25 acres to a religious organization. The mansion itself was used by the Eudist Fathers, a French Catholic order, as a Seminary until 1963. Later that year the property was purchased by a real estate syndicate, and it became the centerpiece of the Willowbrook apartment complex.⁵

Today the first story of the mansion houses a day care center, and the carriage house to the east serves as the physical plant for the apartment complex. The mansion is in deteriorating condition, due to water damage, vandalism and neglect. It is, however, of considerable historical and architectural significance. It was designed as a country estate for an affluent Anglo-American family by one of the leading architects of the day, and is one of the last great country houses of the 1920's, an era which ended abruptly with the stock market crash and Great Depression. It is structurally sound, and restorable, and is one of only two such estate houses in Prince George's County.

Notes

1 Prince George's County Deeds, EWB #1:140, #169:276; Martenet Map of Prince George's County, 1861; G.M. Hopkins Atlas, 1878 and 1894.

2 The American Architect, Vol. 129, No. 2497, May 20, 1926; cf. also Langley Park, A Case Study in Preservation, University of Maryland, College Park, 1987. Laurel News Leader, August 29, 1963, p. A-10.

3 The American Architect, op. cit.; Prince George's County Deed #926:171, Plat p. 173.

4 Prince George's County Deed #375:243; The Evening Star (Washington), June 19, 1964, p. C-2; Laurel News Leader, op. cit.

5 Prince George's County Deeds #926:171; #1205:311; #2851:432; The Evening Star, op. cit.; Laurel News Leader, op. cit.

9. Major Bibliographical References

Survey No. PG#65-7

- cf. Chain of title
- cf. Notes, Item # 8

10. Geographical Data

Acreeage of nominated property 24.45 acres Tax map 32 /4972/ Parcel L
 Quadrangle name Washington East, Section A Quadrangle scale _____

UTM References do NOT complete UTM references

A	<input type="text"/>	<input type="text"/>	<input type="text"/>	B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing		Zone	Easting	Northing
C	<input type="text"/>	<input type="text"/>	<input type="text"/>	D	<input type="text"/>	<input type="text"/>	<input type="text"/>
E	<input type="text"/>	<input type="text"/>	<input type="text"/>	F	<input type="text"/>	<input type="text"/>	<input type="text"/>
G	<input type="text"/>	<input type="text"/>	<input type="text"/>	H	<input type="text"/>	<input type="text"/>	<input type="text"/>

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code

11. Form Prepared By

name/title Susan G. Pearl, Research Historian

organization Historic Preservation Commission date August 1987

street & number c/o County Planning, MNCPPC telephone 952-3521

city or town Upper Marlboro state MD

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
 Shaw House
 21 State Circle
 Annapolis, Maryland 21401
 (301) 269-2438

Chain of Title

Langley Park
P.G. #65-7

#5040:71
29 Dec. 1978 J. Willard Marriott to Willow Brook Real Estate, 24.4538 acres, same described in #2851:432.

2851:432
5 Aug. 1963
Deed Eudist Fathers to Teplin, Reines, Wolman and Foreman; 24.4538 acres Langley Park, as surveyed by Seybolt and George, Parcel L.



1205:311
11 Jan. 1950
Deed From S. F. Kennedy, Y. Savoie and Albert D'Amours to Eudist Fathers; Parcel 1, 24.996 acres sold by trustee Evans to D'Amours.

926:171
24 Mar. 1947
Deed From Joshua Evans, Jr., trustee for McCormick-Goodharts to Albert D'Amours; Parcel 1 (24.996 acres) including Mansion, outbuildings and lake; same as first tract in Deed 169:276.


375:243
12 Dec. 1931
Deed From Henrietta McCormick-Goodhart, widow, to Leander and Frederick H. McCormick-Goodhart, tenants in common, 231 acres.

169:276
1 Jan. 1921
Deed W. Bladen Jackson et al., to Frederick E. and Henrietta McCormick-Goodhart; Parcel #1, part of Elizabeth's Delight, 231 acres, being part of the land conveyed to B. L. and W. B. Jackson, EWB #1:140.

EWB #1:140 From John B. King and Dionysius Sheriff, trustees, to Benjamin L. Jackson and William B. Jackson; King and Sheriff having been appointed trustees in Equity case (1852) John B. King et al., vs. James R. King.



COUNTRY HOUSE OF F. E. MCCORMICK-GOODHART, NEAR WASHINGTON, D. C.
GEORGE OAKLEY TOTTEN, JR., ARCHITECT



COUNTRY HOUSE OF F. E. MCCORMICK-GOODHART, NEAR WASHINGTON, D. C.
GEORGE OAKLEY TOTTEN, JR., ARCHITECT

PRINCE GEORGE'S COUNTY
HISTORIC SITES SUMMARY SHEET

P.G. County Survey # 65-7 Date 1924
Building Name Langley Park or McCormick-Goodhart Mansion
Location 15th Ave. off University Blvd., Langley Park, Md.
Open to Public yes no restricted

This is a massive, Georgian Revival, brick mansion, built as an estate in 1920's. The central section, three bays wide, projects slightly from the two flanking sections, each three bays wide. The south (main) facade has a massive stone pedimented portico, supported by four tall Ionic columns and full entablature. Light colored stone is used effectively in the watertable, pilasters, and keystones.

The tract upon which the McCormick-Goodhart mansion stands was part of a large farm owned for many generations by the Jackson family, prominent merchants and farmers of Prince George's County. Frederick and Henrietta McCormick-Goodhart acquired the farm in 1921, and commissioned architect George Oakley Totter Jr. to design their mansion. It was completed in 1924. The grounds included the 170 foot mansion, garage, greenhouse, and a landscaped lake (300' by 100') to the north, with a right of way to the mansion from the south. The estate was named Langley Park after the P.E. Goodhart family estate in England. Henrietta McCormick was a relative of Cyrus McCormick, inventor of the reaper.

The estate was divided by the McCormick-Goodhart heirs, and the mansion tract sold to the Eudist Fathers, who used the mansion as their headquarters until recent years. It now houses a school and nursery for the Willowbrook Apartment complex.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC Langley Park

AND/OR COMMON McCormick-Goodhart Mansion

2 LOCATION

STREET & NUMBER 15th Avenue off University Boulevard

CITY, TOWN Langley Park, VICINITY OF CONGRESSIONAL DISTRICT 5th

STATE Maryland P.G. COUNTY

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input checked="" type="checkbox"/> EDUCATIONAL <input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME Willowbrook Apartments
(Teplin, Reines, Wolman & Foreman) Telephone #: 439-5155

STREET & NUMBER 15th Avenue off University Boulevard

CITY, TOWN Langley Park VICINITY OF STATE, zip code Maryland 20787

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC. P.G. County Courthouse

Liber #: 2851
Folio #: 432

STREET & NUMBER Main Street

CITY, TOWN Upper Marlboro STATE Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE P.G. County Inventory of Historic Sites

DATE 1974 FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR SURVEY RECORDS Calvert Mansion, 4811 Riverdale Rd.

CITY, TOWN Riverdale, Md. 20840 STATE

7 DESCRIPTION

CONDITION

CHECK ONE

CHECK ONE

EXCELLENT
 GOOD
 FAIR

DETERIORATED
 RUINS
 UNEXPOSED

UNALTERED
 ALTERED

ORIGINAL SITE
 MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This is a massive, Georgian Revival, brick mansion, built as an estate in the 1920's. The central section, three bays wide, projects slightly from the two flanking sections, also ^{each} three bays wide. The south (main) facade has a massive stone pedimented portico, supported by four tall Ionic columns and full entablature. Light colored stone is used effectively in the water-table, pilasters and keystones.

A five-bay service wing, part of the original plan, extends to the east.

8 SIGNIFICANCE

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)		
		<input type="checkbox"/> INVENTION				x local history

SPECIFIC DATES 1924 BUILDER/ARCHITECT George Oakley Totten, Jr.

STATEMENT OF SIGNIFICANCE

The tract upon which the McCormick-Goodhart mansion stands was part of a large farm owned for many generations by the Jackson family, prominent merchants and farmers of Prince George's County. Frederick and Henrietta McCormick-Goodhart acquired the farm in 1921¹, and commissioned architect George Oakley Totten, Jr., to design their mansion. It was completed in 1924. The grounds included the 170 foot mansion, garage, greenhouse, and a landscaped lake (300 by 100 feet) to the north, with a right of way to the mansion from the south.² The estate was named Langley Park after the F.E. Goodhart family estate in England. Henrietta McCormick was a relative of Cyrus McCormick, inventor of the reaper.

The estate was divided by the McCormick-Goodhart heirs³, and the mansion tract sold to the Eudist Fathers of the Congregation of Jesus and Mary, Inc., who used the mansion as their headquarters until recent years.⁴ It now houses a school and nursery for the Willowbrook Apartment complex.

- 1. P.G. Deed: 169:276
- 2. " 926:171
- 3. " 375:243
- 4. " 1205:311

9 MAJOR BIBLIOGRAPHICAL REFERENCES

P.G.C. Deeds: #2851:432; 1205:311; 926:171; 375:243; 169:276;
FWB#1:140

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

11 FORM PREPARED BY

NAME / TITLE
Susan G. Pearl, Project Co-ordinator

ORGANIZATION
P.G. Historical & Cultural Trust

DATE
March 1980

STREET & NUMBER
Calvert Mansion, 4811 Riverdale Rd.

TELEPHONE
779-2011

CITY OR TOWN
Riverdale

STATE
Maryland 20840

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

CHAIN OF TITLE

Langley Park (McCormick-Goodhart Mansion)

P.G. 65-7

2851:432
5 Aug 1963
Deed

Eudist Fathers to Teplin, Reines, Wolman & Foreman; 24.4538 acres Langley Park, as surveyed by Seybolt & George, Parcel L

1205:311
11 Jan 1950
Deed

From S.F. Kennedy, Y. Savoie & Albert D'Amours to Eudist Fathers; Parcel 1, 24.996 acres sold by trustee Evans to D'Amours

926:171
24 Mar 1947
Deed

From Joshua Evans, Jr., trustee for McCormick-Goodharts to Albert D'Amours; Parcel 1 (24.996 acres) including Mansion, outbuildings and lake; same as first tract in Deed 169:276

375:243
12 Dec 1931
Deed

From Henrietta McCormick-Goodhart, widow, to Leander and Frederick H. McCormick-Goodhart tenants in common, 231 acres

169:276
1 Jan 1921
Deed

W. Bladen Jackson et al to Frederick E. and Henrietta McCormick-Goodhart; Parcel #1, part of Elizabeth's Delight, 231 acres, being part of the land conveyed to B.L. and W.B. Jackson
EWB#1:140

EWB#1:140

From John B. King and Dionysius Sheriff, trustees, to Benjamin L. Jackson and William B. Jackson; King and Sheriff having been appointed trustees in Equity case (1852) John B. King et al vs. James R. King

PG: #65-7

P. 448

1700484704

MARYLAND HISTORICAL TRUST

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Langley Park

AND/OR COMMON

McCormick-Goodhart Mansion

2 LOCATION

STREET & NUMBER

15th Ave. off University Blvd.

CITY, TOWN

Langley Park

CONGRESSIONAL DISTRICT

— VICINITY OF

STATE

Maryland

COUNTY

Prince George's

3 CLASSIFICATION

CATEGORY

- DISTRICT
- BUILDING(S)
- STRUCTURE
- SITE
- OBJECT

OWNERSHIP

- PUBLIC
- PRIVATE
- BOTH
- PUBLIC ACQUISITION**
- IN PROCESS
- BEING CONSIDERED

STATUS

- OCCUPIED
- UNOCCUPIED
- WORK IN PROGRESS
- ACCESSIBLE
- YES: RESTRICTED
- YES: UNRESTRICTED
- NO

PRESENT USE

- AGRICULTURE
- COMMERCIAL
- EDUCATIONAL
- ENTERTAINMENT
- GOVERNMENT
- INDUSTRIAL
- MILITARY
- MUSEUM
- PARK
- PRIVATE RESIDENCE
- RELIGIOUS
- SCIENTIFIC
- TRANSPORTATION
- OTHER

4 OWNER OF PROPERTY

(apt. complex-bldg.)

NAME

Willowbrook Apartments

Telephone #:

STREET & NUMBER

CITY, TOWN

Langley Park

— VICINITY OF

STATE, zip code

Maryland

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

Prince George's County Courthouse

Liber #:

Folio #:

STREET & NUMBER

CITY, TOWN

Upper Marlboro

STATE

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

—FEDERAL —STATE —COUNTY —LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

CONDITION		CHECK ONE	CHECK ONE
<input checked="" type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input checked="" type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This is a massive, Georgian Revival, brick structure-built as an estate in the 1920's. The main house consists of 3 sections of similar proportions, each having 3 bays. The center section projects slightly, and is overshadowed by a massive, stone pedimented portico. The use of light-colored stone for trim appears in the water-table, pilasters, keystones, and balustraded porches.

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

This was originally part of Burgundy Farm (owned by the Jackson family for generations.) The old Jackson farmhouse was bought by the McCormick-Goodharts and remodelled in 1921, but burned down a year later. They then proceeded to build the present mansion, which served as their estate for years. They named it Langley Park, after the original Goodhart estate in Beckenham, England. Although English, they were related to Cyrus McCormick, American inventor of the reaper. The mansion was designed by architect George Oakley Totter, Jr., and completed in 1924. A religious order used the building for its headquarters from the 1940's to the 1960's. The place is now a community building for the Willowbrook Apt. Complex. It is one of the few remaining Prince George's Co. estates of the 1920's era.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

- 1) AMERICAN ARCHITECT, (May 20, 1926), article with photos and floor plans.
- 2) WASHINGTON STAR, (June 19, 1964), real estate article.
- 3) THE NEWS-LEADER, Laurel, Md. (Aug. 29, 1963; Jan. 20, 1966).

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE _____ COUNTY _____

STATE _____ COUNTY _____

11 FORM PREPARED BY

NAME / TITLE

Michael F. Dwyer, Senior Park Historian

ORGANIZATION

M-NCPPC

DATE

8/20/75

STREET & NUMBER

8787 Georgia Ave.

TELEPHONE

589-1480

CITY OR TOWN

Silver Spring

STATE

Maryland


The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.


The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
 The Shaw House, 21 State Circle
 Annapolis, Maryland 21401
 (301) 267-1438

PG:65-7

MC CORMICK-GOODHART
MANSION (65-7)





LANGLEY PARK

1481

LANGLEY PARK/
MCCORMICK
SCHOOL
R-R
6777

R-35

R-18

AVE

R-55
15TH

R-55

LANGLEY

HAMPSHIRE
ESTATES

1257

C-1

PARCEL 'B'
LANGLEY
PARK
2448

LANGLEY PARK

PARCEL 'L'

4972

R-18

PG. 65-7

LANGLEY PARK

1482

C-2

LANGLEY PARK

1483

PARCEL I

2561

R-55

LEBANON

LANGLEY P

1656-A

UNIVERSITY

EL A

12

BOULEVARD

14TH

15TH

16TH

17TH

18TH

19TH

20TH

21TH

22TH

23TH

24TH

25TH

26TH

27TH

28TH

29TH

30TH

31TH

32TH

33TH

34TH

35TH

36TH

C-0

IRE GARDENS

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

GEO. A. GUIDE

1858

PAR. B

LANGLEY ACRE

6964

P. A

PLAZA
MAYOR

LTD PARTNERSHIP

5935/715

4.76

P.73

193

5797/562

0.04

P.74

R-10

LANGLEY PARK

2693

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

COHEN BROS.
PROPERTY

124069

'C'

BOARD OF ED.

1468-213

9.84 A.

P.75

R-55

UNIVERSITY
PLAZA

7452

8403

6977

2972

CAROLE HIGHLANDS

PARCEL A

650

R-10

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

Washington East

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY



5562 11 SE
(KENSINGTON)

77°00' 327 328000m E. 329 330 57°30'



65-12

65-10

57°30'

Handwritten notes: 65-4, 65-5, 65-6, 65-7, 65-8, 65-9

Handwritten note: 65-1

Handwritten note: 65-8

Handwritten note: 65-11



P.G. #65-7

Langley Park
Prince George's County
Susan G. Pearl
February 1987
North Elevation, detail
Neg: Md. Hist. Trust, Annapolis, Md.



P.G.#65-7

Langley Park
Prince George's County
Susan G. Pearl
February 1987
North Elevation
Neg: Md. Hist. Trust, Annapolis, Md.



P.G. #65-7

Langley Park
Prince George's County
Susan G. Pearl
February 1987
South Elevation, detail
Neg: Md. Hist. Trust, Annapolis, Md.



P.G. #65-7

Langley Park
Prince George's County
Susan G. Pearl
February 1987
South Elevation
Neg: Md. Hist, Trust, Annapolis, Md.

PG:65-7
Langley Park (McCormick-Goodhart Mansion)
8151 15th Avenue, Langley Park
5/27/2010 by CASA de Maryland
Front Façade



Night view of west wing after restoration



PG:65-7
Langley Park (McCormick-Goodhart Mansion)
8151 15th Avenue, Langley Park
5/27/2010 by CASA de Maryland
Front pediment after restoration



Main stair after restoration

