

PRINCE GEORGE'S COUNTY
HISTORIC SITE SUMMARY SHEET

Survey #: P.G. #73-8 Building Date: ca. 1880

Building Name: Anderson-Beall Farm

Location: 10001 Ardwick-Ardmore Road, Landover, Maryland

Private/Residence/Unoccupied/Deteriorated/Inaccessible

Description

The Anderson-Beall farm is located at the end of a long hemlock-lined farm lane on the south side of the old Ardwick Road. The farmstead consists of a dwelling house, two tobacco barns, a tenant house, and several small sheds. The dwelling is a three-bay-by-one-bay frame gable-roof house, with entrance in the central bay of the three-bay main north facade. Across the north and wrapping around the other elevations is a one-story porch which is supported by handsome posts: tapered and panelled wooden columns, square in section, which rest on high bases made of molded concrete blocks. The house is presently covered with brick-pattern asphalt shingle which is deteriorated in some places to reveal the German siding underneath. The doors and windows have plain board surrounds. The roof is of standing seam tin. There are two corbelled brick interior chimneys at the ridge, flanking the central passage. Across the south facade of the house is a one-story addition. There is a large gable-roof tobacco barn south of the house; it has wide vertical siding and rests on foundations of local iron-bearing sandstone. To the east is a smaller barn and a one-story tenant dwelling.

Significance

The Anderson-Beall house is typical of the vernacular farm dwellings of the late nineteenth century. It was constructed circa 1880 by William Anderson on part of a tract called Three Sisters which he purchased from heirs of the Hilleary family. This was the site of the ancient homestead of the Hilleary family. It is probable that the old dwelling was destroyed, or simply replaced after Anderson purchased the 165-acre farm in 1877, for he built his house on the slope of the hill, slightly north of the old house site. William Anderson died in 1906, and the farm passed to his son, who retained the farm until 1921. It was probably during this period that the handsome wraparound porch was constructed. Owned since that time by members of the Beall family, it has been a tenant dwelling for many years. The barn is relatively recent but may rest on older foundations; the house, which has suffered damage from fire, is not occupied. This was a typical I-house, which has been varied by the early twentieth century porch.

Acreage: 68.23 acres

Survey No. P.G. #73-8

Magi No.

DOE yes no

Maryland Historical Trust State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic Anderson-Beall House and Farm

and/or common indicated in 1974 survey as Wheeler House

2. Location

street & number 10001 Ardwick Ardmore Road not for publication

city, town Landover vicinity of congressional district 5

state Maryland county Prince George's County

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input checked="" type="checkbox"/> unoccupied	<input type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input checked="" type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name William P. Beall, Robert L. Beall, et. al.

street & number 900 Brightseat Road telephone no.:

city, town Landover state and zip code Maryland 20785

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse liber Estate file

street & number Main Street folio 18658

city, town Upper Marlboro state Maryland 20772

6. Representation in Existing Historical Surveys

title Prince George's County Inventory of Historic Sites

date 1974 federal state county local

depository for survey records P.G. Co. Historic Preservation Commission c/o M-NCPPC

city, town Upper Marlboro state Maryland 20772

7. Description

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input checked="" type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date of move _____
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Anderson-Beall farm is located at the end of a long hemlock-lined farm lane on the south side of the old Ardwick Road. The farmstead consists of a dwelling house, two tobacco barns, and a small tenant house.

The dwelling house is a two-and-one-half story, three-bay-by-one-bay frame gable-roof house, with entrance in the central bay of the three-bay main north facade. A one-story porch shelters this north facade, and wraps around the east, west, and part of the south elevation. This porch is supported by handsome posts: tapered and panelled wooden columns, square in section, which rest on high bases made of molded concrete block with egg-and-dart molding. The porch is partly enclosed on the north facade. The house is presently covered with brick-pattern asphalt shingle which is deteriorated in some places to reveal the German siding underneath. Windows are 6/6 double hung sash, and have plain board surrounds. The roof is of standing seam tin. There are two corbelled brick interior chimneys at the ridge, flanking the central passage. Across the west half of the rear (south) facade is a one-story addition, a one-bay-deep shed-roof utility room and bath. The brick foundation encloses a full unfinished basement.

Interior plan of the house is that of a traditional I-house: central stairhall flanked by one parlor on each side. The open-string staircase rises along the west wall of the stairhall, turns 90° again and rises to a small hall space on the second story. The ghost of a staircase on that second story wall indicates that the stair once continued to loft level. The stair has a turned newel, and turned balusters, and the stairends are plain. The plain spandrel is plastered, enclosing the stairs to the basement.

Surrounds of doors and windows are of multi-band molding, bold cyma reversa and torus moldings bounded by a plain backband. The west parlor has been converted into a kitchen space, and the fireplace in the interior wall has been replaced by a stove pipe. The handsome Victorian wood mantel in the east parlor, however, is intact. It has applied decorative panels on both frieze and pilasters, and a curved shelf. Interior doors have four panels, while exterior doors have six.

Southeast of the house, accessible by the unpaved farm lane is a large gable-roof tobacco barn. It has wide vertical board siding, and opening on the north gable end. Sill beams of the barn are pegged

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM

Survey No. P.G.#73-8

Description (continued)

Section 7 Page 2

together with Z shaped joint, but most members appear to be circular sawn. The barn rests on a foundation of local iron-bearing stone; a wide side aisle has been added in the west, built on a lower level, on a platform of stone. The stone foundations on which the main part of the barn stands are clearly visible inside this westerly addition; the size and condition of this foundation suggest that it may have supported an earlier building.

East of this barn is a smaller gable-roof tobacco barn with entrance in the north gable end. This smaller tobacco barn is covered with vertical board siding and rests on a concrete block foundation. Its members are circular sawn and joined by nails. Both barns have metal roofs.

North of the easterly barn is a small front-gabled one-story tenant dwelling. Entrance is in the three-bay south gable end, through an off-center door flanked by small 1/1 windows. The building is sheathed with brick-pattern asphalt shingle, and the roof is covered with tar paper. Plain board surrounds frame the doors and windows in the four-room interior.

The hemlock-lined drive leads south from Ardwick-Ardmore Road, and forks as it ascends the hill where the buildings stand. One branch bends to the east past the tenant house and leads to the barns; the other bends to the west around the rear of the main dwelling. Several large trees, both evergreen and deciduous, frame the main dwelling.

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input checked="" type="checkbox"/> other (specify)
		<input type="checkbox"/> invention		Local History

Specific dates ca. 1880 **Builder/Architect**

check: Applicable Criteria: A B C D
and/or
Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Anderson-Beall House is an example of a typical vernacular farm dwelling of the late nineteenth century: a frame I-house (central passage with a parlor on each side). It was constructed circa 1880 by William Anderson on part of a tract called Three Sisters. This was the site of the ancient homestead of the Hilleary family,¹ a 30 by 24 foot frame dwelling of the eighteenth century which had been the home of Tilghman Hilleary, Sarah Hilleary and a second Tilghman Hilleary.²

In 1877 William Anderson purchased from the heirs of the Hilleary family approximately 200 acres of Three Sisters and adjoining woodland.³ It is probable that the old Hilleary dwelling was destroyed, or simply replaced, after Anderson's purchase. (It is possible that the heavy stone foundation of the larger tobacco barn, sited at the highest elevation on the property, once supported the early frame dwelling of Tilghman Hilleary.) Within a few years, Anderson had built his modest I-house on the slope of the hill, slightly north of the old house site. In the 1890's, Anderson was assessed for a modest but substantial house, barn and outbuildings.⁴

William Anderson died (apparently in a railroad accident) in 1906, and the farm passed to his son, William O. Anderson, who retained the farm until 1921.⁵ It was probably during this period that the handsome wrap-around porches was constructed around the house. It was purchased in 1938 by J. B. and Mildred Beall and became their family home, as well as the scene of local political meetings. When Mildred Beall died in 1963, the property was described as "improved by a two-story detached dwelling of seven rooms. Condition very poor. Further improved by a one-story frame tenant dwellingtwo large barns and three small barns."⁶ Owned by Mrs. Beall's heirs since that time, the farm has been a tenant property, and has been operated as a sod farm. The main dwelling house has suffered damage from fire, and is in deteriorating condition. Neither it nor the small tenant house is presently occupied.

The Anderson-Beall House was typical of the modest I-house form popular in late-nineteenth century Prince George's County. It can be compared to several other I-houses identified in recent surveys. The Donaldson House (#62-2) is a very modest I-house built ca. 1896 in the Victorian subdivision of Oakcrest. The Charles S. Early, Sr. House (#85B-10) was built in Brandywine in the 1870's, and has considerably more Victorian decorative detail than the Anderson-Beall House; it differs also in that it has flush chimneys in the gable ends. The Franklin Pierce House (#70-4), built in Seabrook in 1907 to replace an earlier house destroyed by fire, is similar in its modest form to the Anderson-Beall House, but has a central crossgable which varies its main facade. Unlike the Anderson-Beall House, all three of these I-houses have rear kitchen ells.⁷ The Anderson-Beall House was a typical late nineteenth century I-house, made unusual by the addition of the early twentieth century wraparound porch.

Notes

- 1 Descendants of Thomas Hilleary, to whom the 1,050-acre Three Sisters tract was patented in 1683.
- 2 Federal District Tax, Collington and Western Branch Hundreds, 1978; cf. also "Three Sisters", P.G. #73-2; these were two of five small frame dwellings which stood on the Three Sisters tract at the time of the 1798 tax assessment.
- 3 Prince George's County Deed ATB #1:198.
- 4 Prince George's County Tax Assessments, 1880's-1900.
- 5 Prince George's County Estate file #2077; cf. chain of title.
- 6 Prince George's County Estate file #14714.
- 7 See MHT forms P.G. #62-2, #70-4, #85B-10.

9. Major Bibliographical References

Survey No. P.G. #73-8

cf. Chain of Title
cf. Notes, Item #8

10. Geographical Data

Acreeage of nominated property 68.23 a

Tax map #60, p. 26

Quadrangle name Lanham, Md. Sec. D

Quadrangle scale 1:24,000

UTM References do NOT complete UTM references

A	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

C	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

D	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

E	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

F	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

G	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

H	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Susan G. Pearl, Research/Architectural Historian

organization P.G. Co. Historic Preservation Commission date Sept. 1985 and June 1988

street & number #4010 C.A.B. County Planning Div, M-NCPPG telephone 952-3521

city or town Upper Marlboro state Maryland 20772

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

PRINCE GEORGE'S COUNTY
HISTORIC SITE SUMMARY SHEET

Survey #: P.G. #73-8 Building Date: ca. 1880

Building Name: Anderson-Beall Farm

Location: 10001 Ardwick-Ardmore Road, Landover, Maryland

Private/Residence/Unoccupied/Deteriorated/Inaccessible

Description

The Anderson-Beall farm is located at the end of a long hemlock-lined farm lane on the south side of the old Ardwick Road. The farmstead consists of a dwelling house, two tobacco barns, a tenant house, and several small sheds. The dwelling is a three-bay-by-one-bay frame gable-roof house, with entrance in the central bay of the three-bay main north facade. Across the north and wrapping around the other elevations is a one-story porch which is supported by handsome posts: tapered and panelled wooden columns, square in section, which rest on high bases made of molded concrete blocks. The house is presently covered with brick-pattern asphalt shingle which is deteriorated in some places to reveal the German siding underneath. The doors and windows have plain board surrounds. The roof is of standing seam tin. There are two corbelled brick interior chimneys at the ridge, flanking the central passage. Across the south facade of the house is a one-story addition. There is a large gable-roof tobacco barn south of the house; it has wide vertical siding and rests on foundations of local iron-bearing sandstone. To the east is a smaller barn and a one-story tenant dwelling.

Significance

The Anderson-Beall house is typical of the vernacular farm dwellings of the late nineteenth century. It was constructed circa 1880 by William Anderson on part of a tract called Three Sisters which he purchased from heirs of the Hilleary family. This was the site of the ancient homestead of the Hilleary family. It is probable that the old dwelling was destroyed, or simply replaced after Anderson purchased the 165-acre farm in 1877, for he built his house on the slope of the hill, slightly north of the old house site. William Anderson died in 1906, and the farm passed to his son, who retained the farm until 1921. It was probably during this period that the handsome wraparound porch was constructed. Owned since that time by members of the Beall family, it has been a tenant dwelling for many years. The barn is relatively recent but may rest on older foundations; the house, which has suffered damage from fire, is not occupied. This was a typical I-house, which has been varied by the early twentieth century porch.

Acreage: 68.23 acres

Maryland Historical Trust State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic Anderson-Beall House and Farm

and/or common indicated in 1974 survey as Wheeler House

2. Location

street & number 10001 Ardwick Ardmore Road not for publication

city, town Landover vicinity of congressional district 5

state Maryland county Prince George's County

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture <input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input checked="" type="checkbox"/> unoccupied	<input type="checkbox"/> commercial <input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational <input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment <input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government <input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial <input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military <input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name William P. Beall, Robert L. Beall, et. al.

street & number 900 Brightseat Road telephone no.:

city, town Landover state and zip code Maryland 20785

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse liber Estate file

street & number Main Street folio 18658

city, town Upper Marlboro state Maryland 20772

6. Representation in Existing Historical Surveys

title Prince George's County Inventory of Historic Sites

date 1974 federal state county local

depository for survey records P.G. Co. Historic Preservation Commission c/o M-NCPPC

city, town Upper Marlboro state Maryland 20772

7. Description

Survey No. P.G.#73-8

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input checked="" type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed		date of move _____

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Anderson-Beall farm is located at the end of a long hemlock-lined farm lane on the south side of the old Ardwick Road. The farmstead consists of a dwelling house, two tobacco barns, and a small tenant house.

The dwelling house is a two-and-one-half story, three-bay-by-one-bay frame gable-roof house, with entrance in the central bay of the three-bay main north facade. A one-story porch shelters this north facade, and wraps around the east, west, and part of the south elevation. This porch is supported by handsome posts: tapered and panelled wooden columns, square in section, which rest on high bases made of molded concrete block with egg-and-dart molding. The porch is partly enclosed on the north facade. The house is presently covered with brick-pattern asphalt shingle which is deteriorated in some places to reveal the German siding underneath. Windows are 6/6 double hung sash, and have plain board surrounds. The roof is of standing seam tin. There are two corbelled brick interior chimneys at the ridge, flanking the central passage. Across the west half of the rear (south) facade is a one-story addition, a one-bay-deep shed-roof utility room and bath. The brick foundation encloses a full unfinished basement.

Interior plan of the house is that of a traditional I-house: central stairhall flanked by one parlor on each side. The open-string staircase rises along the west wall of the stairhall, turns 90° again and rises to a small hall space on the second story. The ghost of a staircase on that second story wall indicates that the stair once continued to loft level. The stair has a turned newel, and turned balusters, and the stairends are plain. The plain spandrel is plastered, enclosing the stairs to the basement.

Surrounds of doors and windows are of multi-band molding, bold cyma reversa and torus moldings bounded by a plain backband. The west parlor has been converted into a kitchen space, and the fireplace in the interior wall has been replaced by a stove pipe. The handsome Victorian wood mantel in the east parlor, however, is intact. It has applied decorative panels on both frieze and pilasters, and a curved shelf. Interior doors have four panels, while exterior doors have six.

Southeast of the house, accessible by the unpaved farm lane is a large gable-roof tobacco barn. It has wide vertical board siding, and opening on the north gable end. Sill beams of the barn are pegged

together with Z shaped joint, but most members appear to be circular sawn. The barn rests on a foundation of local iron-bearing stone; a wide side aisle has been added in the west, built on a lower level, on a platform of stone. The stone foundations on which the main part of the barn stands are clearly visible inside this westerly addition; the size and condition of this foundation suggest that it may have supported an earlier building.

East of this barn is a smaller gable-roof tobacco barn with entrance in the north gable end. This smaller tobacco barn is covered with vertical board siding and rests on a concrete block foundation. Its members are circular sawn and joined by nails. Both barns have metal roofs.

North of the easterly barn is a small front-gabled one-story tenant dwelling. Entrance is in the three-bay south gable end, through an off-center door flanked by small 1/1 windows. The building is sheathed with brick-pattern asphalt shingle, and the roof is covered with tar paper. Plain board surrounds frame the doors and windows in the four-room interior.

The hemlock-lined drive leads south from Ardwick-Ardmore Road, and forks as it ascends the hill where the buildings stand. One branch bends to the east past the tenant house and leads to the barns; the other bends to the west around the rear of the main dwelling. Several large trees, both evergreen and deciduous, frame the main dwelling.

8. Significance

Survey No. P.G.#73-8

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input checked="" type="checkbox"/> other (specify: Local History)

Specific dates ca. 1880 Builder/Architect

check: Applicable Criteria: A B C D
and/or

Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Anderson-Beall House is an example of a typical vernacular farm dwelling of the late nineteenth century: a frame I-house (central passage with a parlor on each side). It was constructed circa 1880 by William Anderson on part of a tract called Three Sisters. This was the site of the ancient homestead of the Hilleary family,¹ a 30 by 24 foot frame dwelling of the eighteenth century which had been the home of Tilghman Hilleary, Sarah Hilleary and a second Tilghman Hilleary.²

In 1877 William Anderson purchased from the heirs of the Hilleary family approximately 200 acres of Three Sisters and adjoining woodland.³ It is probable that the old Hilleary dwelling was destroyed, or simply replaced, after Anderson's purchase. (It is possible that the heavy stone foundation of the larger tobacco barn, sited at the highest elevation on the property, once supported the early frame dwelling of Tilghman Hilleary.) Within a few years, Anderson had built his modest I-house on the slope of the hill, slightly north of the old house site. In the 1890's, Anderson was assessed for a modest but substantial house, barn and outbuildings.⁴

William Anderson died (apparently in a railroad accident) in 1906, and the farm passed to his son, William O. Anderson, who retained the farm until 1921.⁵ It was probably during this period that the handsome wrap-around porches was constructed around the house. It was purchased in 1938 by J. B. and Mildred Beall and became their family home, as well as the scene of local political meetings. When Mildred Beall died in 1963, the property was described as "improved by a two-story detached dwelling of seven rooms. Condition very poor. Further improved by a one-story frame tenant dwellingtwo large barns and three small barns."⁶ Owned by Mrs. Beall's heirs since that time, the farm has been a tenant property, and has been operated as a sod farm. The main dwelling house has suffered damage from fire, and is in deteriorating condition. Neither it nor the small tenant house is presently occupied.

The Anderson-Beall House was typical of the modest I-house form popular in late-nineteenth century Prince George's County. It can be compared to several other I-houses identified in recent surveys. The Donaldson House (#62-2) is a very modest I-house built ca. 1896 in the Victorian subdivision of Oakcrest. The Charles S. Early, Sr. House (#85B-10) was built in Brandywine in the 1870's, and has considerably more Victorian decorative detail than the Anderson-Beall House; it differs also in that it has flush chimneys in the gable ends. The Franklin Pierce House (#70-4), built in Seabrook in 1907 to replace an earlier house destroyed by fire, is similar in its modest form to the Anderson-Beall House, but has a central crossgable which varies its main facade. Unlike the Anderson-Beall House, all three of these I-houses have rear kitchen ells.⁷ The Anderson-Beall House was a typical late nineteenth century I-house, made unusual by the addition of the early twentieth century wraparound porch.

Notes

- 1 Descendants of Thomas Hilleary, to whom the 1,050-acre Three Sisters tract was patented in 1683.
- 2 Federal District Tax, Collington and Western Branch Hundreds, 1798; cf. also "Three Sisters", P.G. #73-2; these were two of five small frame dwellings which stood on the Three Sisters tract at the time of the 1798 tax assessment.
- 3 Prince George's County Deed ATB #1:198.
- 4 Prince George's County Tax Assessments, 1880's-1900.
- 5 Prince George's County Estate file #2077; cf. chain of title.
- 6 Prince George's County Estate file #14714.
- 7 See MHT forms P.G. #62-2, #70-4, #85B-10.

Chain of Title

William Anderson House
P.G. #73-8

GSMcG #4:346
20 Aug 1968
Will
(Estate #18658) Evelyn L. Beane, who died 1 Jul 1968, devised her estate to her husband, Frederick B. Beane, Sr.; deceased's real estate consisted of a one-ninth undivided interest in approximately 110 acres in Landover.

WDA #11:599
5 Mar 1963
Will Mildred G. Beall, who died 7 Nov 1962, devised 110 acres in Landover to her children, one-third to her sons William P. and Paul F. Beall and two-thirds to Carleton G. Beall, Evelyn L. Beane, Lois Flexner, Robert L. Beall, Alvin J. Beall and J. Bernard Beall, her other children.

#502:89
1 Jan 1938
Deed For \$9,000, Harry and Madeline Berger to J. Bernard and Mildred G. Beall, as tenants by the entireties; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrews and Three Sisters; same which grantors acquired by #178:150 and #301:517.

#178:150
10 Dec 1921
Deed For \$8,750, Adelaide and William O. Anderson to Harry Berger; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrew and Three Sisters (excepting 50 acres conveyed in 1921 to Edmund Robbins); same which grantors acquired by #79:384.

#79:384
28 Mar 1913
Deed Emma S. Collins to Adelaide Anderson; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrew and Three Sisters; same which was conveyed to William Anderson by ATB #1:198.

#79:382
28 Mar 1913
Deed William O. and Adelaide Anderson to Emma S. Collins; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrew and Three Sisters; part of the land conveyed to William Anderson by ATB #1:198.

#83:77
11 Jun 1912
Deed John H. Anderson, Armour C. Anderson, both unmarried, and Mary J. Watts, widow, all of Denver, children and heirs of William Anderson, deceased, to William O. Anderson; all their rights in their father's 127 1/4 acres tract in Kent District, plus their rights in the one-sixth share which was conveyed to him by Katie Anderson, the wife of Alexander; part of the land conveyed by ATB #1:198.

#83:52
10 June 1912
Deed Alexander M. Anderson, son and heir of William Anderson, to William O. Anderson, one-sixth undivided portion of 127 1/2 acres in Kent District, plus his right to the one-sixth undivided portion of Lewis R. Anderson, now deceased, part of the lands conveyed by ATB #1:198.

- 2 -

Admin #2428 1912 Estate of Lewis R. Anderson who died intestate 31 Oct 1911; deceased possessed a 1/6 undivided interest in the property of William Anderson.

#83:42 11 Dec 1911 Deed For \$25, Katie Anderson, wife of Alexander M. Anderson, to Armour C. Anderson; 2 lots in Kent Election District called Three Sisters, now sometimes known as Myrtle Hill and Warren's Lot; all the grantor's interest or claim through inheritance as the wife of Alexander M. Anderson to the lands conveyed to William Anderson by ATB #1:198.

Admin. #2077 1906 Estate of William Anderson who died intestate 15 Dec 1906; as his heirs, deceased left six children; John H. Anderson, Mary J. Watts, William O. Anderson, Armour C. Anderson, Lewis R. Anderson and Alexander M. Anderson; deceased possessed 125 acres called Three Sisters.

ATB #1:198 26 Jul 1877 Deed For \$3,000, Julian C. and Joseph R. Wheeler to William Anderson; two lots in Kent Election District, 164 3/4 acres called Three Sisters and 44 3/4 acres, a part of Warren's Lot; same which grantors acquired by HB #12:679.

HB #12:679 26 Jul 1877 Deed For \$3,500, Richard H. and Eugenia Magruder to Julia C. Wheeler, wife of Joseph R. Wheeler; 164 3/4 acres called Three Sisters, same which was conveyed to grantors by Harrison Wallis, sheriff, and 44-3/4 acres of which Sallie O. Hilleary died possessed, both being referred to in No. 6 Judicials to the June Term 1875 of the Circuit Court.

HB #11:524 19 Sept 1876 Deed For \$1,183, Harrison Wallis, sheriff, to Richard H. Magruder; 160 acres known as Three Sisters, on which Leonard Hilleary resided, and 40 acres of woodland known as Warren's Lot; sheriff exposed property to public sale to satisfy judgment levied by Circuit Court on 3 Jan 1873 against Leonard Hilleary, in a suit brought by William H. Tuck.

WAJ #1:253 16 Jun 1863 Will Estate of Tilghman Hilleary who died 9 Apr 1863; deceased left his real estate, known as Three Sisters and Waring's Lot, to his wife Louisa McTavish Hilleary; (will is in Administration #620 which mentions a Circuit Court case - Leonard Hilleary vs Louisa Hilleary and Daniel Clarke - involving the real estate of Tilghman Hilleary).

FS #1:536 27 Mar 1863 Deed Tilghman Hilleary to Daniel Clarke; Three Sisters on which Tilghman Hilleary now resides, and tract of woodland adjoining known as Waring's Lot; being the same real estate devised to grantor by the will of Sarah O. Hilleary, deceased.

- 3 -

FS #1:535 Daniel Clarke to Tilghman Hilleary; Three Sisters on which
27 Mar 1863 Tilghman Hilleary now resides, and tract of woodland
Deed adjoining known as Waring's Lot; being the same real estate
devised to grantor by the will of Sarah O. Hilleary,
deceased.

PC #1:472 Testator, Sarah O. Hilleary; all real estate in Maryland to
20 Sept 1851 her nephew, Tilghman Hilleary; (if Tilghman died before her
Will nephew, Leonard Hilleary, leaving no issue, then the real
estate descended to Leonard and his heirs.)

JBB #7:218 For \$20 an acre, C.C. Magruder, trustee by decree of Equity
5 Jul 1851 dated 11 Jul 1842, to Sarah O. Hilleary; 160 acres, part of
Deed Three Sisters, now in possession to Sarah O. Hilleary.

#616 Washington Hilleary et al vs Sarah O. Hilleary and William
11 Jul 1842 Hilleary, executors of Tilghman Hilleary; all parties were
Chancery heirs of Tilghman Hilleary, deceased, but under the
(Old Equity) deceased's will the defendants had been allotted special
privileges which made it impossible to settle the estate;
defendants were willing to waive their rights and all
parties were willing to accept the court decree to sell the
real estate involved; by decree 11 Jul 1842, C.C. Magruder
was appointed trustee to make sale; by private sale, lot
#3, 160 acres, was sold to Sarah O. Hilleary.

PC #1:38 Testator, Tilghman Hilleary; by a codicil added to his will
14 Mar 1837 15 Feb 1827, the deceased provided that the plantation on
Will which he resided was to be under the management of his
executors until his daughter, Sarah O. Hilleary, married or
died and then it was to be sold; Sarah was given sole
occupancy and control "of my present dwelling house."
After specific bequests, the rest of the deceased's estate
was to be divided into seven parts for distribution among
the heirs named, i.e., the children of his son, Clement T.
Hilleary, the children of his son, Thomas Hilleary, his
sons, Tilghman, William and Washington, and his daughters,
Sarah Hilleary and Mary Bowie.

PRINCE GEORGE'S COUNTY
HISTORIC SITE SUMMARY SHEET

Survey #: P.G. #73-8 Building Date: ca. 1880

Building Name: William Anderson Farm

Location: 10001 Ardwick-Ardmore Road, Landover, Maryland

Private/Residence/Occupied/Fair/Inaccessible

Description

The William Anderson farm is located at the end of a long hemlock lined farm lane on the south side of the old Ardwick road. The farmstead consists of a dwelling house, a large barn, a tenant house, and several small sheds. The dwelling house is a three-bay-by-one-bay frame gable-roofed house, with entrance in the central bay of the three-bay main north facade. Across the north is a one-story porch which is supported by handsome posts: tapered and panelled wooden columns, square in section, which rest on high bases made of molded concrete blocks. The house is presently covered with brick-pattern asphalt shingle which is deteriorated in some places to reveal the German siding underneath. The doors and windows have plain board surrounds. The roof is of standing seam tin. There are two corbelled brick interior chimneys at the ridge, flanking the central passage. Across the rear (south) facade of the house are two one-story additions: on the west, a one-bay-deep shed-roof storage room, and on the east a hip-roof porch supported by the posts similar to those on the front porch. There is a large gable-roofed barn south of the house; it has wide vertical siding (circular sawn), and rests on foundations of local iron-bearing sandstone.

Significance

The William Anderson House is an example of a typical vernacular farm dwelling of the late nineteenth century: a frame I-house (central passage with a parlor on each side). It was constructed circa 1880 by William Anderson on part of a tract called Three Sisters which he purchased from heirs of the Hilleary family. This was the site of the ancient homestead of the Hilleary family, a frame dwelling of the eighteenth century. It is probable that the old dwelling was destroyed, or simply replaced after Anderson purchased the 165-acre farm in 1877, for he built his house on the slope of the hill, slightly north of the old house site. In the 1890's he was assessed for a modest but substantial house, barn and outbuildings. William Anderson died in 1906, and the farm passed to his son, who retained the farm until 1921. It was probably during this period that the handsome porches were constructed on the front and back of the house. Owned since that time by members of the Beall family, it has been a tenant dwelling for many years. The barn, which is relatively recent but may rest on older foundations, is in use, but the house, which has suffered damage from fire, is not occupied. The farmstead is a noticeable landmark in a still rural area which is gradually being overtaken by development from the west.

Acreage: 68.23 acres

Magi No.

DOE yes no

Maryland Historical Trust State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic William Anderson Farm

and/or common indicated in 1974 survey as Wheeler House

2. Location

street & number 10001 Ardwick Ardmore Road not for publicationcity, town Landover vicinity of congressional district 5

state Maryland county Prince George's County

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name William P. Beall

street & number 900 Brightseat Road telephone no.:

city, town Landover state and zip code Maryland 20785

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse liber estate

street & number Mainstreet folio 18658

city, town Upper Marlboro state Maryland

6. Representation in Existing Historical Surveys

title Prince George's County Inventory of Historic Sites

date 1974 federal state county local

depository for survey records History Division, M-NCPPC

city, town Riverdale state Maryland

7. Description

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The William Anderson farm is located at the end of a long hemlock lined farm lane on the south side of the old Ardwick road. The farmstead consists of a dwelling house, a large barn, a tenant house, and several small sheds. The dwelling house is a three-bay-by-one-bay frame gable-roofed house, with entrance in the central bay of the three-bay main north facade. Across both the north and south facades is a one-story (screen-enclosed) porch which is supported by handsome posts: tapered and panelled wooden columns, square in section, which rest on high bases made of molded concrete blocks. The house is presently covered with brick-pattern asphalt shingle which is deteriorated in some places to reveal the German siding underneath. The doors and windows have plain board surrounds. The roof is of standing seam tin. There are two corbelled brick interior chimneys at the ridge, flanking the central passage. Across the rear (south) facade of the house are two one-story additions: on the west, a one-bay-deep shed-roof storage room, and on the east a hip-roof porch supported by the posts similar to those on the front porch.

There is a large gable-roofed barn to the rear (south) of the house; it has wide vertical siding (circular sawn), and rests on foundations of local iron-bearing sandstone.

9. Major Bibliographical References

Survey No. P.G. #73-8

cf. Chain of Title
cf. Notes, Item #8

10. Geographical Data

Acreage of nominated property 68.23 a

Tax map #60, p. 26

Quadrangle name Lanham, MD Sec. D

Quadrangle scale _____

UTM References do NOT complete UTM references

A	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

C	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

D	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

E	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

F	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

G	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

H	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Susan G. Pearl, Research Historian

organization Historic Preservation Commission date September 1985

street & number c/o County Planning Division, M-NCPPC telephone 952-3521

city or town Upper Marlboro state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

Chain of Title

William Anderson House P.G. #73-8

- GSMcG #4:346
20 Aug 1968
Will
(Estate #18658) Evelyn L. Beane, who died 1 Jul 1968, devised her estate to her husband, Frederick B. Beane, Sr.; deceased's real estate consisted of a one-ninth undivided interest in approximately 110 acres in Landover.
- WDA #11:599
5 Mar 1963
Will Mildred G. Beall, who died 7 Nov 1962, devised 110 acres in Landover to her children, one-third to her sons William P. and Paul F. Beall and two-thirds to Carleton G. Beall, Evelyn L. Beane, Lois Flexner, Robert L. Beall, Alvin J. Beall and J. Bernard Beall, her other children.
- #502:89
1 Jan 1938
Deed For \$9,000, Harry and Madeline Berger to J. Bernard and Mildred G. Beall, as tenants by the entireties; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrews and Three Sisters; same which grantors acquired by #178:150 and #301:517.
- #178:150
10 Dec 1921
Deed For \$8,750, Adelaide and William O. Anderson to Harry Berger; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrew and Three Sisters (excepting 50 acres conveyed in 1921 to Edmund Robbins); same which grantors acquired by #79:384.
- #79:384
28 Mar 1913
Deed Emma S. Collins to Adelaide Anderson; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrew and Three Sisters; same which was conveyed to William Anderson by ATB #1:198.
- #79:382
28 Mar 1913
Deed William O. and Adelaide Anderson to Emma S. Collins; 127 1/2 acres in Kent District, parts of Blackburn, St. Andrew and Three Sisters; part of the land conveyed to William Anderson by ATB #1:198.
- #83:77
11 Jun 1912
Deed John H. Anderson, Armour C. Anderson, both unmarried, and Mary J. Watts, widow, all of Denver, children and heirs of William Anderson, deceased, to William O. Anderson; all their rights in their father's 127 1/4 acres tract in Kent District, plus their rights in the one-sixth share which was conveyed to him by Katie Anderson, the wife of Alexander; part of the land conveyed by ATB #1:198.
- #83:52
10 June 1912
Deed Alexander M. Anderson, son and heir of William Anderson, to William O. Anderson, one-sixth undivided portion of 127 1/2 acres in Kent District, plus his right to the one-sixth undivided portion of Lewis R. Anderson, now deceased, part of the lands conveyed by ATB #1:198.

- 2 -

Admin #2428 1912 Estate of Lewis R. Anderson who died intestate 31 Oct 1911; deceased possessed a 1/6 undivided interest in the property of William Anderson.

#83:42 11 Dec 1911 Deed For \$25, Katie Anderson, wife of Alexander M. Anderson, to Armour C. Anderson; 2 lots in Kent Election District called Three Sisters, now sometimes known as Myrtle Hill and Warren's Lot; all the grantor's interest or claim through inheritance as the wife of Alexander M. Anderson to the lands conveyed to William Anderson by ATB #1:198.

Admin. #2077 1906 Estate of William Anderson who died intestate 15 Dec 1906; as his heirs, deceased left six children; John H. Anderson, Mary J. Watts, William O. Anderson, Armour C. Anderson, Lewis R. Anderson and Alexander M. Anderson; deceased possessed 125 acres called Three Sisters.

ATB #1:198 26 Jul 1877 Deed For \$3,000, Julian C. and Joseph R. Wheeler to William Anderson; two lots in Kent Election District, 164 3/4 acres called Three Sisters and 44 3/4 acres, a part of Warren's Lot; same which grantors acquired by HB #12:679.

HB #12:679 26 Jul 1877 Deed For \$3,500, Richard H. and Eugenia Magruder to Julia C. Wheeler, wife of Joseph R. Wheeler; 164 3/4 acres called Three Sisters, same which was conveyed to grantors by Harrison Wallis, sheriff, and 44-3/4 acres of which Sallie O. Hilleary died possessed, both being referred to in No. 6 Judicials to the June Term 1875 of the Circuit Court.

HB #11:524 19 Sept 1876 Deed For \$1,183, Harrison Wallis, sheriff, to Richard H. Magruder; 160 acres known as Three Sisters, on which Leonard Hilleary resided, and 40 acres of woodland known as Warren's Lot; sheriff exposed property to public sale to satisfy judgment levied by Circuit Court on 3 Jan 1873 against Leonard Hilleary, in a suit brought by William H. Tuck.

WAJ #1:253 16 Jun 1863 Will Estate of Tilghman Hilleary who died 9 Apr 1863; deceased left his real estate, known as Three Sisters and Waring's Lot, to his wife Louisa McTavish Hilleary; (will is in Administration #620 which mentions a Circuit Court case - Leonard Hilleary vs Louisa Hilleary and Daniel Clarke - involving the real estate of Tilghman Hilleary).

FS #1:536 27 Mar 1863 Deed Tilghman Hilleary to Daniel Clarke; Three Sisters on which Tilghman Hilleary now resides, and tract of woodland adjoining known as Waring's Lot; being the same real estate devised to grantor by the will of Sarah O. Hilleary, deceased.

- 3 -

- FS #1:535
27 Mar 1863
Deed
Daniel Clarke to Tilghman Hilleary; Three Sisters on which Tilghman Hilleary now resides, and tract of woodland adjoining known as Waring's Lot; being the same real estate devised to grantor by the will of Sarah O. Hilleary, deceased.
- PC #1:472
20 Sept 1851
Will
Testator, Sarah O. Hilleary; all real estate in Maryland to her nephew, Tilghman Hilleary; (if Tilghman died before her nephew, Leonard Hilleary, leaving no issue, then the real estate descended to Leonard and his heirs.)
- JBB #7:218
5 Jul 1851
Deed
For \$20 an acre, C.C. Magruder, trustee by decree of Equity dated 11 Jul 1842, to Sarah O. Hilleary; 160 acres, part of Three Sisters, now in possession to Sarah O. Hilleary.
- #616
11 Jul 1842
Chancery
(Old Equity)
Washington Hilleary et al vs Sarah O. Hilleary and William Hilleary, executors of Tilghman Hilleary; all parties were heirs of Tilghman Hilleary, deceased, but under the deceased's will the defendants had been allotted special privileges which made it impossible to settle the estate; defendants were willing to waive their rights and all parties were willing to accept the court decree to sell the real estate involved; by decree 11 Jul 1842, C.C. Magruder was appointed trustee to make sale; by private sale, lot #3, 160 acres, was sold to Sarah O. Hilleary.
- PC #1:38
14 Mar 1837
Will
Testator, Tilghman Hilleary; by a codicil added to his will 15 Feb 1827, the deceased provided that the plantation on which he resided was to be under the management of his executors until his daughter, Sarah O. Hilleary, married or died and then it was to be sold; Sarah was given sole occupancy and control "of my present dwelling house." After specific bequests, the rest of the deceased's estate was to be divided into seven parts for distribution among the heirs named, i.e., the children of his son, Clement T. Hilleary, the children of his son, Thomas Hilleary, his sons, Tilghman, William and Washington, and his daughters, Sarah Hilleary and Mary Bowie.

PG #73-8
1701635504

MARYLAND HISTORICAL TRUST

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Wheeler House

AND/OR COMMON

2 LOCATION

STREET & NUMBER

south side of Ardmore-Ardwick Road

CITY, TOWN

Lanham

___ VICINITY OF

CONGRESSIONAL DISTRICT

STATE

Maryland

COUNTY

Prince George's

3 CLASSIFICATION

CATEGORY

- DISTRICT
- BUILDING(S)
- STRUCTURE
- SITE
- OBJECT

OWNERSHIP

- PUBLIC
- PRIVATE
- BOTH
- PUBLIC ACQUISITION**
- IN PROCESS
- BEING CONSIDERED

STATUS

- OCCUPIED
- UNOCCUPIED
- WORK IN PROGRESS
- ACCESSIBLE**
- YES RESTRICTED
- YES UNRESTRICTED
- NO

PRESENT USE

- AGRICULTURE
- MUSEUM
- COMMERCIAL
- PARK
- EDUCATIONAL
- PRIVATE RESIDENCE
- ENTERTAINMENT
- RELIGIOUS
- GOVERNMENT
- SCIENTIFIC
- INDUSTRIAL
- TRANSPORTATION
- MILITARY
- OTHER

4 OWNER OF PROPERTY

NAME

William P. Beall et al (?)

Telephone #:

STREET & NUMBER

CITY, TOWN

___ VICINITY OF

STATE, zip code

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

Prince George's County Courthouse

Liber #:

Folio #:

STREET & NUMBER

CITY, TOWN

Upper Marlboro

STATE

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

___ FEDERAL ___ STATE ___ COUNTY ___ LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

DESCRIPTION

CONDITION

EXCELLENT DETERIORATED

GOOD RUINS

FAIR UNEXPOSED

CHECK ONE

UNALTERED

ALTERED

CHECK ONE

ORIGINAL SITE

MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This is an older, two-story farmhouse, in an abandoned state. It was not seen closely at the time of this inventory, but it appears to have three bays on its main (north) facade. There is a one-story porch across the front, and a central door. House is covered with fake-brick, asphalt siding. Windows have 2/2 sash. Twin, stove chimneys centered on roof ridge. There are several run-down farm buildings.

SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

A house on this site appears with the name "Wheeler" on Hopkins' 1878 Atlas. Before that period, this was a Hilleary property.

MAJOR BIBLIOGRAPHICAL REFERENCES

CONTINUE ON SEPARATE SHEET IF NECESSARY

GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	COUNTY

STATE	COUNTY

FORM PREPARED BY

NAME / TITLE

Michael F. Dwyer, Senior Park Historian

ORGANIZATION

M-NCPPC

DATE

9/25/73

STREET & NUMBER

8787 Georgia Ave.

TELEPHONE

589-1480

CITY OR TOWN

Silver Spring

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
 The Shaw House, 21 State Circle
 Annapolis, Maryland 21401
 (301) 267-1438

Chain of Title

William Anderson House
P.G. #73-8

GSMcG #4:346 Evelyn L. Beane, who died 1 Jul 1968, devised her estate to
20 Aug 1968 her husband, Frederick B. Beane, Sr.; deceased's real
Will estate consisted of a one-ninth undivided interest in
(Estate #18658) approximately 110 acres in Landover.

WDA #11:599 Mildred G. Beall, who died 7 Nov 1962, devised 110 acres in
5 Mar 1963 Landover to her children, one-third to her sons William P.
Will and Paul F. Beall and two-thirds to Carleton G. Beall,
Evelyn L. Beane, Lois Flexner, Robert L. Beall, Alvin J.
Beall and J. Bernard Beall, her other children.

#502:89 For \$9,000, Harry and Madeline Berger to J. Bernard and
1 Jan 1938 Mildred G. Beall, as tenants by the entireties; 127 1/2
Deed acres in Kent District, parts of Blackburn, St. Andrews and
Three Sisters; same which grantors acquired by #178:150 and
#301:517.

#178:150 For \$8,750, Adelaide and William O. Anderson to Harry
10 Dec 1921 Berger; 127 1/2 acres in Kent District, parts of Blackburn,
Deed St. Andrew and Three Sisters (excepting 50 acres conveyed
in 1921 to Edmund Robbins); same which grantors acquired by
#79:384.

#79:384 Emma S. Collins to Adelaide Anderson; 127 1/2 acres in Kent
28 Mar 1913 District, parts of Blackburn, St. Andrew and Three Sisters;
Deed same which was conveyed to William Anderson by ATB #1:198.

#79:382 William O. and Adelaide Anderson to Emma S. Collins; 127
28 Mar 1913 1/2 acres in Kent District, parts of Blackburn, St. Andrew
Deed and Three Sisters; part of the land conveyed to William
Anderson by ATB #1:198.

#83:77 John H. Anderson, Armour C. Anderson, both unmarried, and
11 Jun 1912 Mary J. Watts, widow, all of Denver, children and heirs of
Deed William Anderson, deceased, to William O. Anderson; all
their rights in their father's 127 1/4 acres tract in Kent
District, plus their rights in the one-sixth share which
was conveyed to him by Katie Anderson, the wife of
Alexander; part of the land conveyed by ATB #1:198.

#83:52 Alexander M. Anderson, son and heir of William Anderson, to
10 June 1912 William O. Anderson, one-sixth undivided portion of 127 1/2
Deed acres in Kent District, plus his right to the one-sixth
undivided portion of Lewis R. Anderson, now deceased, part
of the lands conveyed by ATB #1:198.

- 2 -

Admin #2428 1912 Estate of Lewis R. Anderson who died intestate 31 Oct 1911; deceased possessed a 1/6 undivided interest in the property of William Anderson.

#83:42 11 Dec 1911 Deed For \$25, Katie Anderson, wife of Alexander M. Anderson, to Armour C. Anderson; 2 lots in Kent Election District called Three Sisters, now sometimes known as Myrtle Hill and Warren's Lot; all the grantor's interest or claim through inheritance as the wife of Alexander M. Anderson to the lands conveyed to William Anderson by ATB #1:198.

Admin. #2077 1906 Estate of William Anderson who died intestate 15 Dec 1906; as his heirs, deceased left six children; John H. Anderson, Mary J. Watts, William O. Anderson, Armour C. Anderson, Lewis R. Anderson and Alexander M. Anderson; deceased possessed 125 acres called Three Sisters.

ATB #1:198 26 Jul 1877 Deed For \$3,000, Julian C. and Joseph R. Wheeler to William Anderson; two lots in Kent Election District, 164 3/4 acres called Three Sisters and 44 3/4 acres, a part of Warren's Lot; same which grantors acquired by HB #12:679.

HB #12:679 26 Jul 1877 Deed For \$3,500, Richard H. and Eugenia Magruder to Julia C. Wheeler, wife of Joseph R. Wheeler; 164 3/4 acres called Three Sisters, same which was conveyed to grantors by Harrison Wallis, sheriff, and 44-3/4 acres of which Sallie O. Hilleary died possessed, both being referred to in No. 6 Judicials to the June Term 1875 of the Circuit Court.


HB #11:524 19 Sept 1876 Deed For \$1,183, Harrison Wallis, sheriff, to Richard H. Magruder; 160 acres known as Three Sisters, on which Leonard Hilleary resided, and 40 acres of woodland known as Warren's Lot; sheriff exposed property to public sale to satisfy judgment levied by Circuit Court on 3 Jan 1873 against Leonard Hilleary, in a suit brought by William H. Tuck.

WAJ #1:253 16 Jun 1863 Will Estate of Tilghman Hilleary who died 9 Apr 1863; deceased left his real estate, known as Three Sisters and Waring's Lot, to his wife Louisa McTavish Hilleary; (will is in Administration #620 which mentions a Circuit Court case - Leonard Hilleary vs Louisa Hilleary and Daniel Clarke - involving the real estate of Tilghman Hilleary).

FS #1:536 27 Mar 1863 Deed Tilghman Hilleary to Daniel Clarke; Three Sisters on which Tilghman Hilleary now resides, and tract of woodland adjoining known as Waring's Lot; being the same real estate devised to grantor by the will of Sarah O. Hilleary, deceased.

- 3 -

- FS #1:535
27 Mar 1863
Deed
Daniel Clarke to Tilghman Hilleary; Three Sisters on which Tilghman Hilleary now resides, and tract of woodland adjoining known as Waring's Lot; being the same real estate devised to grantor by the will of Sarah O. Hilleary, deceased.
- PC #1:472
20 Sept 1851
Will
Testator, Sarah O. Hilleary; all real estate in Maryland to her nephew, Tilghman Hilleary; (if Tilghman died before her nephew, Leonard Hilleary, leaving no issue, then the real estate descended to Leonard and his heirs.)
- JBB #7:218
5 Jul 1851
Deed
For \$20 an acre, C.C. Magruder, trustee by decree of Equity dated 11 Jul 1842, to Sarah O. Hilleary; 160 acres, part of Three Sisters, now in possession to Sarah O. Hilleary.
- #616
11 Jul 1842
Chancery
(Old Equity)
Washington Hilleary et al vs Sarah O. Hilleary and William Hilleary, executors of Tilghman Hilleary; all parties were heirs of Tilghman Hilleary, deceased, but under the deceased's will the defendants had been allotted special privileges which made it impossible to settle the estate; defendants were willing to waive their rights and all parties were willing to accept the court decree to sell the real estate involved; by decree 11 Jul 1842, C.C. Magruder was appointed trustee to make sale; by private sale, lot #3, 160 acres, was sold to Sarah O. Hilleary.
- PC #1:38
14 Mar 1837
Will
Testator, Tilghman Hilleary; by a codicil added to his will 15 Feb 1827, the deceased provided that the plantation on which he resided was to be under the management of his executors until his daughter, Sarah O. Hilleary, married or died and then it was to be sold; Sarah was given sole occupancy and control "of my present dwelling house." After specific bequests, the rest of the deceased's estate was to be divided into seven parts for distribution among the heirs named, i.e., the children of his son, Clement T. Hilleary, the children of his son, Thomas Hilleary, his sons, Tilghman, William and Washington, and his daughters, Sarah Hilleary and Mary Bowie.



Dwelling

Tenant house

Tobacco barns

ANDERSON-BEALL FARM

PG#73-8

PG. 73-8

Site Plan

1" = 200'



•192

•149

150

150

175

14 A
P.150



R-E
R-R
MAP 53 P.59

TRA-E
ENT. INC.
5523/582
2.94 A.
P.188

HARRY T STUMPF
1118-168
8.22 A
P.149

R-R

ADAM E. CAPPELO
2309/292
22.80 A.
P.148


JAS. M. PRETTYMAN
3062 / 355
2.39 A.
P.9

R-80

JEERY W. BRADLEY
4502/253
3.90 A.
P.10

EARL R. ELLENBERGER
5758/970
8.10 A.
P.12

MAP 60
P.26



LYNDON B. JOHNSON
SENIOR HIGH SCHOOL

'A'

8623

MAP 53 P.58

LYNDON B. JOHNSON SENIOR HIGH
SCHOOL

'A'


8623

WILLIAM P. BEALL, ETAL
502/089
68.23 A.
P.26

PG: 73-8

MAP 61-
P.27

R-R



PG# 73-8

LANHAM





P. 73-8

Anderum - Boase Farm

Prince Georges Co. MD

Susan H. Pearl

June 1958

North elevation

Reg. Md. Hist. Trust,

Annapolis, MD.



Epilix

P₆ 73-8

Anderson. Beall Farm
Prince George's Co. MD.
Susan H. Pearl
June 1958
Montel, east parlor
Neg. Md. Hist. Thruout,
Annapolis, MD.



PG # 73 X

Anderson Beall Farm
Prince Georges Co. MD.
Susan H. Pearl
June 1988

Stair from northeast
Neg: Md. Heat. Thrust,
Annapolis, MD

Stair



PG #73-8

Anderson. Beall Larson
Princi Lungs Co. M.D.
Susan L. Pearl

June 1988

Interest Train

Neg: Md. Hist. Trust,
Annapolis, MD

Train



P.G. #73-8

William Anderson House
Prince George's County, MD.

Susan G. Pearl

April 1985

South elevation

Neg: Md. Hist. Trust, Annapolis, MD.



P.G. #73-8

William Anderson Farm

Prince George's County, MD.

Susan G. Pearl

April 1985

North elevation

Neg: Md. Hist. Trust, Annapolis, MD.



Pg #73-8

Anderson - Beale Farm
Prince Georges Co MD.

Susan H. Pearl

June 1988

Small detail.

Neg. Md. Hist. Trust,
Annapolis, MD

S. H. Pearl



NAME # 73-8 WHEELER HOUSE

LOCATION ARDMORE / ARDWICK Rd LANHAM, Md VIC

FACADE N

PHOTO TAKEN 9/25/73 MOWYER