

MARYLAND HISTORICAL TRUST
NR-ELIGIBILITY REVIEW FORM

NR Eligible: yes
no

Property Name: Glendale/Foster House Inventory Number: T-1139

Address: 30485 Matthewstown Road City: Easton Zip Code: _____

County: Talbot USGS Topographic Map: Easton

Owner: James Foster

Tax Parcel Number: 29 Tax Map Number: 26 Tax Account ID Number: 155734

Project: Harrison Tower Agency: FCC

Site visit by MHT Staff: no yes Name: _____ Date: _____

Eligibility recommended Eligibility not recommended

Criteria: A B C D Considerations: A B C D E F G None

Is the property located within a historic district? no yes Name of district: Goldsborough Farms Rural Historic Landscape

Is district listed? no yes Determined eligible? no yes District Inventory Number: _____

Documentation on the property/district is presented in:

Description of Property and Eligibility Determination: *(Use continuation sheet if necessary and attach map and photo)*

This property is a farmstead located south of Matthewstown Road and west of Mullet Branch Road. Entry to the property is via unsurfaced drives terminating at both roads. The farmstead covers an area of 158.2 acres and consists of a house, agricultural outbuildings, and equine riding pens.

This property is a large farmstead that during the nineteenth century was known as "Lark's Discovery" (Talbot County Deed Book 85: 255). Originally owned by the Goldsborough family, the property appears to have been developed during the ownership of Henry H. Goldsborough (1859-1878). The house at the property is illustrated in the 1877 atlas map of Talbot County (Lake 1877). In 1878, Henry H. Goldsborough sold the farm to William McQuaker. According to the deed transferring the title from Goldsborough to McQuaker, the sale was for "a farm or plantation known as 'Lark's Discovery'" (Talbot County Deed Book 85: 255). The property — 190 acres — was sold several times following the 1878 transaction. By 1895, the farm appears to have been renamed "Glendale" (Talbot County Deed Book 122: 435).

Prepared by: David S. Rotenstein

Date Prepared: January 2001

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended <input checked="" type="checkbox"/>	Eligibility not recommended <input type="checkbox"/>
Criteria: <input type="checkbox"/> A <input checked="" type="checkbox"/> B <input checked="" type="checkbox"/> C <input type="checkbox"/> D	Considerations: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input type="checkbox"/> None
Comments: <u>As a contributing resource to the Goldsborough Rural District</u>	
<u>David S. Rotenstein</u> Reviewer, Office of Preservation Services	<u>2/15/2001</u> Date
<u>[Signature]</u> Reviewer, NR program	<u>2/16/01</u> Date

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM

T-1139

Continuation Sheet No. 1

Glendale Farm is a well-preserved example of an intact nineteenth century farmstead that continues to function in the agricultural sector. The house at this property appears to have been built during the second half of the nineteenth century and appears to have evolved organically through time with the development of the farm. Although metal storm windows have been added over the original windows in the farm house, the building's fabric retains its integrity. The farmstead plan also appears to retain its integrity, as well as its historical circulation network and access to local roads (as illustrated in historic maps). Glendale, currently an active farm, appears to have a period of significance from ca. 1858 to 1950 based on cartographic and documentary data (1858 and 1877 maps and deeds). The property appears to be eligible for listing in the National Register of Historic Places under Criteria B (association with Henry H. Goldsborough/Goldsborough family) and C (intact farmstead with architecture representative of the nineteenth century [house] and agricultural plan and landscape). The farm also appears to be a contributing element to the proposed Goldsborough Farms Rural Historic Landscape district.

T-1139. Glendale Farm/Foster House

This property is a farmstead located south of Matthewstown Road and west of Mullet Branch Road. Entry to the property is via unsurfaced drives terminating at both roads. The farmstead covers an area of 158.2 acres and consists of a house, agricultural outbuildings, and equine riding pens. The house is a 2½-story wood frame vernacular building with a rectangular plan. The house appears to have been built in two stages. The older block is a rectangular cross-gabled two-story building on which has been built (to the southern side) a two-story frame gable roof addition. The original block, which was constructed on brick piers, has a screened entry porch with a hip roof and measures three bays by one bay. There are two external gable end brick chimneys. The western (principal façade) has symmetrical fenestration and a central cross gable with a lancet window. The house's original block has wood double hung sash (6/6 lights) windows with added metal storm windows. Clad by clapboard siding, the original block's roof has cornice returns and is clad by composition shingles.

The two-story gable roof addition to the south has a partially enclosed wrap-around hip-roof porch and a gable end door. The porch is supported by square wood posts and windows in the addition include six-light casement windows and wood double hung sash (6/6 lights) windows. The addition is clad by wood drop siding and its roof, which has cornice returns, is clad by composition shingles. According to the owner, the southern addition was once a separate building located on another part of the farmstead that was moved by a former owner and added to the main house. To the south of the house is a complex of wood frame agricultural buildings and the ruins of a rockfaced concrete block barn. The outbuildings include a gable roof stable clad by vertical wood plank siding with a corrugated metal roof and a louvered cupola ventilator. Adjacent to the stable are other wood frame buildings, including a corn crib and shed, as well as an open gable roof stable

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. T-1139

1. Name of Property (indicate preferred name)

historic Glendale Farm

other Foster House

2. Location

street and number 30485 Matthewstown Road not for publication

city, town Easton vicinity

county Talbot

3. Owner of Property (give names and mailing addresses of all owners)

name James W. Foster

street and number 30485 Matthewstown Road telephone

city, town Easton state MD zip code 21601

4. Location of Legal Description

courthouse, registry of deeds, etc. Talbot County Courthouse liber 729 folio 108

city, town Easton tax map 26 tax parcel 29 tax ID number 155734

5. Primary Location of Additional Data

- Contributing Resource in National Register District
 Contributing Resource in Local Historic District
 Determined Eligible for the National Register/Maryland Register
 Determined Ineligible for the National Register/Maryland Register
 Recorded by HABS/HAER
 Historic Structure Report or Research Report at MHT
 Other:

6. Classification

Category	Ownership	Current Function	Resource Count
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> agriculture	Contributing
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<u>7</u>
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	Noncontributing
<input type="checkbox"/> site		<input type="checkbox"/> domestic	<u> </u> buildings
<input type="checkbox"/> object		<input type="checkbox"/> education	<u> </u> sites
		<input type="checkbox"/> funerary	<u> </u> structures
		<input type="checkbox"/> government	<u> </u> objects
		<input type="checkbox"/> health care	<u>7</u> Total
		<input type="checkbox"/> industry	
		<input type="checkbox"/> landscape	
		<input checked="" type="checkbox"/> recreation/culture	
		<input type="checkbox"/> religion	
		<input type="checkbox"/> social	
		<input type="checkbox"/> transportation	
		<input type="checkbox"/> work in progress	
		<input type="checkbox"/> unknown	
		<input type="checkbox"/> vacant/not in use	
		<input type="checkbox"/> other:	

**Number of Contributing Resources
previously listed in the Inventory**

7. Description

Inventory No. T-1139

Condition

excellent deteriorated
 good ruins
 fair altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

This property is a farmstead located south of Matthewstown Road and west of Mullet Branch Road. Entry to the property is via unsurfaced drives terminating at both roads. The farmstead covers an area of 158.2 acres and consists of a house, agricultural outbuildings, and equine riding pens.

The house is a 2½-story wood frame vernacular building with a rectangular plan. The house appears to have been built in two stages. The older block is a rectangular cross-gabled two-story building on which has been built (to the southern side) a two-story frame gable roof addition. The original block, which was constructed on brick piers, has a screened entry porch with a hip roof and measures three bays by one bay. There are two external gable end brick chimneys. The western (principal façade) has symmetrical fenestration and a central cross gable with a lancet window. The house's original block has wood double hung sash (6/6 lights) windows with added metal storm windows. Clad by clapboard siding, the original block's roof has cornice returns and is clad by composition shingles.

The two-story gable roof addition to the south has a partially enclosed wrap-around hip-roof porch and a gable end door. The porch is supported by square wood posts and windows in the addition include six-light casement windows and wood double hung sash (6/6 lights) windows. The addition is clad by wood drop siding and its roof, which has cornice returns, is clad by composition shingles. According to the owner, the southern addition was once a separate building located on another part of the farmstead that was moved by a former owner and added to the main house.

To the south of the house is a complex of wood frame agricultural buildings and the ruins of a rockfaced concrete block barn. The outbuildings include a gable roof stable clad by vertical wood plank siding with a corrugated metal roof and a louvered cupola ventilator. Adjacent to the stable are other wood frame buildings, including a corn crib and shed, as well as an open gable roof stable.

8. Significance

Inventory No. T-1139

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> Agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input checked="" type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> Architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:

Specific dates ca. 1859-1950

Architect/Builder

Construction dates ca. 1859

Evaluation for:

National Register

Maryland Register

not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

This property is a large farmstead that during the nineteenth century was known as “Lark’s Discovery” (Talbot County Deed Book 85: 255). Originally owned by the Goldsborough family, the property appears to have been developed during the ownership of Henry H. Goldsborough (1859-1878). The house at the property is illustrated in the 1877 atlas map of Talbot County (Lake 1877). In 1878, Henry H. Goldsborough sold the farm to William McQuaker. According to the deed transferring the title from Goldsborough to McQuaker, the sale was for “a farm or plantation known as ‘Lark’s Discovery’ ” (Talbot County Deed Book 85: 255). The property — 190 acres — was sold several times following the 1878 transaction. By 1895, the farm appears to have been renamed “Glendale” (Talbot County Deed Book 122: 435).

Glendale Farm is a well-preserved example of an intact nineteenth century farmstead that continues to function in the agricultural sector. The house at this property appears to have been built during the second half of the nineteenth century and appears to have evolved organically through time with the development of the farm. Although metal storm windows have been added over the original windows in the farm house, the building’s fabric retains its integrity. The farmstead plan also appears to retain its integrity, as well as its historical circulation network and access to local roads (as illustrated in historic maps). Glendale, currently an active farm, appears to have a period of significance from ca. 1858 to 1950 based on cartographic and documentary data (1858 and 1877 maps and deeds). The property appears to be eligible for listing in the National Register of Historic Places under Criteria B (association with Henry H. Goldsborough/Goldsborough family) and C (intact farmstead with architecture representative of the nineteenth century [house] and agricultural plan and landscape). The farm also appears to be a contributing element to the proposed Goldsborough Farms Rural Historic Landscape district.

9. Major Bibliographical References

Inventory No. T-1139

Dilworth, William H., Map of Talbot County, Maryland with Farm Limits (1858); Lake, Griffing & Stevenson, Atlas of Talbot & Dorchester Counties, Maryland (Philadelphia, Pennsylvania, 1877); Preston, Dickson J., Talbot County: A History (Centreville, Maryland, 1983); Talbot County Deed Books; Tilghman, Oswald, History of Talbot County, Maryland (Baltimore, Maryland, 1967)

10. Geographical Data

Acreage of surveyed property 158.2 acres
Acreage of historical setting 2.0 acres
Quadrangle name Easton, MD Quadrangle scale: 1:24,000

Verbal boundary description and justification

The historic boundary for this property conforms the property limits, as delimited in the Talbot Count tax map.

11. Form Prepared by


name/title	Dr. David Rotenstein/Historian	
organization	URS/DamesMoore	date 12/2000
street & number	7101 Wisconsin Ave	telephone 301-652-2215
city or town	Bethesda	state MD

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600

T-1139



0 0.5 1.0 mile

Easton, MD Quadrangle
1:24,000 (7.5' series)





F-1139

Glendale Farm
Talbot Co., MD
David Rotenstern
November, 2000
MD SHPD

Farmstead, view to
West

1/5



T-1139

Glendale Farm
Talbot Co., MD
David Rotenstein
November, 2000
MDS/HPO

House, east elevation

2/5



T-1139

Glendale Farm

Talbot Co., MD

David Rotenstein

November, 2000

5.22-1240 522- MD SHPO

House: West elevation
and rear/side
additions

3/5



T-1139

Glendale Farm
Talbot Co., MD
David Rotenstein
November, 2000
MD SHPO

Agricultural buildings
cluster, view to
Southeast

4/5



T-1139

Glendale Farm
Talbot Co, MD
David Rotenstein
November, 2000
MD SHPO

Agricultural Buildings,
view to Northwest

5/5