

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

28 WA-HAG-
220574-1311 128 22

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

(formerly 6002)

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC MILLER HOUSE

listed on NR as

AND/OR COMMON MILLER HOUSE

Price-Miller house

2 LOCATION

STREET & NUMBER
131-135 West Washington Street

NOT FOR PUBLICATION
CONGRESSIONAL DISTRICT

CITY, TOWN
Hagerstown

VICINITY OF
Third

STATE CODE COUNTY CODE
Maryland 24 Washington 043

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	<input type="checkbox"/> PUBLIC ACQUISITION	<input type="checkbox"/> ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input checked="" type="checkbox"/> OTHER: Library, Offices

4 OWNER OF PROPERTY

NAME
Washington County Historical Society, Inc.

STREET & NUMBER
135 West Washington Street

CITY, TOWN STATE
Hagerstown VICINITY OF Maryland 21740

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.
Washington County Courthouse

STREET & NUMBER
95 West Washington Street

CITY, TOWN STATE
Hagerstown Maryland 21740

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR SURVEY RECORDS

CITY, TOWN STATE

DESCRIPTION

WA-NAG-128

CONDITION		CHECK ONE	CHECK ONE
<input checked="" type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Located at 131-135 West Washington Street in Hagerstown, Washington County, the Miller House stands on the south side of the street near the center of the block formed by Summit Avenue and Prospect Street.

The Miller House is a circa 1820's brick neoclassical style townhouse which is two and one-half storeys in height and rests on a high cut stone foundation. The house is basically rectangular in shape with an ell or wing projecting from the back or south side and a one bay addition, built circa 1915, attached to the east side. The main section of the house has a metal-covered gable roof which extends over the east addition and internal double-end chimneys on the east and west walls. The west wall extends above the roofline forming a parapet.

The principal or street facade (north side) has four bays, counting the east addition, and a narrow cornice of wood molding. The addition is slightly recessed but otherwise matches the original facade fairly well. The main entranceway is located in the west end bay and is reached by a stone, probably marble, stoop with iron railing. The basement has two windows in line with those of the upper levels in the original house and a window and door in the addition. The basement door is reached by a small flight of steps with iron railing matching that of the steps leading to the main entrance.

The first and second floor windows have double-hung wooden sashes with six-over-six lights and narrow frames molded in an ovolo or convex manner. Each of these windows have stone, probably marble, sills and lintels and are flanked by exterior shutters. The shutters on the first floor windows have three solid panels each while those of the second story windows are louvered. The basement windows have double-hung wooden sashes with three-over-three lights.

The main entranceway has a molded stone, probably marble, lintel, a rectangular transom with geometric tracery, and double wooden doors with three panels each.

The back or south side of the main section has a tripartite window on the first floor looking onto the garden. The wing, which abuts the west property line, has a shed roof sloping downward in an easterly direction. A portion of the wing is thought by many to date from an earlier period. The east wall of the wing has a series of double-hung wooden sash windows with nine-over-six lights and narrow frames with a bead.

Regarding the interior of the Miller House, the floor plan is essentially the same on the first and second floors. The main section of the house has two rooms and a passage on each level. The woodwork of the principal rooms is double-faced architrave molding with a pronounced round bead at the outer edge. Most of the doors have six raised panels. Each of the two parlors on the first floor has dark marble mantels with little embellishment other than reeding and fluting.

The most elaborate interior area is the entrance hall which has a cantilevered, rounded staircase which is open to the top floor. The staircase has open-string stairs and scroll brackets. The balustrade consists of a round handrail and round baluster and terminates in a twist around the newel. The hall is divided into two sections by an archway with fluted round pilasters. Entrance to the second story of the wing is gained by a small set of steps rising from the rounded section of the main staircase.

(See continuation sheet 1)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

MILLER HOUSE
Washington County
Maryland

7

CONTINUATION SHEET

ITEM NUMBER

PAGE 1

7. Description Continued:

The woodwork in the back wing is generally of the single-faced type, although not as wide as that in the front section. The mantel in the room now furnished as a dining room is early nineteenth century in design. Immediately behind the entrance hall is a smaller hall with an enclosed staircase on the west end and a large doorway with sidelights and a semi-elliptical transom. This doorway leads onto a porch and is at right angles to the tripartite window of the main section. Both the mantel piece and the doorway described here may not be original to the house as their decorative detailing is not quite the same as that in the rest of the wing.

An early twentieth century photograph of the house, owned by the Historical Society and identified as the house when Dr. Miller purchased it in 1912, shows that the principal or street facade has been changed little except for the alterations noted above. Another area of possible alteration is the flooring of the principal interior rooms which are covered with narrow boards.

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input checked="" type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input checked="" type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The Miller House is a circa 1820's neoclassical style townhouse which presently serves as the headquarters of the Washington County Historical Society. The house is a fine example of the type of urban dwelling that was built in western Maryland and south central Pennsylvania in the first third of the nineteenth century.

The main portion of the house is believed to have been built for William Price (17 -1868), a prominent attorney who purchased the property in 1823. (Deed Book GG, p. 173). Price twice served in the Maryland Legislature and was appointed a U.S. District Attorney by President Lincoln. (Williams, p. 426.) In 1825, he was elected to the State Senate from Washington County. Forty years later, he returned to the Legislature, representing the Baltimore area. A native of Washington County, Price moved to Cumberland, Allegany County, about 1842 and later to Baltimore. He was the father of the noted late nineteenth century architect Bruce Price (1845-1903) and the grandfather of Emily Price Post (1873-1960), the late author and etiquette authority.

Price sold the house in 1844 to Alexander Neil, Jr. (1808-c. 1863), a lawyer and President of the Hagerstown Bank. (Deed Book O.H.W. No. 2, p. 491.) Subsequently, the property was acquired by Neil's son, Alexander Neil, III (1844-1911), who was a member of the Maryland House of Delegates in 1870 and served as auditor of the Washington County Court in 1876. (Scharf, p. 1043.)

The house was enlarged in about 1915 when a one-bay addition was attached to the east end of the main portion. The addition was built to house the medical offices of Victor D. Miller, Jr. (1875-1955), a prominent physician who purchased the property in 1912 from the heirs of Alexander Neil, III. (Deed Book 138, p. 102). Miller is also responsible for restoring the original front doors which had been replaced in the late nineteenth century.

The Washington County Historical Society acquired the house in 1966 from the Miller family through donation and purchase. Named in honor of Dr. Miller, the Miller House is now used by the Society for its office, library, and museum.

The house stands on the westerly half of Lot No. 91 of the original plat of Hagerstown. Peter Bell purchased the half-lot in 1802 for £300. (Deed Book O, p. 481.) Bell and his sons operated a pottery on this site well into the first quarter of the 1800's when the property was sold for payment of debts. It is traditionally said that a section of the Bell House is included in the present back wing of the Miller House.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

MILLER HOUSE
Bibliography

CONTINUATION SHEET

ITEM NUMBER

9

PAGE

2

9. Major Bibliographical References, continued

- Washington County Historical Society, files. Miller House,
Hagerstown, Maryland.
Washington County Land Records, Courthouse, Hagerstown, Maryland.
Williams, Thomas J. C. A History of Washington County, Maryland.
2 vols. Hagerstown, Maryland: John M Runk and L.R.
Titworth, 1906.

ON NATL REG

WA-HAG-128
2205284303
1

HISTORIC SITE
SURVEY INVENTORY

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM
for the
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

1. NAME				
COMMON: Miller House				
AND/OR HISTORIC:				
2. LOCATION				
STREET AND NUMBER: 131-135 West Washington Street				
CITY OR TOWN: Hagerstown				
STATE Maryland			COUNTY: Washington	
3. CLASSIFICATION				
CATEGORY (Check One)		OWNERSHIP		STATUS
<input type="checkbox"/> District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object		<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both		<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
ACCESSIBLE TO THE PUBLIC				
Yes:				
<input checked="" type="checkbox"/> Restricted				
<input type="checkbox"/> Unrestricted				
<input type="checkbox"/> No				
PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input type="checkbox"/> Private Residence	<input checked="" type="checkbox"/> Other (Specify)	
<input type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious	library	
<input type="checkbox"/> Entertainment	<input checked="" type="checkbox"/> Museum	<input type="checkbox"/> Scientific	offices	
4. OWNER OF PROPERTY				
OWNER'S NAME: Washington County Historical Society, Inc.				
STREET AND NUMBER: 135 West Washington Street				
CITY OR TOWN: Hagerstown			STATE: Maryland	21740
5. LOCATION OF LEGAL DESCRIPTION				
COURTHOUSE, REGISTRY OF DEEDS, ETC: Washington County Courthouse				
STREET AND NUMBER: 95 West Washington Street				
CITY OR TOWN: Hagerstown			STATE: Maryland	
Title Reference of Current Deed (Book & Pg. #): 437-29				
6. REPRESENTATION IN EXISTING SURVEYS				
TITLE OF SURVEY: Maryland Historical Trust Inventory, No. W-6002				
DATE OF SURVEY: <input type="checkbox"/> Federal <input checked="" type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local				
DEPOSITORY FOR SURVEY RECORDS: Maryland Historical Trust				
STREET AND NUMBER: Shaw House, 21 State Circle				
CITY OR TOWN: Annapolis			STATE: Maryland	

Mr. Ralph Donnelly
President
Mrs. Wanda Allenback
Executive Secretary
Please notify if accepted:

7. DESCRIPTION

CONDITION	(Check One)					
	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

Located at 131-135 West Washington Street in Hagerstown, Washington County, the Miller House stands on the south side of the street near the center of the block formed by Summit Avenue and Prospect Street.

The Miller House is a circa 1820s brick neoclassical style town-house which is two and a half stories in height and rests on a high cut stone foundation. The house is basically rectangular in shape with an ell or wing projecting from the back or south side and a one bay addition, built circa 1915, attached to the east side. The main section of the house has a metal-covered gable roof, which extends over the east addition, and internal double-end chimneys on the east and west walls. The west wall extends above the roofline forming a parapet.

The principal or street facade (north side) has four bays, counting the east addition, and a narrow cornice of wood molding. The addition is slightly recessed but otherwise matches the original facade fairly well. The main entranceway is located in the west end bay and is reached by a stone, probably marble, stoop with iron railing. The basement has two windows in line with those of the upper levels in the original house and a window and door in the addition. The basement door is reached by a small flight of steps with iron railing that matches that of the steps leading to the main entrance.

The first and second floor windows have double-hung wooden sashes with six-over-six lights and narrow frames molded in an ovolo or convex manner. Each of these windows have stone, probably marble, sills and lintels and are flanked by exterior shutters. The shutters on the first floor windows have three solid panels each while those of the second story windows are louvered. The basement windows have double-hung wooden sashes with three-over-three lights.

The main entranceway has a molded stone, probably marble, lintel, a rectangular transom with geometric tracery, and double wooden doors with three panels each.

The back or south side of the main section has a tripartite window on the first floor looking on to the garden. The wing, which abuts the west property line, has a shed roof sloping downward in an easterly direction. A portion of the wing is thought by many to date from an earlier period. The east wall of the wing has a series of double-hung wooden sash windows with nine-over-six lights and narrow frames with a bead.

Regarding the interior of the Miller House, the floor plan is essentially the same on the first and second floors. The main section of the house has two rooms and a passage on each level. The woodwork of the principal rooms is ~~entablature~~ molding with a pronounced round bead at the outer edge. Most of the doors have six raised panels. Each of the two parlors on the first floor have dark marble mantels with little embellishment other than reeding and fluting.

*double-faced architecture

SEE CONTINUATION SHEET

SEE INSTRUCTIONS

MARYLAND HISTORICAL TRUST WORKSHEET

CONTINUATION SHEET

Miller House
131-135 West Washington Street
Hagerstown, Maryland 21740

#7. DESCRIPTION continued

The most elaborate interior area is the entrance hall which has a cantilevered, rounded staircase which is open to the top floor. The staircase has open-string stairs and scroll brackets. The balustrade consists of a round handrail and round balusters*. The hall is divided into two sections by an archway with fluted round pilasters. Entrance to the second story of the wing is gained by a small set of steps rising from the rounded section of the main staircase.

The woodwork in the back wing is generally of the ^{single-faced} ~~entablature~~ type, although not as wide as that in front section. The mantel in the room now furnished as a dining room is early nineteenth century in design. Immediately behind the entrance hall is a smaller hall with an enclosed staircase on the west end and a large doorway with sidelights and a semi-elliptical transom. This doorway leads onto a porch and is at right angles to the tripartite window of the main section. Both the mantel piece and the doorway described here may not be original to the house because ^{as their decorative detailing is that in} ~~both do not have quite the same as~~ the rest of the decorative detailing of the wing.

An early twentieth century photograph of the house, ^{owned by} ~~in the~~ possession of the Historical Society and identified as ~~being the~~ appearance of the house when Dr. Miller purchased it in 1912, shows that the principal or street facade has ^{been} ~~changed~~ little except for the alterations noted above. Another area of possible alteration is the flooring of the principal interior rooms which are covered with narrow boards.

* and terminates in a twist around the newel.

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

<input type="checkbox"/> Pre-Columbian	<input type="checkbox"/> 16th Century	<input type="checkbox"/> 18th Century	<input type="checkbox"/> 20th Century
<input type="checkbox"/> 15th Century	<input type="checkbox"/> 17th Century	<input checked="" type="checkbox"/> 19th Century	

SPECIFIC DATE(S) (If Applicable and Known) circa 1820s

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

<input type="checkbox"/> Aboriginal	<input checked="" type="checkbox"/> Education	<input checked="" type="checkbox"/> Political	<input type="checkbox"/> Urban Planning
<input type="checkbox"/> Prehistoric	<input type="checkbox"/> Engineering	<input type="checkbox"/> Religion/Philosophy	<input type="checkbox"/> Other (Specify) _____
<input type="checkbox"/> Historic	<input type="checkbox"/> Industry	<input type="checkbox"/> Science	_____
<input type="checkbox"/> Agriculture	<input type="checkbox"/> Invention	<input type="checkbox"/> Sculpture	_____
<input checked="" type="checkbox"/> Architecture	<input type="checkbox"/> Landscape Architecture	<input checked="" type="checkbox"/> Social/Humanitarian	_____
<input type="checkbox"/> Art	<input type="checkbox"/> Literature	<input type="checkbox"/> Theater	_____
<input type="checkbox"/> Commerce	<input type="checkbox"/> Military	<input type="checkbox"/> Transportation	_____
<input type="checkbox"/> Communications	<input type="checkbox"/> Music		
<input type="checkbox"/> Conservation			

STATEMENT OF SIGNIFICANCE

The Miller House is a circa 1820s neoclassical style townhouse which presently serves as the headquarters of the Washington County Historical Society. The house is a fine example of the type of urban dwelling that was being built in western Maryland and southcentral Pennsylvania in the first third of the nineteenth century.

The main portion of the house is believed to have been built for William Price (17 -1868), a prominent attorney who purchased the property in 1823. (Deed Book GG, p. 173.) Price twice served in the Maryland Legislature and was appointed a U. S. District Attorney by President Lincoln. (Williams, p. 426.) In 1825, he was elected to the State Senate from Washington County. Forty years later, he returned to the Legislature, representing the Baltimore area. A native of Washington County, Price moved to Cumberland, Allegany County, about 1842 and later to Baltimore. He was the father of the noted late nineteenth century architect Bruce Price (1845-1903) and the grandfather of Emily Price Post (1873-1960), the late author and etiquette authority.

Price sold the house in 1844 to Alexander Neil, Jr., (1808-c.1863), a lawyer and President of the Hagerstown Bank. (Deed Book O.H.W. No. 2, p. 491.) Subsequently, the property was acquired by Neil's son, Alexander Neil, III, (1844-1911), who was a member of the Maryland House of Delegates in 1870 and served as auditor of the Washington County Court in 1876. (Scharf, p. 1043.)

The house was enlargedⁿ about 1915 when a one bay addition was attached to the east end of the main portion. The addition was built to house the medical offices of Victor D. Miller, Jr., (1875-1955), a prominent physician who purchased the property in 1912 from the heirs of Alexander Neil, III. (Deed Book 138, p. 102.) Miller is also responsible for restoring the original front doors which ^{had been} were replaced in the late nineteenth century.

The Washington County Historical Society acquired the house in 1966 from the Miller family through donation and purchase. Named in honor of Dr. Miller, the Miller House is now used by the Society for its office, library, and museum.

SEE CONTINUATION SHEET

SEE INSTRUCTIONS

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Graybill, Samuel H., Jr. "Bruce Price, American Architect, 1845-1903," dissertation. Yale University, New Haven, Connecticut, 1957.

Scharf, J. Thomas. History of Western Maryland, 2 vols. Philadelphia: Louis H. Everts, 1882.

Thomas, James W. and T. J. C. Williams. History of Allegany County, Maryland, 2 vols. n.p.: Titsworth Publishing Company, 1928.

SEE CONTINUATION SHEET

10 GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 60' x 200'

Acreage Justification:

The property measures approximately 60' x 200'.

SEE INSTRUCTIONS

11 FORM PREPARED BY

NAME AND TITLE: Ronald L. Andrews, Historic Preservation Consultant

ORGANIZATION: City of Hagerstown DATE: _____

STREET AND NUMBER: City Hall

CITY OR TOWN: Hagerstown STATE: Maryland 21740

12 State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National State Local

Signature _____

MARYLAND HISTORICAL TRUST WORKSHEET

CONTINUATION SHEET

Miller House
131-135 West Washington Street
Hagerstown, Maryland 21740

#8. SIGNIFICANCE continued

The house stands on the westerly half of Lot No. 91 of the original plat of Hagerstown. Peter Bell purchased the half-lot in 1802 for £300. (Deed Book O, p. 481.) Bell and his sons operated a pottery on this site well into the first quarter of the 1800s when the property was sold for payment of debts. It is traditionally said that a section of the Bell house is included in the present back wing of the Miller House.

#9. MAJOR BIBLIOGRAPHICAL REFERENCES continued

Washington County Historical Society, files. Miller House, Hagerstown, Maryland.

Washington County Land Records, Courthouse, Hagerstown, Maryland.

Williams, Thomas J. C. A History of Washington County, Maryland, 2 vols. Hagerstown, Md.: John M. Runk and L. R. Titsworth, 1906.

WA-NAG-128

WA - VI - 2
Hagerstown -

9/29/68 AP-

Miller House

(128)

135 W. Washington St. Hagerstown -

Wing added by Victor Miller Senior 1913.

Became headquarters for the WA Cty Historical Soc.

1967 or 1966 - about 2 years ago.

opened for season Sept 29/68 - AP attended.

Pearl clock collection.

Doll collection.

C & O canal pictures.

Civil War collection.

Photos from Harpers Weekly 1862

* Brady photos -

color photo - 4833, 4810

Castons - on Morgan

WA-NAG-128

135 Wash - St.
Hagerstown -

9/30/68 AP

See John Potts
Wa-Obz Museum -

Leon Morgan's house (Shaysburg?)
Chaplain (Chap-lin) Doubt's hill & Beawa Creek

Photos

Lock House Dam 5 (another marked 1910)

East End C&O

Pennipels's Lock

Cushwa's Wharf 1880-1888

Schaefer Lock 52, Hancock, C&O - (Bodine)

model of C&O canal -

* Brady photo of Barracks at Fort Carroll
Maryland Heights, Brady

map - 1879

Hag & Whsept
Shows houses -

see
Harold Hoffner
Lawyer Hagerstown
for copy

Bloody Lane photos -

Hagerstown Bicycle Club - 1885-90
July 5th 1886

wring on house 1913 by Vic Miller

Sharpsburg
Map of Battleground of Antietam
prepared by Lt Wm H. Wilcox
shows bldgs in Sharpsburg -

Miller House
135 Wash... St
Hagerstown
9/29/68
WA-NAG-128

*in passage
way at
Miller House.*
New York Illustrated News - 10/11/1862
The Town Hall -
Massaponax Bridge - Oct 4/1862
in Frank Leslie's Illustrated Newspaper.

Frederick City - air view of
Harper's WKly Sept 27, 1862
The Soldier in Our Civil War pg 398

Boonsboro The Invasion of Md, Antietam Sept 1862
Harper's WKly, Oct 25, 1862 pg 395

Middletown

Sugar loaf Mt.

Williamsport

Harper's WKly July 6, 1861 pg 429

National Road

Harper's WKly - 1862

Mrs. Harold Bester -
 (cousin of Mrs. Bowman -

Early View of H & Miller House - Hagerstown -
 E. Sachse (see Harold Hoffman)

Plan of Hagerstown 1850 (see Harold Hoffman)
 Printed at T. Swiclain, Phila -

* Litho - W. Kreis, 111 or 191 Walnut St. Phila
 shows location of bldgs -

~~Frank Kirk, 9-10. 9/30/68 AP. 9¹⁵ - 11~~
~~Page 11 - at Waeport -~~

Mrs. Hensley - WSD - 9 -

2nd floor Original drawings of Latrobe's 2nd Wae. Ct. C.H.

Dr. Frederick Dorey, b 1775 - d 1858
 3 generations lived in Hagerstown


Sheraton mirror, gift from W^m C Newman picture on it?

Hagerstown letters - Lat mps.

Mrs. Bowman & change


site: Miller House
 131-135 West Washington Street
 Hagerstown
 Washington County, Maryland

map: Tax Map No. 32
 Hagerstown, Washington Co., Maryland
 revised to October, 1974
 scale 1"=100'



site: Miller House
131-135 West Washington Street
Hagerstown
Washington County, Maryland

map: City of Hagerstown, Maryland
Engineering Department
revised 1972
scale 1:1200



WA-HAG-178



UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

821-544-54

**NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM**

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- ENCLOSE WITH PHOTOGRAPH

1 NAME

HISTORIC Miller House

AND/OR COMMON Miller House

2 LOCATION

CITY, TOWN Hagerstown VICINITY OF Maryland STATE COUNTY Washington

3 PHOTO REFERENCE

PHOTO CREDIT Ronald, Andrews DATE OF PHOTO July 1975

NEGATIVE FILED AT Maryland Historical Trust, Annapolis, Maryland

4 IDENTIFICATION

DESCRIBE VIEW, DIRECTION, ETC. IF DISTRICT, GIVE BUILDING NAME & STREET north elevation

PHOTO NO. 2



WA-ANG-128

WA-NAG-128

Form No. 10-301a
(Rev. 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- ENCLOSE WITH PHOTOGRAPH

1 NAME
HISTORIC Miller House

AND/OR COMMON Miller House

2 LOCATION			
CITY, TOWN Hagerstown	VICINITY OF	STATE Maryland	COUNTY Washington

3 PHOTO REFERENCE	
PHOTO CREDIT Ronald Andrews	DATE OF PHOTO July 1975
NEGATIVE FILED AT Maryland Historical Trust, Annapolis, Maryland	

4 IDENTIFICATION	
DESCRIBE VIEW, DIRECTION, ETC. IF DISTRICT, GIVE BUILDING NAME & STREET	PHOTO NO.
entrance hall, first floor	1



WA-HAG-128

Miller House

131-135 West Washington St.

Hagerstown

Washington Co.

Maryland

north elevation

July, 1935

Ronald L. Andrews



WA-HAG-128
entrance hall, first floor
Miller House
131-135 West Washington St.
Hagerstown
Washington Co.
Maryland
July, 1975

Ronald L. Andrews